



District Address: District 4 Construction Office, located at 3400 West Commercial Blvd. Fort Lauderdale, FL 33309

District Phone: (954) 777-4130

Proposal: T4585  
Project: 435337-1-52-01  
Letting Date: 8/25/2021  
Location: CENTRAL OFFICE  
Description: SR 9 (I-95) AT ST LUCIE WEST BLVD

---

Question: 34752: The "Detail of Asphalt Base Curb Pad" indicates that the travel lanes are receiving asphalt base material (OBG 9) but there is not a note of this under the Typical Section for OBG 09 and it isn't called out on the SQ sheets (except at one cross over).

Posted: 7/7/2021 2:58:35 PM

Can the Department clarify if the roadway travel lanes are to receive Type B-12.5 asphalt base for OBG 09?

---

Answer: The OBG 9 is the base material to be used for the roadway. It will be the contractors option to use B-12.5 or any of the other OBG-9 options per the pavement design manual. For the sake of ease to the contractor, the use of homogeneous base material under the new curb and gutter and roadway areas will be allowed.

Status: ANSWER PUBLISHED

Posted: 7/9/2021 1:36:30 PM

The B-12.5 is noted to be used in the roadway in an area that needs to be quickly opened to traffic in an intersection. The roadway travel lanes will not require the B-12.5 option of the OBG-9, this will be at the contractors option to use if they so choose.

---

Question: 34913: Optional materials table shows (RCP) Steel-Reinforced , CL I as the plotted pipe, confirming that the other pipe types listed are viable for use on the project as alternate materials.

Posted: 7/16/2021 10:07:38 AM

---

Answer: All of the pipes shown on the optional materials tabulation sheet are acceptable to be used for this project.

Status: ANSWER PUBLISHED

Posted: 7/16/2021 2:05:23 PM

---

Question: 35150: Can the department please provide the multi column sign data for the 700-2-15 Multi Post, 51-100SF pay item? The information for the other multi post pay items was provided for on page S-31, but not for these six signs.

Posted: 8/2/2021 11:42:43 AM

---

Answer: These six signs are for the food and lodging (blue with local businesses). The size of each of these six signs are 96"x96". The names of the companies will be provided before the project starts.

Status: ANSWER PUBLISHED

Posted: 8/2/2021 3:01:29 PM

---

Question: 35184: In response to Q&A #35150, can the department provide the size and height of the post required for pay item 700-2-15? Posted: 8/5/2021 11:49:09 AM

---

Answer: The 3D model has been provided in the bid documents for the bidder to determine max post sizes required. Status: ANSWER PUBLISHED  
Posted: 8/12/2021 12:11:27 PM

---

Question: 35271: Can the Department provide cross sections for Temporary Ramp F? Posted: 8/16/2021 3:12:58 PM

---

Answer: The cross sections for Temporary Ramp F can be found in two different CADD files. The CADD files are MODLRD09 and RDXSRD40. Status: ANSWER PUBLISHED  
Posted: 8/18/2021 7:24:51 AM

---

Question: 35291: Can the Department please provide roadway corings for St. Lucie West Blvd and the ramps? Posted: 8/18/2021 8:52:53 AM

---

Answer: Here is the Flexible Pavement design report Status: ANSWER PUBLISHED  
Posted: 8/18/2021 11:32:18 AM

---

Document: 12191079: FLEXIBLE PAVEMENT DESIGN REPORT ST LUCIE WEST BLVD Final.pdf

FLEXIBLE PAVEMENT DESIGN REPORT ST LUCIE WEST BLVD Final.pdf