



Bid Questions and Answers Report

Date & Time: 12/8/2021 9:09:09 AM

District Address: District 4 Construction Office, located at 3400 West Commercial Blvd. Fort Lauderdale, FL 33309

District Phone: (954) 777-4130

Proposal: T4566

Project: 439761-1-52-01

Letting Date: 12/8/2021

Location: CENTRAL OFFICE

Description: SR 9 (I-95) NB AND SB OFF-RAMPS

Question: 35810: Will CAD files be provided for this Project? Posted: 10/14/2021 10:09:25 AM

Answer: FDOT uploaded the CAD files as requested Status: ANSWER PUBLISHED
Posted: 10/15/2021 12:41:13 PM

Answer: FDOT uploaded the CADD files to
\\codata\shares\CO\ProjRev\Public\DistrictPost Status: ANSWER VOIDED
Posted: 10/14/2021 3:12:53 PM

Question: 35811: Please provide Lighting Analysis Design Report in .PDF format. Posted: 10/14/2021 10:10:43 AM

Answer: Attached is the lighting Analysis Design Report in PDF Status: ANSWER PUBLISHED
Posted: 10/14/2021 3:15:38 PM

Document: 12454527: 439761-1 Lighting Design Analysis Report.pdf

439761-1 Lighting Design Analysis Report

Question: 36165: Can FDOT check the FC 12.5C quantity, coming up with about 350 more tons than FDOT. Posted: 11/17/2021 9:44:30 AM

Answer: The Department verified the quantity and it is correct as shown in the plans. Status: ANSWER PUBLISHED
Posted: 11/18/2021 8:18:20 AM

Question: 36171: Can FDOT confirm that there is only .47 tons of overbuild on Gatlin Blvd? Posted: 11/17/2021 10:20:05 AM

Answer: The Department verified only .47 tons of overbuild on Gatlin Blvd is required. Since this overbuild is only in 7.25 SY, the Department will allow the contractor to place .47 tons while placing FC. If the contractor elects to place this overbuild with FC, payment for overbuild shall be .47 tons and will be done under structural pay item. This amount will be rounded to hundred place (ie .47 tons). Status: ANSWER PUBLISHED
Posted: 11/18/2021 8:09:49 AM

Question: 36182: On sheet 12 and 13 the detail of the asphalt curb pad refers to the base as asphalt base but the typical just call for OBG 09, can DOT please clarify if the OGB 09 is asphalt base? Posted: 11/17/2021 3:57:53 PM

Answer: Asphalt Base curb pad is required to be used if the Contractor elects to do Black Base as an Optional Base. The cost of asphalt curb pad is included in the cost of the curb. Status: ANSWER PUBLISHED
Posted: 11/18/2021 8:39:24 AM

Question: 36190: Can the Department provide the Borings Information referenced on S-18 Posted: 11/18/2021 2:28:57 PM

Answer: See attached Status: ANSWER PUBLISHED
Posted: 11/18/2021 3:58:15 PM

Document: 12617574: MiscStructuresGeotechReport.pdf

MiscStructuresGeotechReport.pdf

Question: 36206: In reference to question 36182 just to clarify, if we do FDOT rock base then does the curb pad still have to be asphalt? Posted: 11/22/2021 10:49:12 AM

Answer: If the contractor uses rock base, no asphalt curb pad is required. Status: ANSWER PUBLISHED
Posted: 11/22/2021 11:30:52 AM