



Bid Questions and Answers Report

Date & Time:

1/27/2021 8:35:24 AM

District Address: District 7 Construction Office, located at 11201 N McKinley, Tampa, FL 33612

District Phone: (813) 975-6285

Proposal: T7460

Project: 436041-1-52-01

Letting Date: 1/27/2021

Localtion: CENTRAL OFFICE

Description: SR 60

---

Question: 31962: Typical Section Details Sheet indicates 2.25" milling where removal of existing concrete median and overbuild area. There is no bid item for 2.25" milling. Posted: 1/6/2021 9:31:59 AM

---

Answer: The concrete median removal detail and overbuild detail should follow the recommendation depicted in the typical section. The Designer's intent was for the Contractor to remove the friction course before placing the separator or placing the overbuild on the existing pavement. The Type SP structural course label under the traffic separator is not needed and not quantified in the plans. A plan revision addendum will follow, depicting these corrections. Status: ANSWER PUBLISHED  
Posted: 1/7/2021 4:15:49 PM

---

Question: 32299: On pay item 700-4-620 Overhead Static Sign Structure Remove Span. Is it only the span to be removed and disregard the foundations. Posted: 1/20/2021 2:42:06 PM

---

Answer: The Method of Measurement under Section 700 (Highway Signing) of the FDOT Standard Specifications include the removal of supports and footings (foundations). Status: ANSWER PUBLISHED  
Posted: 1/21/2021 3:23:22 PM

---

Question: 32339: Do the lane closure restrictions listed on sheet 45 under Lane Closure Notes apply to all the lane closures shown on sheets 46, 47A, 48, 49, 50, 51, 54, 55? Are any of the lanes closures shown allowed to be left in place for an extended period? Posted: 1/21/2021 5:38:13 PM

---

Answer: Sheet 45 includes the lane closure hour restrictions for SR 60. General Note 2 depicts coordination with Hillsborough County for their road closures requirements. If the County issues an extended period road closure permit, then the auxiliary left turn lane shown in the preceding drawings will need to be closed as shown on sheet 47A and 51. Status: ANSWER PUBLISHED  
Posted: 1/22/2021 5:08:25 PM

---

Question: 32340: Certain activities will impact all lanes of traffic on SR60 in both directions. For example, removal of the existing overhead sign truss near STA 371+60, removal of the existing diagonal span wire at Grand Regency Blvd, and installation of the two new span wires east and west of Grand Regency Blvd. Are there any project specific requirements or limitations related to these types of activities?

Posted: 1/21/2021 5:44:19 PM

---

Answer: The specific requirements for removing the structures are included in FDOT Standard Plans Index 102-600 (Overhead work), as well as other Standard Plan Indexes, FDOT Standard Specifications, and the contract documents.

Status: ANSWER PUBLISHED

Posted: 1/22/2021 5:05:45 PM