



Bid Questions and Answers Report

Date & Time:

5/26/2021 8:40:16 AM

District Address: District 4 Construction Office, located at 3400 West Commercial Blvd. Fort Lauderdale, FL 33309

District Phone: (954) 777-4130

Proposal: T4563

Project: 436196-1-52-01

Letting Date: 5/26/2021

Localtion: CENTRAL OFFICE

Description: SW 40TH AVE

Question: 33831: what type of sod will be implemented on this project? Posted: 4/29/2021 7:58:39 AM

Answer: St. Augustine Sod Status: ANSWER PUBLISHED

Posted: 4/29/2021 8:48:49 AM

Question: 33937: There are no pay items 0102-104 & 0102-107-1, will the electrical contractor be responsible for these activities under another pay item? Posted: 5/5/2021 7:55:38 AM

Answer: These pay items will be added prior to letting. Status: ANSWER PUBLISHED

Posted: 5/5/2021 10:41:11 AM

Question: 34069: how will the asphalt driveway items be paid there are no pay items for 1.5" structural course as noted on sheet 6 of the contract plans. Posted: 5/13/2021 8:35:16 AM

Answer: the asphalt base for the driveways is included in item 0286-2. The structural asphalt concrete material for the driveways is included in item 0334-1-12. Status: ANSWER PUBLISHED

Posted: 5/13/2021 4:11:06 PM

Question: 34070: how will the 4" conc ditch pavement items shown on the roadway plans be paid? Posted: 5/13/2021 8:39:45 AM

| | | |
|-----------|---|-------------------------------|
| Answer: | the concrete ditch pavement is included in pay item number 0524-1-2. | Status: ANSWER PUBLISHED |
| | | Posted: 5/13/2021 4:11:36 PM |
| Question: | 34074: Does optional base group 4 have to be type b12.5? if not, could you identify the area for the driveways which do call for asphalt only? | Posted: 5/13/2021 9:35:52 AM |
| Answer: | Optional Base Group 4 for the roadway reconstruction areas must be Type B-12.5. The location of the asphalt driveway base material is shown on plan sheet Q-19. | Status: ANSWER PUBLISHED |
| | | Posted: 5/13/2021 4:12:09 PM |
| Question: | 34075: why does the reconstruction subtitle below the typical section on sheet 6 identify OBG 4, if the typical states the existing base is to remain in the reconstruction area? | Posted: 5/13/2021 9:40:58 AM |
| Answer: | The existing roadway base material must be removed and replaced in the reconstruction areas | Status: ANSWER PUBLISHED |
| | | Posted: 5/13/2021 5:28:45 PM |
| Answer: | The existing roadway base material must be removed and replaced in the reconstruction areas. A plan revision will be issued prior to letting. | Status: ANSWER VOIDED |
| | | Posted: 5/13/2021 4:12:50 PM |
| Question: | 34078: sheet SQ-1, pay item notes identify pay item 443-70-3 to include utility pipe sleeves through french drains, yet this pay item does not exist in the contract documents. Please advise. | Posted: 5/13/2021 10:58:04 AM |
| Answer: | The pay item footnote on sheet SQ-1 should reference item number 443-70-4. A plan revision will be issue prior to letting. | Status: ANSWER PUBLISHED |
| | | Posted: 5/13/2021 4:13:25 PM |
| Question: | 34157: the plans do not call for the removal of the existing fence shown on the plans in conflict with the proposed work, how will this work be addressed? | Posted: 5/17/2021 9:04:04 AM |
| Answer: | Please note that all fences encroaching into the right way and are in the way of construction are to be removed/relocated by the property owners as the city coordinated with them prior to start of construction | Status: ANSWER PUBLISHED |
| | | Posted: 5/17/2021 10:27:52 AM |

| | | | |
|-----------|---|---------|-----------------------|
| Question: | 34160: could you please denote what and where pay item no. 0425 11, modify existing drainage structure, scope of work entails? | Posted: | 5/17/2021 9:23:27 AM |
| Answer: | Pay item 425-11 was added to the plans to cover structures E-2,E-6,E-9 as detailed in the drainage cross section sheets 39, 43,44 | Status: | ANSWER PUBLISHED |
| | | Posted: | 5/17/2021 9:38:11 AM |
| Question: | 34161: could you please provide detail for rubble riprap? | Posted: | 5/17/2021 9:40:30 AM |
| Answer: | sheets W-3 of the structural plans provides detail for rubble riprap. | Status: | ANSWER PUBLISHED |
| | | Posted: | 5/17/2021 12:20:27 PM |
| Question: | 34172: how will the 9 lf of guiderail (steel) shown on the drainage structure sheets be paid? | Posted: | 5/17/2021 1:59:17 PM |
| Answer: | See SQ-20, AND SUMMARY OF PAY ITMES, SHEET 3. Quantity of Guiderail is shown on both pages | Status: | ANSWER PUBLISHED |
| | | Posted: | 5/17/2021 2:39:07 PM |
| Question: | 34234: could you please provide the revised Engineer's estimate for this project including the added items through addendum no. 1 & 2? | Posted: | 5/19/2021 12:47:31 PM |
| Answer: | The Department is not able to provide this request. | Status: | ANSWER PUBLISHED |
| | | Posted: | 5/20/2021 5:56:50 PM |
| Question: | 34255: addendum no. 3, Roadway Plan Sheet No. 6, addresses the removal of the existing base to be removed in reconstruction area. is this quantity included in the regular excavation item? | Posted: | 5/20/2021 7:43:06 AM |
| Answer: | The removal of the existing asphalt pavement and base is include in pay item 110-1-1 Clearing and Grubbing as per section 110-2 of the Standard Specifications. | Status: | ANSWER PUBLISHED |
| | | Posted: | 5/20/2021 5:55:24 PM |
| Question: | 34256: in addendum no. 3, sheet 7, pay item no. 443-70-4 you identify a pipe sleeve thru french drains per index 443-001, do you consider a pipe sleeve the same as a coupling? there is no pipe sleeve detail in the standard plans index 443-001. | Posted: | 5/20/2021 7:46:46 AM |

Answer: A pipe sleeve is not the same as a coupling. Sheet 2 of 3 of Index 443-001 depicts the pipe sleeve. Note 5 of the same index sheet lists the pipe sleeve materials.

Status: ANSWER PUBLISHED

Posted: 5/20/2021 5:55:43 PM