



Bid Questions and Answers Report

Date & Time:

5/26/2021 8:42:22 AM

District Address: District 4 Construction Office, located at 3400 West Commercial Blvd. Fort Lauderdale, FL 33309

District Phone: (954) 777-4130

Proposal: T4580

Project: 439929-1-52-01

Letting Date: 5/26/2021

Localtion: CENTRAL OFFICE

Description: SR 25 (US 27)

Question: 33996: Per sheet SQ-1, pay item note 285701 states: OPTIONAL BASE GROUP 1 SHALL NOT BE SUBSTITUTED WITH RAP BASE. Our interpretation of the specification is that RAP base is not a substituted material, it is a specified optional material. Please confirm the use of RAP base is an acceptable material to use for the 285701 pay item on this project. Posted: 5/10/2021 9:45:26 AM

Answer: US-27 is considered a limited access facility in this area and as such, RAP material is not permitted. Also, since the RAP has no structural number, the use of RAP will not meet the required structural number for the shoulder pavement design. Status: ANSWER PUBLISHED
Posted: 5/11/2021 1:04:29 PM

Answer: US-27 is considered a limited access facility in this area and as such, RAP material is not permitted Status: ANSWER VOIDED
Posted: 5/11/2021 9:36:09 AM

Question: 34167: Will railroad insurance be required for this project? Posted: 5/17/2021 12:17:25 PM

Answer: yes, Per the FDOT Specs Section 7-13.3, Railroad Insurance is required when the Contract includes work or operations in the vicinity of the railroad right-of-way. Status: ANSWER PUBLISHED
Posted: 5/17/2021 1:38:42 PM

Question: 34174: Please clarify limits of Geogrid since there is a discrepancy between the Roadway Soil Survey and the Geogrid Reinforcement Installation Details Typical Section plan sheet 30. Posted: 5/17/2021 2:58:42 PM

Answer: The limits provided in the Geotechnical Roadway Soil Survey Report (Pages 13-14) should be used as the limits of the Geogrid. Status: ANSWER PUBLISHED
Posted: 5/17/2021 3:36:55 PM

Question:	34175: For Subsoil excavation, please confirm that the material is to be disposed per Standard Specification Section 120-5 Disposal of Surplus and Unsuitable Material.	Posted:	5/17/2021 2:59:29 PM
Answer:	Yes, confirmed.	Status:	ANSWER PUBLISHED
		Posted:	5/17/2021 3:37:47 PM
Question:	34232: Plan Sheet B1-11 has a note regarding one of the existing overhead cables on the west side of the bridge, specifically "Exist. Overhead Cable (To Remain) ??????" Please clarify what the question marks are for and it would appear based on the drawing that that line will need to be removed to allow for pile installation.	Posted:	5/19/2021 11:45:56 AM
Answer:	The existing overhead fiber optic cables are located 60-ft from the existing bridge and will not be impacted due to the bridge widening. The existing overhead fiber optic cables will remain as indicated in the plan sheet. No relocation is required during construction. The utility lines shown in sheet B1-11 will be revised to show the actual locations as shown in Roadway Plans Sheet 66. The question marks on Sheet B1-11 will be omitted.	Status:	ANSWER PUBLISHED
		Posted:	5/21/2021 11:40:43 AM
Answer:	The existing overhead fiber optic cables are located 60-ft from the existing bridge and will not be impacted due to the bridge widening. The existing overhead fiber optic cables will remain as indicated in the plan sheet. No relocation is required during construction. The utility lines shown in sheet B1-11 will be revised to show the actual locations as shown in Roadway Plans Sheet 66. The question marks on Sheet B1-11 will be omitted.	Status:	ANSWER VOIDED
		Posted:	5/21/2021 11:32:19 AM
Question:	34233: Plan Sheet B1-11 has a note regarding the existing overhead cables on the west side of the bridge as "Exist. Overhead Cable (To Remain) ??????" The overhead line needs to be removed to allow for pile installation. Please clarify what the question marks are for and when the overhead line will be relocated before construction?	Posted:	5/19/2021 12:14:29 PM
Answer:	The existing overhead fiber optic cables are located 60-ft from the existing bridge and will not be impacted due to the bridge widening. The existing overhead fiber optic cables will remain as indicated in the plan sheet. No relocation is required during construction. The utility lines shown in sheet B1-11 will be revised to show the actual locations as shown in Roadway Plans Sheet 66. The question marks on Sheet B1-11 will be omitted.	Status:	ANSWER PUBLISHED
		Posted:	5/21/2021 11:33:34 AM

Question: 34267: Please confirm the limits of the channel excavation. Are we to excavate per the cross-section on Sheet No. B1-6 under the Bolles Canal Bridge from station 39+39.24 to 42+40 (approximately 200 LF)?

Posted: 5/20/2021 3:18:37 PM

Answer: The limits of excavation is approximately 300 LF. Please refer to the Bridge Canal Grading Exhibit and Canal Cross Sections from the approved SFWMD ROW Permit No. 6774M that was acquired for the Bolles Canal bridge widening. These details show the grading requirements to conform with the SFWMD canal design section for the Bolles Canal and how it will accommodate the bridge widening section. attached is the SFWMD ROW 6774M

Status: ANSWER PUBLISHED

Posted: 5/21/2021 11:28:00 AM

Document: 11762705: SFWMD ROW 6774M.pdf

SFWMD ROW Permit No. 6774M

Question: 34280: Please clarify bid item 440-73-2, in the summary of quantities the total is 644 lf, not 1,275 lf?

Posted: 5/21/2021 2:52:51 PM

Answer: Yes, the correct quantity for Pay Item 440-73-2 is 644 LF.

Status: ANSWER PUBLISHED

Posted: 5/21/2021 5:23:41 PM

Question: 34281: Please clarify bid item 440-1-20 Underdrain type II, in the summary of quantities the total is 3,920 lf. not 7,210 lf.?

Posted: 5/21/2021 2:57:12 PM

Answer: Yes, the correct quantity for Pay Item 440-1-20 is 3920 LF.

Status: ANSWER PUBLISHED

Posted: 5/21/2021 5:22:54 PM