

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: CT210428 Call Order: 003 Proposal: T1786 District:01
Counties: HIGHLANDS
Road Name: SR 70
Limits: FROM CR 29 TO LONESOME ISLAND RD
Project(s): 41450665201(*) Federal Aid No: D120018B
Total Roadway Length: 4.383 Miles Contract Days: 90
Total Bridge Length: 0.000 Miles Letting Date: 04/28/21
Total Proposal Length: 4.383 Miles Contract Execution Days: 10
Special Start Date: N/A
Aquis/Flexible Start Time: 15 Days
Proposal Budget Estimate: \$2,066,728.00

Please read the full advertisement

Description:

The improvements under this contract consist of milling and resurfacing, signing and pavement markings and shoulder treatment along SR 70 from CR 29 Easterly for 4.383 miles to Lonesome Island Road in Highlands County.

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Call Order: 003 Proposal: T1786

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (41450665201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (41450665201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	4,770.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	4,230.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	15.000
	0102- 78-	TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER	EA	590.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	208.000
	0102-115-	TYPE III BARRICADE	ED	180.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	63.000
	0104- 10- 3	SEDIMENT BARRIER	LF	45,036.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	1.000
	0107- 1-	LITTER REMOVAL	AC	79.400
	0107- 2-	MOWING	AC	72.100
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (41450665201)	LS	1.000
	0327- 70- 4	MILLING EXISTING ASPHALT PAVEMENT, 3" AVG DEPTH	SY	54,051.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	18,260.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	4,459.200
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	5,965.700
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	13,424.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	8.764
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.171
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	4.339
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (41450665201)	LS	1.000
Section 0002 Signing				
	0546- 72- 2	GROUND-IN RUMBLE STRIPS, 8" CYLINDRICAL	GM	9.954
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	1.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	1.000
	0701- 18-101	PROFILED THERMOPLASTIC, STANDARD- ASPHALT SURFACES, WHITE, SOLID, 6"	GM	2.128
	0701- 18-201	PROFILED THERMOPLASTIC, STANDARD- ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	0.171
	0701- 18-221	PROFILED THERMOPLASTIC, STANDARD- ASPHALT SURFACES, YELLOW, SKIP, 6"	GM	1.024
	0705- 10- 2	OBJECT MARKER, TYPE 2	EA	4.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (41450665201)	LS	1.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	6.636
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	3.318