

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: CT210428 Call Order: 005 Proposal: T2791 District:02

Counties: DUVAL

Road Name: SR 211

Limits: FROM HERSCHEL ST TO CANTERBURY ST

Project(s): 44355115201(*) Federal Aid No: D219155B

Total Roadway Length:	0.361 Miles	Contract Days:	210
Total Bridge Length:	0.034 Miles	Letting Date:	04/28/21
Total Proposal Length:	0.395 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	15 Days

Proposal Budget Estimate: \$1,608,860.00

Please read the full advertisement

Description:

JEA Standards. Table A -- Schedule of Values is required to be submitted with the bid, as per Technical Special Provision T1000-9.

Please upload completed Table A as a zip file within your EBS File using the "File Attachment Upload" tab before submitting your bid.

The improvements under this contract consist of milling and resurfacing, base work, curb and gutters, traffic signals, lighting, highway signing, sidewalks/bicycle path and other incidental construction on SR 211 (St. Johns Ave.) in Duval County from MP 3.427 to MP 3.822.

Call Order: 005 Proposal: T2791

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44355115201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44355115201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	720.000
	0102- 60-	WORK ZONE SIGN	ED	32,802.000
	0102- 61-	BUSINESS SIGN	EA	18.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	59,148.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	74,876.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	120.000
	0102- 78-	TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER	EA	1,649.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	2,000.000
	0102-115-	TYPE III BARRICADE	ED	520.000
	0104- 1-	ARTIFICIAL COVERINGS /ROLLED EROSION CONTROL PRODUCTS	SY	12.000
	0104- 10- 3	SEDIMENT BARRIER	LF	462.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	14.000
	0107- 1-	LITTER REMOVAL	AC	45.670
	0107- 2-	MOWING	AC	45.670
	0110- 1- 1	CLEARING & GRUBBING (44355115201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	735.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	1,702.000
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (44355115201)	LS	1.000

Call Order: 005 Proposal: T2791

ALT	Item	Description	Unit	Quantity
	0285-711-	OPTIONAL BASE, BASE GROUP 11	SY	412.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	12,591.000
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	1,048.500
	0350- 3- 13	PLAIN CEMENT CONCRETE PAVEMENT, 12"	SY	307.000
	0350- 5-	CLEANING & SEALING JOINTS- CONCRETE PAVEMENT	LF	542.000
	0425- 4-	INLETS, ADJUST	EA	8.000
	0425- 5-	MANHOLE, ADJUST	EA	5.000
	0425- 5- 1	MANHOLE, ADJUST, UTILITIES	EA	9.000
	0425- 6-	VALVE BOXES, ADJUST	EA	11.000
	0458- 1- 11	BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&I POURED JOINT WITH BACKER ROD	LF	83.000
	0458- 1- 21	BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITH BACKER ROD	LF	968.000
	0515- 1- 1	PIPE HANDRAIL - GUIDERAIL, STEEL	LF	10.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	201.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	1,514.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	222.000
	0520- 2- 8	CONCRETE CURB, TYPE RA	LF	328.000
	0520- 5- 11	TRAFFIC SEPARATOR CONCRETE-TYPE I, 4' WIDE	LF	394.000
	0520- 70-	CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH	SY	471.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	570.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	314.000
	0523- 1-	PATTERNED PAVEMENT, VEHICULAR AREAS	SY	307.000
	0527- 2-	DETECTABLE WARNINGS	SF	496.000
	0536- 73-	GUARDRAIL REMOVAL	LF	69.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	1,183.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	3.017
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	977.000
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.059
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	11.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	6.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	1.968
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44355115201)	LS	1.000
Section 0002 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	70.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	3.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	1.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	18.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	12.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	45.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	75.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44355115201)	LS	1.000

Call Order: 005 Proposal: T2791

ALT	Item	Description	Unit	Quantity
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	0.021
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	1,452.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	1,203.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	158.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.097
	0711- 11-144	THERMOPLASTIC, STANDARD, WHITE, 2-2 DOTTED EXTENSION LINE, 12" FOR ROUNDABOUT	GM	0.024
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	10.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	1.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	600.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.044
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	964.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	10.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	10.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	1.440
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	1.207
Section 0003 Lighting				
	1000- 7-	UTILITY WORK- JPA/UTILITY AGREEMENT, POWER (44355115201)	LS	1.000
Section 0004 Signalization				
	0632- 7- 6	SIGNAL CABLE, REMOVE- INTERSECTION	PI	2.000
	0639- 1-610	ELECTRICAL POWER SERVICE, REMOVE OVERHEAD	AS	2.000
	0639- 2- 6	ELECTRICAL SERVICE WIRE, REMOVE	LF	550.000
	0641- 2- 80	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- POLE 30' AND GREATER	EA	5.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	17.000
	0670- 5-600	TRAFFIC CONTROLLER ASSEMBLY, REMOVE CONTROLLER WITH CABINET	AS	2.000