



**Call Order: 002 Proposal: T5716**

ALT	Item	Description	Unit	Quantity
	0285-711-	OPTIONAL BASE, BASE GROUP 11	SY	1,339.000
	0285-712-	OPTIONAL BASE, BASE GROUP 12	SY	262.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	10,573.000
	0327- 70- 7	MILLING EXISTING ASPHALT PAVEMENT, 4" AVG DEPTH	SY	679.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	219.400
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	1,003.900
	0425- 1-203	INLETS, CURB, TYPE 9, J BOT, <10'	EA	1.000
	0425- 1-351	INLETS, CURB, TYPE P-5, <10'	EA	5.000
	0425- 1-361	INLETS, CURB, TYPE P-6, <10'	EA	1.000
	0425- 1-451	INLETS, CURB, TYPE J-5, <10'	EA	1.000
	0425- 1-521	INLETS, DT BOT, TYPE C, <10'	EA	1.000
	0430-174-112	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 12"SD	LF	28.000
	0430-174-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"SD	LF	134.000
	0430-175-112	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 12"S/CD	LF	14.000
	0430-175-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD	LF	189.000
	0430-175-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"S/CD	LF	12.000
	0430-984-129	MITERED END SECTION, OPTIONAL ROUND, 24" SD	EA	3.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	1,736.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	1,096.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	757.000
	0522- 3-	BUS BOARDING PAD- CONCRETE	SY	2.000
	0522- 4-	BUS SHELTER PAD- CONCRETE	SY	22.000
	0527- 2-	DETECTABLE WARNINGS	SF	184.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	3,088.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	1.716
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	401.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	141.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	1.458
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.579
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43745115201)	LS	1.000
<b>Section 0002 Signing</b>				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	5.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	2.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	3.000
	0700- 2- 50	MULTI- POST SIGN, GROUND MOUNT, RELOCATE	AS	1.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	2.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	30.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43745115201)	LS	1.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.130
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	13.000

**Call Order: 002 Proposal: T5716**

ALT	Item	Description	Unit	Quantity
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	80.000
	0711- 14-123	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 12" FOR CROSSWALK	LF	1,020.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	905.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	1.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	13.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.910
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6", 1C -30 SKIP OR 3-9 LANE DROP	GM	0.604
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.434
<b>Section 0003 Lighting</b>				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	1,496.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	631.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	17.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	4,977.000
	0715- 1- 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	LF	5,305.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	13.000
	0715-511-140	LIGHT POLE COMPLETE- SPECIAL DESIGN, F&I, SINGLE ARM SHOULDER MOUNT, ALUMINUM, 40'	EA	10.000
	0715-516-315	LIGHT POLE COMPLETE- SPECIAL DESIGN, F&I ,POLE TOP MOUNT, CONCRETE, 15'	EA	3.000
	0715-550-000	LIGHT POLE COMPLETE- SPECIAL DESIGN, REMOVE	EA	15.000
<b>Section 0004 Signalization</b>				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	374.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	488.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	1.000
	0632- 7- 6	SIGNAL CABLE, REMOVE- INTERSECTION	PI	1.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	19.000
	0639- 1-121	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER FURNISHED BY POWER COMPANY	AS	1.000
	0639- 1-123	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER NOT REQUIRED	AS	1.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	255.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	1.000
	0641- 2- 11	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II PEDESTAL	EA	2.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	8.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	2.000
	0649- 1- 65	STEEL STRAIN POLE, REMOVE, DEEP FOUNDATION REMOVAL, BOLT ON ATTACHMENT	EA	4.000
	0649- 21- 10	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 60'	EA	1.000
	0649- 21- 15	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 70'	EA	1.000

**Call Order: 002 Proposal: T5716**

ALT	Item	Description	Unit	Quantity
	0649- 21- 21	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 78'	EA	2.000
	0650- 1- 34	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL POLYCARBONATE, 3 SECTION, 1 WAY	AS	12.000
	0650- 1- 36	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL POLYCARBONATE, 4 SECTION, 1 WAY	AS	2.000
	0650- 1- 39	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL POLYCARBONATE, 5 SECTION CLUSTER, 1 WAY	AS	1.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	8.000
	0660- 4- 11	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL CABINET EQUIPMENT	EA	6.000
	0660- 4- 12	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT	EA	6.000
	0663- 1-121	SIGNAL PRIORITY AND PREEMPTION SYSTEM, FURNISH AND INSTALL, GPS, REPLACE CABINET ELECTRONICS	EA	1.000
	0663- 1-122	SIGNAL PRIORITY AND PREEMPTION SYSTEM, FURNISH AND INSTALL, GPS, DETECTOR	EA	1.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	8.000
	0670- 5-400	TRAFFIC CONTROLLER ASSEMBLY, MODIFY	AS	1.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	3.000
	0700- 5- 22	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF	EA	4.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	2,520.000
	0715- 5- 32	LUMINAIRE & BRACKET ARM- GALV STEEL, FURNISH & INSTALL NEW LUMINAIRE AND ARM ON NEW/EXISTING POLE	EA	1.000
<b>Section 0005 Landscape / Peripheral</b>				
	0580- 1- 1	LANDSCAPE COMPLETE- SMALL PLANTS (43745115201)	LS	1.000
	0580- 1- 2	LANDSCAPE COMPLETE- LARGE PLANTS (43745115201)	LS	1.000
	0590- 70-	IRRIGATION SYSTEM (43745115201)	LS	1.000
<b>Section 0006 Intelligent Transportation System</b>				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	55.000
	0633- 8- 1	MULTI-CONDUCTOR COMMUNICATION CABLE, FURNISH & INSTALL	LF	65.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	1.000
	0635- 2- 13	PULL & SPLICE BOX, F&I, 30" X 60" RECTANGULAR OR 36" ROUND COVER SIZE	EA	1.000
	0670- 5-400	TRAFFIC CONTROLLER ASSEMBLY, MODIFY	AS	1.000
	0682- 1-113	ITS CCTV CAMERA, F&I, DOME PTZ ENCLOSURE - PRESSURIZED, IP, HIGH DEFINITION	EA	1.000
	0682- 1-600	ITS CCTV CAMERA, REMOVE & DISPOSAL	EA	1.000