

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

| | | | | |
|------------------------|-------------------------------|----------------------------|------------------|-------------|
| Letting: | CT210428 | Call Order: 017 | Proposal: T7474 | District:07 |
| Counties: | HILLSBOROUGH | | | |
| Road Name: | SR 600 (US 92) | | | |
| Limits: | FROM 56TH ST TO THE I-4 RAMPS | | | |
| Project(s): | 44555415201(*) | Federal Aid No: D720036B | | |
| Total Roadway Length: | 1.426 Miles | Contract Days: | 200 | |
| Total Bridge Length: | 0.000 Miles | Letting Date: | 04/28/21 | |
| Total Proposal Length: | 1.426 Miles | Contract Execution Days: | 10 | |
| | | Special Start Date: | N/A | |
| | | Aquis/Flexible Start Time: | 90 Calendar Days | |

Proposal Budget Estimate: \$901,500.00

Please read the full advertisement

Description: FLEXIBLE START

The improvements under this contract consist of the installation of lighting and all appurtenances along both sides of SR 600 (US 92).

Call Order: 017 Proposal: T7474

| ALT | Item | Description | Unit | Quantity |
|------------------------------|-------------|---|------|------------|
| Section 0001 Roadway | | | | |
| | 0101- 1- | MOBILIZATION (44555415201) | LS | 1.000 |
| | 0102- 1- | MAINTENANCE OF TRAFFIC (44555415201) | LS | 1.000 |
| | 0102- 60- | WORK ZONE SIGN | ED | 14,200.000 |
| | 0102- 74- 1 | CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD | ED | 8,200.000 |
| | 0102- 99- | PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY | ED | 428.000 |
| | 0999- 25- | INITIAL CONTINGENCY AMOUNT, DO NOT BID (44555415201) | LS | 1.000 |
| Section 0002 Lighting | | | | |
| | 0630- 2- 11 | CONDUIT, FURNISH & INSTALL, OPEN TRENCH | LF | 7,450.000 |
| | 0630- 2- 12 | CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE | LF | 6,874.000 |
| | 0635- 2- 11 | PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE | EA | 88.000 |
| | 0639- 1-122 | ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR | AS | 1.000 |
| | 0639- 2- 1 | ELECTRICAL SERVICE WIRE, FURNISH & INSTALL | LF | 10.000 |
| | 0641- 2- 12 | PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE | EA | 1.000 |
| | 0715- 1- 12 | LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6 | LF | 35,942.000 |
| | 0715- 1- 13 | LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2 | LF | 13,503.000 |
| | 0715- 4- 13 | LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT | EA | 31.000 |
| | 0715- 4- 14 | LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 45' MOUNTING HEIGHT | EA | 13.000 |
| | 0715- 7- 11 | LOAD CENTER, F&I, SECONDARY VOLTAGE | EA | 1.000 |
| | 0715-500- 1 | POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL | EA | 44.000 |