

Call Order: 004 Proposal: T1784

ALT	Item	Description	Unit	Quantity
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	21,800.000
	0630- 2- 14	CONDUIT, FURNISH & INSTALL, ABOVEGROUND	LF	30.000
	0632- 7- 2	SIGNAL CABLE- REPAIR/REPLACE/OTHER, FURNISH & INSTALL	LF	100.000
	0633- 1-121	FIBER OPTIC CABLE, F&I, UNDERGROUND,2-12 FIBERS	LF	807.000
	0633- 1-123	FIBER OPTIC CABLE, F&I, UNDERGROUND,49-96 FIBERS	LF	39,127.000
	0633- 1-620	FIBER OPTIC CABLE, REMOVE, UNDERGROUND	LF	223.000
	0633- 2- 31	FIBER OPTIC CONNECTION, INSTALL, SPLICE	EA	224.000
	0633- 2- 32	FIBER OPTIC CONNECTION, INSTALL, TERMINATION	EA	156.000
	0633- 3- 11	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE ENCLOSURE	EA	9.000
	0633- 3- 14	FIBER OPTIC CONNECTION HARDWARE, F&I, BUFFER TUBE FAN OUT KIT	EA	13.000
	0633- 3- 16	FIBER OPTIC CONNECTION HARDWARE, F&I, PATCH PANEL- FIELD TERMINATED	EA	6.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	2.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	38.000
	0635- 2- 13	PULL & SPLICE BOX, F&I, 30" X 60" RECTANGULAR OR 36" ROUND COVER SIZE	EA	8.000
	0650- 2-109	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, BACKPLATE- FLEXIBLE REQUIRED	EA	16.000
	0660- 5- 11	VEHICLE DETECTION SYSTEM- WIRELESS MAGNETOMETER, FURNISH & INSTALL, CABINET EQUIPMENT	EA	4.000
	0660- 5- 12	VEHICLE DETECTION SYSTEM- WIRELESS MAGNETOMETER, FURNISH & INSTALL, ABOVE GROUND EQUIPMENT	EA	8.000
	0660- 5- 13	VEHICLE DETECTION SYSTEM- WIRELESS MAGNETOMETER, FURNISH & INSTALL, IN-ROAD ELECTRONICS	EA	42.000
	0671- 2- 11	TRAFFIC CONTROLLER WITHOUT CABINET, F&I IN EXISTING CABINET, NEMA	EA	6.000
	0671- 2- 60	TRAFFIC CONTROLLER, REMOVE- CABINET TO REMAIN	EA	6.000
	0682- 1-133	ITS CCTV CAMERA, F&I, DOME ENCLOSURE - NON-PRESSURIZED, IP, HIGH DEFINITION	EA	5.000
	0684- 1- 1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	EA	6.000