

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	CT210217	Call Order: 006	Proposal: T2802	District:02
Counties:	DUVAL			
Road Name:	SR 202 (J TURNER BUTLER BLVD)			
Limits:	FROM PHILIPS HIGHWAY TO SR A1A			
Project(s):	43575715201(*)	Federal Aid No: N/A		
Total Roadway Length:	9.537 Miles	Contract Days:	180	
Total Bridge Length:	0.558 Miles	Letting Date:	02/17/21	
Total Proposal Length:	10.095 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	90 Days	

Proposal Budget Estimate: \$1,414,078.00

Please read the full advertisement

Description:

The improvements under this contract consist of installing ITS conduit and fiber and other incidental construction along SR 202 (J Turner Butler Blvd.) from US 1 (Philips Highway) to SR A1A in Duval County.

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Call Order: 006 Proposal: T2802

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (43575715201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43575715201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	4,320.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	4,680.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	180.000
	0104- 10- 3	SEDIMENT BARRIER	LF	5,884.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	8.000
	0110- 1- 1	CLEARING & GRUBBING (43575715201)	LS	1.000
	0550- 10-110	FENCING, TYPE A, 0.0-5.0', STANDARD	LF	16.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43575715201)	LS	1.000
Section 0002 Intelligent Transportation System				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	29,455.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	26,395.000
	0633- 1-121	FIBER OPTIC CABLE, F&I, UNDERGROUND,2-12 FIBERS	LF	11,280.000
	0633- 1-122	FIBER OPTIC CABLE, F&I, UNDERGROUND,13-48 FIBERS	LF	120.000
	0633- 1-124	FIBER OPTIC CABLE, F&I, UNDERGROUND, 97 - 144 FIBERS	LF	62,995.000
	0633- 2- 31	FIBER OPTIC CONNECTION, INSTALL, SPLICE	EA	264.000
	0633- 2- 32	FIBER OPTIC CONNECTION, INSTALL, TERMINATION	EA	36.000
	0633- 3- 11	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE ENCLOSURE	EA	19.000
	0633- 3- 12	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE TRAY	EA	22.000
	0633- 3- 14	FIBER OPTIC CONNECTION HARDWARE, F&I, BUFFER TUBE FAN OUT KIT	EA	3.000
	0633- 3- 16	FIBER OPTIC CONNECTION HARDWARE, F&I, PATCH PANEL- FIELD TERMINATED	EA	2.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	70.000
	0635- 2- 13	PULL & SPLICE BOX, F&I, 30" X 60" RECTANGULAR OR 36" ROUND COVER SIZE	EA	26.000
	0684- 1- 1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	EA	1.000