

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: CT210217 Call Order: 007 Proposal: T3760 District:03
Counties: FRANKLIN
Road Name: SR 30 (US 98)
Limits: FROM E OF CR 385 (TILTON RD) TO CR 384 (12TH ST)
Project(s): 44154015201(*) Federal Aid No: D320045B
Total Roadway Length: 5.509 Miles Contract Days: 150
Total Bridge Length: 0.005 Miles Letting Date: 02/17/21
Total Proposal Length: 5.514 Miles Contract Execution Days: 10
Special Start Date: N/A
Aquis/Flexible Start Time: 15 Days Acquis.

Proposal Budget Estimate: \$2,955,760.00

Please read the full advertisement

Description:

The improvements under this contract consist of milling and resurfacing on SR 30 (US 98) from East of CR 385 Tilton Road to CR 384 12th Street. Other work includes minor drainage improvements, asphalt turnout construction, guardrail updates, addition of sidewalk and signing and pavement markings. All work to be done in Franklin County.

Call Order: 007 Proposal: T3760

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44154015201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44154015201)	LS	1.000
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	91.100
	0102- 4-	PEDESTRIAN SPECIAL DETOUR (44154015201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	32.000
	0102- 60-	WORK ZONE SIGN	ED	13,950.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	53,850.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	33,750.000
	0102- 78-	TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER	EA	2,007.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	328.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	150.000
	0104- 10- 3	SEDIMENT BARRIER	LF	1,440.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	188.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	17.000
	0107- 1-	LITTER REMOVAL	AC	518.720
	0107- 2-	MOWING	AC	151.050
	0110- 1- 1	CLEARING & GRUBBING (44154015201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	34.000
	0110- 7- 1	MAILBOX, F&I SINGLE	EA	6.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	272.000
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (44154015201)	LS	1.000
	0286- 1-	TURNOUT CONSTRUCTION/DRIVEWAY BASE- OPTIONAL MATERIALS	SY	1,637.000

Call Order: 007 Proposal: T3760

ALT	Item	Description	Unit	Quantity
	0327- 70- 5	MILLING EXISTING ASPHALT PAVEMENT, 2" AVG DEPTH	SY	7,918.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	75,329.000
	0327- 70- 11	MILLING EXISTING ASPHALT PAVEMENT, 2 1/4" AVG DEPTH	SY	376.000
	0327- 70- 12	MILLING EXISTING ASPHALT PAVEMENT, 1 1/4" AVG DEPTH	SY	607.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	6,581.300
	0337- 7- 80	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-9.5, PG 76-22	TN	7,318.800
	0337- 7- 81	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-12.5, PG 76-22	TN	870.200
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	19.100
	0425- 1-521	INLETS, DT BOT, TYPE C, <10'	EA	1.000
	0425- 6-	VALVE BOXES, ADJUST	EA	1.000
	0425- 7-	MANHOLE COVER- REPLACE	EA	1.000
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	144.000
	0430-175-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"S/CD	LF	339.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	9.000
	0430-984-129	MITERED END SECTION, OPTIONAL ROUND, 24" SD	EA	7.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	3,813.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	450.000
	0527- 2-	DETECTABLE WARNINGS	SF	365.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	8.000
	0536- 1- 0	GUARDRAIL -ROADWAY, GENERAL/LOW SPEED TL-2	LF	359.000
	0536- 7- 3	SPECIAL GUARDRAIL POST- ENCASED POST FOR SHALLOW MOUNT	EA	4.000
	0536- 73-	GUARDRAIL REMOVAL	LF	226.000
	0536- 85- 20	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE	EA	2.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	2.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	3,092.000
	0570- 1- 3	PERFORMANCE TURF, SOD AND SOIL- SHOULDER TREATMENT INDEX 570-010	SY	13,935.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	10.871
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	796.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	312.000
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	1.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	8.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	3.886
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	339.000
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	4.071
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44154015201)	LS	1.000
Section 0002 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	5.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	4.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	1.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	1.000

Call Order: 007 Proposal: T3760

ALT	Item	Description	Unit	Quantity
	0701- 18-101	PROFILED THERMOPLASTIC,STANDARD- ASPHALT SURFACES, WHITE, SOLID,6"	GM	6.600
	0701- 18-201	PROFILED THERMOPLASTIC,STANDARD- ASPHALT SURFACES, YELLOW, SOLID,6"	GM	0.199
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	6.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44154015201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	796.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	312.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.192
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	339.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	19.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	8.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	4.241
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	3.886
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	4.066