

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: CT210127 Call Order: 007 Proposal: T2789 District:02

Counties: TAYLOR

Road Name: SR 55 (US 221)

Limits: FROM CEDAR ST TO MADISON CO LINE

Project(s): 44105815201(*)

Federal Aid No: D220088B

Total Roadway Length:	11.217 Miles	Contract Days:	180
Total Bridge Length:	0.190 Miles	Letting Date:	01/27/21
Total Proposal Length:	11.407 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	15 Days

Proposal Budget Estimate: \$5,566,647.00

Please read the full advertisement

Description:

The improvements under this contract consist of milling and resurfacing, base work, shoulder treatment, drainage improvements, highway signing, guardrail, and other incidental construction on SR 55 from Cedar St. to Madison County Line.

Call Order: 007 Proposal: T2789

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0458- 1- 21	BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITH BACKER ROD	LF	695.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (44105815201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44105815201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	11,880.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	18,720.000
	0102- 78-	TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER	EA	6,886.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	720.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	180.000
	0104- 1-	ARTIFICIAL COVERINGS /ROLLED EROSION CONTROL PRODUCTS	SY	434.000
	0104- 10- 3	SEDIMENT BARRIER	LF	74,092.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	3,520.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	12.000
	0107- 1-	LITTER REMOVAL	AC	630.480
	0107- 2-	MOWING	AC	547.440
	0110- 1- 1	CLEARING & GRUBBING (44105815201)	LS	1.000
	0110- 7- 1	MAILBOX, F&I SINGLE	EA	3.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	166.700
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (44105815201)	LS	1.000
	0160- 4-	TYPE B STABILIZATION	SY	289.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	5,923.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	84.000
	0327- 70- 4	MILLING EXIST ASPH PAVT, 3" AVG DEPTH	SY	25,367.000
	0327- 70- 5	MILLING EXIST ASPH PAVT, 2" AVG DEPTH	SY	127,138.000

Call Order: 007 Proposal: T2789

ALT	Item	Description	Unit	Quantity
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	24,674.000
	0327- 70- 16	MILLING EXIST ASPH PAVT, 1/2" AVG DEPTH	SY	52,628.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	12,581.600
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	18,959.000
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	100.400
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	72.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	2.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	4,963.000
	0536- 73-	GUARDRAIL REMOVAL	LF	3,336.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	19.000
	0536- 85- 26	GUARDRAIL END TREATMENT- TYPE CRT	EA	5.000
	0570- 1- 3	PERFORMANCE TURF, SOD AND SOIL- SHOULDER TREATMENT INDEX 570-010	SY	43,360.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	46.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	4,898.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	852.000
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.030
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	4.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	20.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	24.171
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	956.000
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	27.291
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44105815201)	LS	1.000
Section 0003 Signing				
	0546- 72- 3	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL	GM	29.946
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	54.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	47.000
	0700- 3-202	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 12-20 SF	EA	2.000
	0700- 3-602	SIGN PANEL, REMOVE, 12-20 SF	EA	3.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	21.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44105815201)	LS	1.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	2,449.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	426.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.066
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	2.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	10.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	239.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	1.000

Call Order: 007 Proposal: T2789

ALT	Item	Description	Unit	Quantity
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	1.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	22.955
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	7.939
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	9.097
Section 0004 Signalization				
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	1.000
	0632- 7- 6	SIGNAL CABLE, REMOVE- INTERSECTION	PI	1.000
	0634- 4-152	SPAN WIRE ASSEMBLY, F&I, TWO POINT, DIAGONAL	PI	1.000
	0634- 4-600	SPAN WIRE ASSEMBLY, REMOVE- POLES REMAIN	PI	1.000
	0650- 1- 11	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 1 SECTION, 1 WAY	AS	2.000
	0650- 1- 12	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 1 SECTION, 2-4 WAY	AS	2.000