

Call Order: 008 Proposal: T2790

ALT	Item	Description	Unit	Quantity
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	120.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	2.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	147.000
	0107- 1-	LITTER REMOVAL	AC	361.630
	0107- 2-	MOWING	AC	182.990
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (43616815201)	LS	1.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (43616815201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (43616815201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	27,657.000
	0120- 1-	REGULAR EXCAVATION	CY	1,287.000
	0120- 4-	SUBSOIL EXCAVATION	CY	1,116.000
	0120- 6-	EMBANKMENT	CY	416.000
	0160- 4-	TYPE B STABILIZATION	SY	4,289.000
	0173- 71-	DRILLING HOLES FOR PRESSURE GROUTING	EA	486.000
	0173- 76-	GROUT PIPE INSTALLATION	LF	14,295.000
	0173- 77- 1	SUBSURFACE PRESSURE GROUTING, SAND CEMENT	CY	6,777.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	2,854.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	371.000
	0285-715-	OPTIONAL BASE, BASE GROUP 15	SY	473.000
	0289- 1-100	COARSE AGGREGATE BASE SPECIAL DESIGN, PROJECT 436168-1-52-01, 12"	SY	2,272.000
	0289- 1-101	COARSE AGGREGATE BASE SPECIAL DESIGN, PROJECT 436168-1-52-01, 6"	SY	2,151.000
	0327- 70- 4	MILLING EXIST ASPH PAVT, 3" AVG DEPTH	SY	1,517.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	6,775.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	194.500
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	1,005.700
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	24.700
	0350- 4-100	REINFORCED CEMENT CONCRETE PAVEMENT, 12", PROJECT 436168-1-52-01	SY	4,000.000
	0350- 5-	CLEANING & SEALING JOINTS- CONCRETE PAVEMENT	LF	188,057.000
	0350- 6-	CLEANING & SEALING RANDOM CRACKS- CONCRETE PAVEMENT	LF	417.000
	0352- 70-	GRINDING CONCRETE PAVEMENT	SY	119,791.000
	0353- 70-	CONCRETE PAVEMENT SLAB REPLACEMENT	CY	5,510.500
	0401- 70- 4	RESTORE SPALLED AREAS, PORTLAND CEMENT GROUT	CF	22.000
	0415- 1- 1	REINFORCING STEEL- ROADWAY	LB	456,450.000
	0425- 1-345	INLETS, CURB, TYPE P-4, PARTIAL	EA	8.000
	0425- 1-551	INLETS, DT BOT, TYPE E, <10'	EA	1.000
	0425- 5-	MANHOLE, ADJUST	EA	1.000
	0430-175-115	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 15"S/CD	LF	184.000
	0430-175-218	PIPE CULVERT, OPTIONAL MATERIAL, OTHER-ELIP/ARCH, 18"S/CD	LF	296.000
	0430-982-625	MITERED END SECTION, OPTIONAL - ELLIPTICAL / ARCH, 18" CD	EA	1.000
	0431- 1-251	PIPE LINING- CURED IN PLACE 15", PROJECT 436168-1-52-01	LF	767.000
	0431- 1-252	PIPE LINING- CURED IN PLACE 18", PROJECT 436168-1-52-01	LF	2,048.000

Call Order: 008 Proposal: T2790

ALT	Item	Description	Unit	Quantity
	0431- 1-253	PIPE LINING- CURED IN PLACE 24", PROJECT 436168-1-52-01	LF	2,153.000
	0431- 1-254	PIPE LINING- CURED IN PLACE 30", PROJECT 436168-1-52-01	LF	102.000
	0431- 1-255	PIPE LINING- CURED IN PLACE 36", PROJECT 436168-1-52-01	LF	528.000
	0431- 1-256	PIPE LINING- CURED IN PLACE 42", PROJECT 436168-1-52-01	LF	210.000
	0431- 1-258	PIPE LINING- CURED IN PLACE 48", PROJECT 436168-1-52-01	LF	425.000
	0431- 1-259	PIPE LINING- CURED IN PLACE 54", PROJECT 436168-1-52-01	LF	211.000
	0436- 1- 1	TRENCH DRAIN, STANDARD	LF	369.000
	0515- 2-311	PEDESTRIAN/ BICYCLE RAILING, ALUMINUM ONLY,42" TYPE 1	LF	76.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	401.000
	0520- 2- 2	CONCRETE CURB, TYPE B	LF	1,448.000
	0520- 5- 21	TRAFFIC SEPARATOR - CONCRETE, TYPE II, 4' WIDE	LF	716.000
	0520- 5- 22	TRAFFIC SEPARATOR - CONCRETE, TYPE II, 6' WIDE	LF	327.000
	0520- 70-	CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH	SY	750.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	3,008.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	216.000
	0522- 3-	BUS BOARDING PAD- CONCRETE	SY	63.000
	0527- 2-	DETECTABLE WARNINGS	SF	225.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	604.400
	0536- 1- 0	GUARDRAIL -ROADWAY, GENERAL/LOW SPEED TL-2	LF	725.000
	0536- 7- 1	SPECIAL GUARDRAIL POST- DEEP POST FOR SLOPE BREAK CONDITION- TIMBER OR STEEL	EA	116.000
	0536- 73-	GUARDRAIL REMOVAL	LF	392.000
	0536- 85- 20	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE	EA	1.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	1.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	6,553.000
	0571- 1- 11	PLASTIC EROSION MAT, TURF REINFORCED MAT, TYPE 1	SY	1,051.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	13.584
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	1,242.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	145.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	599.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	8.281
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.686
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	38.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	10.328
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	98.000
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.881
	0710- 11-331	PAINTED PAVEMENT MARKINGS, STANDARD,BLACK, SKIP, 6"	GM	6.878
	0906-173- 26	TWO COMPONENT POLYURETHANE INJECTION, PROJECT 436168-1- 52-01	LB	4,212.000
	0999- 20- 1	DISPUTES REVIEW BOARD, MEETING- DO NOT BID	DA	25.000
	0999- 20- 2	DISPUTES REVIEW BOARD, HEARING- DO NOT BID	EA	2.000

Call Order: 008 Proposal: T2790

ALT	Item	Description	Unit	Quantity
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43616815201)	LS	1.000
Section 0002 Signing				
	0654- 2- 22	RECTANGULAR RAPID FLASHING BEACON, FURNISH & INSTALL- SOLAR POWERED, COMPLETE SIGN ASSEMBLY- BACK TO BACK	AS	4.000
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	44.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	9.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	14.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	25.000
	0700- 2- 50	MULTI- POST SIGN, GROUND MOUNT, RELOCATE	AS	1.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	4.000
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	13.000
	0705- 11- 3	DELINEATOR, FLEXIBLE HIGH VISIBILITY MEDIAN	EA	20.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	563.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43616815201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	6,066.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	3,390.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	1,148.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.063
	0711- 11-180	THERMOPLASTIC, STANDARD, WHITE, YIELD LINE	LF	90.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	320.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.821
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	2,196.000
	0711- 14-141	THERMOPLASTIC, PREFORMED, WHITE, 2-4 DOTTED GUIDELINE ON CONCRETE SURFACES	GM	0.135
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	2.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	15.000
	0711- 14-341	THERMOPLASTIC, PREFORMED, BLACK, 2-4 DOTTED GUIDELINE ON CONCRETE SURFACES	GM	0.133
	0711- 14-560	THERMOPLASTIC, PREFORMED, WHITE WITH BLACK CONTRAST ON CONCRETE PAVEMENT, MESSAGE OR SYMBOL	EA	32.000
	0711- 14-570	THERMOPLASTIC, PREFORMED, WHITE WITH BLACK CONTRAST, ARROW ON CONCRETE SURFACE	EA	92.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.111
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.069
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	257.000
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	4.852
	0713-103-102	PERMANENT TAPE, WHITE, SOLID, 8" EXIT LANE AT INTERCHANGE ON CONCRETE PAVEMENT	GM	0.193
	0713-103-131	PERMANENT TAPE, WHITE, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	5.192

Call Order: 008 Proposal: T2790

ALT	Item	Description	Unit	Quantity
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	4.552
	0713-103-331	PERMANENT TAPE, BLACK, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	4.878
Section 0003 Signalization				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	1,399.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	534.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	3.000
	0632- 7- 6	SIGNAL CABLE, REMOVE- INTERSECTION	PI	1.000
	0633- 1-122	FIBER OPTIC CABLE, F&I, UNDERGROUND,13-48 FIBERS	LF	16.000
	0633- 3- 15	FIBER OPTIC CONNECTION HARDWARE, F&I, PRETERMINATED PATCH PANEL	EA	1.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	35.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	1.000
	0639- 1-610	ELECTRICAL POWER SERVICE, REMOVE OVERHEAD	AS	1.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	83.000
	0639- 2- 6	ELECTRICAL SERVICE WIRE, REMOVE	LF	55.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	1.000
	0641- 2- 11	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II PEDESTAL	EA	1.000
	0641- 2- 80	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- POLE 30' AND GREATER	EA	4.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	15.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	2.000
	0649- 1- 61	STEEL STRAIN POLE, REMOVE PEDESTAL OR SERVICE POLE- COMPLETE REMOVAL	EA	4.000
	0649- 21- 1	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 30'	EA	1.000
	0649- 21- 6	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 50'	EA	1.000
	0649- 21- 10	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 60'	EA	2.000
	0650- 1- 14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	11.000
	0650- 1- 16	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 4 SECTION, 1 WAY	AS	2.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	12.000
	0653- 1- 12	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAYS	AS	3.000
	0653- 1- 60	PEDESTRIAN SIGNAL, REMOVE PED SIGNAL- POLE/PEDESTAL TO REMAIN	AS	4.000
	0660- 4- 60	VEHICLE DETECTION SYSTEM- VIDEO, REMOVE	EA	15.000
	0660- 5- 11	VEHICLE DETECTION SYSTEM- WIRELESS MAGNETOMETER, FURNISH & INSTALL, CABINET EQUIPMENT	EA	4.000
	0660- 5- 12	VEHICLE DETECTION SYSTEM- WIRELESS MAGNETOMETER, FURNISH & INSTALL, ABOVE GROUND EQUIPMENT	EA	12.000
	0660- 5- 13	VEHICLE DETECTION SYSTEM- WIRELESS MAGNETOMETER, FURNISH & INSTALL, IN-ROAD ELECTRONICS	EA	115.000
	0665- 1- 12	PEDESTRIAN DETECTOR, FURNISH & INSTALL, ACCESSIBLE	EA	18.000

Call Order: 008 Proposal: T2790

ALT	Item	Description	Unit	Quantity
	0665- 1- 60	PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN	EA	2.000
	0670- 5-111	TRAFFIC CONTROLLER ASSEMBLY, F&I, NEMA, 1 PREEMPTION	AS	1.000
	0670- 5-400	TRAFFIC CONTROLLER ASSEMBLY, MODIFY	AS	3.000
	0670- 5-600	TRAFFIC CONTROLLER ASSEMBLY, REMOVE CONTROLLER WITH CABINET	AS	1.000
	0684- 1- 1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	EA	1.000
	0684- 6- 40	WIRELESS COMMUNICATION DEVICE, RELOCATE	EA	1.000
	0685- 1- 13	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, LINE INTERACTIVE WITH CABINET	EA	1.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	2.000
	0700- 5- 21	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	2.000
	0700- 5- 22	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF	EA	2.000