

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

Letting:	CT210127	Call Order: 010	Proposal: T2799	District:02
Counties:	DUVAL			
Road Name:	SR 5 (US 1/MAIN ST)			
Limits:	AT INDEPENDENT DR TO MAIN ST SB			
Project(s):	43584515201(*)	Federal Aid No:	N/A	
Total Roadway Length:	0.013 Miles	Contract Days:	200	
Total Bridge Length:	0.055 Miles	Letting Date:	01/27/21	
Total Proposal Length:	0.068 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	15 Days (Acq. time)	

Proposal Budget Estimate: \$999,257.00

Please read the full advertisement

Description:

The improvements under this contract consist of ramp demolition of Water Street Eastbound at Independent Drive to Main Street Southbound Bridge #720376 and other incidental construction on SR 5 in Duval County from MP 0.000 to MP 0.068.

**Call Order: 010 Proposal: T2799**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Structures</b>				
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (43584515201-720376)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	365.000
	0400- 4- 4	CONCRETE CLASS IV, SUPERSTRUCTURE	CY	20.600
	0415- 1- 4	REINFORCING STEEL - BRIDGE SUPERSTRUCTURE	LB	2,884.000
	0458- 1- 11	BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&I POURED JOINT WITH BACKER ROD	LF	8.000
	0506- 2-	BRIDGE DRAINAGE PIPE	LF	22.000
	0506- 3-	BRIDGE DRAINS	EA	1.000
	0515- 4- 1	BULLET RAIL, SINGLE RAIL	LF	141.000
<b>Section 0002 Roadway</b>				
	0101- 1-	MOBILIZATION (43584515201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43584515201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	22,400.000
	0102- 71- 16	TEMPORARY BARRIER, F&I, FREE STANDING	LF	200.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	9,512.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	48,600.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	200.000
	0102- 78-	TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER	EA	72.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	2.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,028.000
	0102-115-	TYPE III BARRICADE	ED	2,600.000
	0102-913- 21	REMOVABLE TAPE, WHITE, SOLID 6"	GM	0.068
	0104- 10- 3	SEDIMENT BARRIER	LF	562.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	4.000

**Call Order: 010 Proposal: T2799**

ALT	Item	Description	Unit	Quantity
	0110- 1- 1	CLEARING & GRUBBING (43584515201)	LS	1.000
	0110- 2- 2	SELECTIVE CLEARING AND GRUBBING, AREAS WITH TREES TO REMAIN	AC	0.010
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	129.000
	0110- 21-	TREE PROTECTION BARRIER	LF	434.000
	0527- 2-	DETECTABLE WARNINGS	SF	27.000
	0550- 10-220	FENCING, TYPE B, 5.1-6.0', STANDARD	LF	841.000
	0550- 60-223	FENCE GATE, TYPE B, DOUBLE, 12.1-18.0' OPENING	EA	1.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	1,193.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43584515201)	LS	1.000
<b>Section 0003 Signing</b>				
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	2.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	4.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.013
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	142.000
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.025
	0713-103-103	PERMANENT TAPE, WHITE, SOLID LANE DROP MARKING, 12" FOR CONCRETE BRIDGES	GM	0.008
<b>Section 0004 Lighting</b>				
	0715- 1- 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	LF	810.000
	0715- 4- 71	LIGHT POLE COMPLETE, REMOVE POLE, FOUNDATION REMAINS	EA	3.000
	0715- 11-500	LUMINAIRE, REMOVE	EA	1.000
<b>Section 0005 Signalization</b>				
	0630- 2- 15	CONDUIT, FURNISH & INSTALL, BRIDGE MOUNT	LF	20.000
	0632- 7- 4	SIGNAL CABLE, ADJUST	PI	1.000
	0649- 1- 61	STEEL STRAIN POLE, REMOVE PEDESTAL OR SERVICE POLE- COMPLETE REMOVAL	EA	2.000
	0660- 1-600	LOOP DETECTOR INDUCTIVE, REMOVE- CABINET TO REMAIN	EA	1.000