

Call Order: 012 Proposal: T2816

ALT	Item	Description	Unit	Quantity
	0521- 5- 13	CONCRETE TRAFFIC RAILING- BRIDGE, 36" SINGLE-SLOPE	LF	380.000
	0530- 1-100	RIPRAP, SAND-CEMENT BAGS	CY	46.600
	0530- 3- 3	RIPRAP- RUBBLE, BANK AND SHORE	TN	1,173.000
	0530- 74-	BEDDING STONE	TN	441.000
	0630- 2- 16	CONDUIT, FURNISH & INSTALL, EMBEDDED CONCRETE BARRIERS AND TRAFFIC RAILINGS	LF	1,140.000
	0635- 3- 13	JUNCTION BOX, FURNISH & INSTALL, EMBEDDED	EA	12.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (43740715201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43740715201)	LS	1.000
	0102- 2-123	SPECIAL DETOUR- TEMPORARY BRIDGE, PROJECT 437407-1-52-01 (43740715201)	LS	1.000
	0102- 2-200	SPECIAL DETOUR- TEMPORARY PAVEMENT (43740715201)	LS	1.000
	0102- 2-300	SPECIAL DETOUR- TEMPORARY EARTHWORK/BASE (43740715201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	8,100.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	1,005.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	1,192.000
	0102- 71- 25	TEMPORARY BARRIER, RELOCATE, ANCHORED	LF	805.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	3,934.000
	0102- 78-	TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER	EA	1,248.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	4.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	796.000
	0102-115-	TYPE III BARRICADE	ED	1,600.000
	0102-913- 21	REMOVABLE TAPE, WHITE, SOLID 6"	GM	0.144
	0102-913- 31	REMOVABLE TAPE, YELLOW, SOLID, 6"	GM	0.144
	0104- 10- 3	SEDIMENT BARRIER	LF	1,197.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	302.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (43740715201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (43740715201)	LS	1.000
	0110- 7- 1	MAILBOX, F&I SINGLE	EA	1.000
	0120- 1-	REGULAR EXCAVATION	CY	390.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	1,407.000
	0125- 1-	EXCAVATION FOR STRUCTURES	CY	584.000
	0160- 4-	TYPE B STABILIZATION	SY	1,968.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	839.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	736.000
	0327- 70- 1	MILLING EXIST ASPH PAVT, 1" AVG DEPTH	SY	561.000
	0327- 70- 12	MILLING EXIST ASPH PAVT, 1 1/4" AVG DEPTH	SY	561.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	138.600
	0337- 7- 81	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-12.5, PG 76-22	TN	155.900
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	18.600
	0425- 1-701	INLETS, GUTTER, TYPE S, <10'	EA	6.000
	0430-175-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD	LF	285.000
	0430-982-125	MITERED END SECTION, OPTIONAL ROUND, 18" CD	EA	4.000

Call Order: 012 Proposal: T2816

ALT	Item	Description	Unit	Quantity
	0520- 6-	SHOULDER GUTTER- CONCRETE	LF	489.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	452.100
	0530- 74-	BEDDING STONE	TN	325.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	519.000
	0536- 8-112	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, FURNISH AND INSTALL, NEW BRIDGE OR CONCRETE BARRIER, APPROACH TL-3	EA	4.000
	0536- 73-	GUARDRAIL REMOVAL	LF	454.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	4.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	583.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	0.770
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	2.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.826
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43740715201)	LS	1.000
Section 0003 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	1.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	1.000
	0705- 10- 3	OBJECT MARKER, TYPE 3	EA	4.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43740715201)	LS	1.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	4.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	4.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.279
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.279
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.072
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.072
Section 0004 Utilities				
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43740715601)	LS	1.000
	1000- 6-	UTILITY WORK- JPA/UTILITY AGREEMENT, WATER (43740715601)	LS	1.000