

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: CT210127 Call Order: 013 Proposal: T3761 District:03
 Counties: GADSDEN
 Road Name: SR 267
 Limits: FROM SR 10 (US 90) JEFFERSON ST TO THE GEORGIA ST LINE
 Project(s): 43776115201(*) Federal Aid No: D320029B
 Total Roadway Length: 8.481 Miles Contract Days: 150
 Total Bridge Length: 0.006 Miles Letting Date: 01/27/21
 Total Proposal Length: 8.487 Miles Contract Execution Days: 10
 Special Start Date: N/A
 Aquis/Flexible Start Time: 15 days Acquis.

Proposal Budget Estimate: \$4,042,035.00

Please read the full advertisement

Description:

The improvements under this contract consist of milling and resurfacing SR 267 from SR 10 (US 90) Jefferson Street to the Georgia State line in Gadsden County. Additional work includes, but not limited to, sidewalk repairs, guardrail replacement, sidestreet radial improvements, TTMS replacement, railroad crossing reconstruction, signal loop replacements and signing and pavement markings.

Call Order: 013 Proposal: T3761

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (43776115201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43776115201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	44.000
	0102- 60-	WORK ZONE SIGN	ED	13,805.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	17,578.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	1,650.000
	0102- 78-	TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER	EA	1,962.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	157.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	450.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	450.000
	0102-115-	TYPE III BARRICADE	ED	16.000
	0104- 10- 3	SEDIMENT BARRIER	LF	1,206.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	11.000
	0107- 1-	LITTER REMOVAL	AC	349.030
	0107- 2-	MOWING	AC	272.070
	0110- 1- 1	CLEARING & GRUBBING (43776115201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	238.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	11.200
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (43776115201)	LS	1.000
	0160- 4-	TYPE B STABILIZATION	SY	348.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	79.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	113.000

Call Order: 013 Proposal: T3761

ALT	Item	Description	Unit	Quantity
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	126,142.000
	0327- 70- 15	MILLING EXIST ASPH PAVT, 2 3/4" AVG DEPTH	SY	2,526.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	9,317.600
	0337- 7- 80	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-9.5, PG 76-22	TN	11,266.700
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	6.000
	0425- 5-	MANHOLE, ADJUST	EA	2.000
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	208.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	34.000
	0430-984-129	MITERED END SECTION, OPTIONAL ROUND, 24" SD	EA	2.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	168.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	84.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	117.000
	0527- 2-	DETECTABLE WARNINGS	SF	227.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	147.000
	0536- 73-	GUARDRAIL REMOVAL	LF	152.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	2.000
	0546- 71- 1	RAISED RUMBLE STRIP SET- PERMANENT	EA	4.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	22,195.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	57.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	1.000
	0695- 1- 1	TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL	EA	2.000
	0695- 6- 12	TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 2 LOOPS	EA	2.000
	0695- 7-600	TRAFFIC MONITORING SITE CABINET, REMOVE EXISTING CABINET	EA	2.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	15.372
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	97.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	314.000
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	1.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	7.542
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	5.297
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43776115201)	LS	1.000
Section 0002 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	101.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	2.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	8.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	39.000
	0700- 2- 15	MULTI- POST SIGN, F&I GROUND MOUNT, 51-100 SF	AS	1.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	6.000
	0700- 3-202	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 12-20 SF	EA	1.000
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	2.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	4.000
	0700- 3-602	SIGN PANEL, REMOVE, 12-20 SF	EA	1.000

Call Order: 013 Proposal: T3761

ALT	Item	Description	Unit	Quantity
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	1.000
	0701- 18-101	PROFIED THERMOPLASTIC,STANDARD- ASPHALT SURFACES, WHITE, SOLID,6"	GM	14.003
	0701- 18-201	PROFIED THERMOPLASTIC,STANDARD- ASPHALT SURFACES, YELLOW, SOLID,6"	GM	6.055
	0701- 18-221	PROFIED THERMOPLASTIC,STANDARD- ASPHALT SURFACES, YELLOW, SKIP,6"	GM	5.297
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	15.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43776115201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	1,155.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	665.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	571.000
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	7.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	3.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.024
	0711- 11-421	THERMOPLASTIC, STANDARD, BLUE, SOLID,6"	LF	222.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	525.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	41.000
	0711- 14-191	THERMOPLASTIC, PREFORMED, 6" WHITE, RAILROAD DYNAMIC ENVELOPE	LF	45.000
	0711- 14-193	THERMOPLASTIC, PREFORMED, 12" WHITE ON ASPHALT PAVEMENT RAILROAD DYNAMIC ENVELOPE	LF	99.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	2.876
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	2.781
Section 0003 Signalization				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	156.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	619.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	3.000
	0632- 7- 6	SIGNAL CABLE, REMOVE- INTERSECTION	PI	3.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	22.000
	0641- 2- 60	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- PEDESTAL/SERVICE POLE	EA	3.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	10.000
	0646- 1- 12	ALUMINUM SIGNALS POLE, FURNISH & INSTALL PEDESTRIAN DETECTOR POST	EA	8.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	4.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	6.000
	0653- 1- 12	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAYS	AS	4.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	12.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	18.000
	0665- 1- 60	PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN	EA	4.000

Call Order: 013 Proposal: T3761

ALT	Item	Description	Unit	Quantity
	0670- 5-400	TRAFFIC CONTROLLER ASSEMBLY, MODIFY	AS	3.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	4.000