

Call Order: 017 Proposal: T4560

ALT	Item	Description	Unit	Quantity
	0530- 74-	BEDDING STONE	TN	297.000
	0630- 2- 16	CONDUIT, FURNISH & INSTALL, EMBEDDED CONCRETE BARRIERS AND TRAFFIC RAILINGS	LF	380.000
	0635- 3- 13	JUNCTION BOX, FURNISH & INSTALL, EMBEDDED	EA	2.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (44004315201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44004315201)	LS	1.000
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	14.000
	0102- 60-	WORK ZONE SIGN	ED	48,682.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	8,676.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	992.000
	0102-115-	TYPE III BARRICADE	ED	2,892.000
	0104- 10- 3	SEDIMENT BARRIER	LF	543.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	431.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	2.000
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (44004315201)	LS	1.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (44004315201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (44004315201)	LS	1.000
	0110- 2- 2	SELECTIVE CLEARING AND GRUBBING, AREAS WITH TREES TO REMAIN	AC	0.090
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	291.000
	0110- 21-	TREE PROTECTION BARRIER	LF	249.000
	0110- 23-	TREE REMOVAL	EA	2.000
	0120- 1-	REGULAR EXCAVATION	CY	128.600
	0120- 6-	EMBANKMENT	CY	251.200
	0160- 4-	TYPE B STABILIZATION	SY	826.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	227.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	642.000
	0327- 70- 12	MILLING EXIST ASPH PAVT, 1 1/4" AVG DEPTH	SY	840.000
	0334- 1- 11	SUPERPAVE ASPHALTIC CONC, TRAFFIC A	TN	14.800
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	24.400
	0337- 7- 80	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-9.5, PG 76-22	TN	84.700
	0425- 1-521	INLETS, DT BOT, TYPE C, <10'	EA	4.000
	0425- 1-525	INLETS, DITCH BOTTOM, TYPE C, PARTIAL	EA	1.000
	0425- 1-541	INLETS, DT BOT, TYPE D, <10'	EA	2.000
	0425- 2- 41	MANHOLES, P-7, <10'	EA	1.000
	0425- 2- 62	MANHOLES, P-8, >10'	EA	2.000
	0425- 2- 91	MANHOLES, J-8, <10'	EA	1.000
	0430-175-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD	LF	181.000
	0430-175-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"S/CD	LF	24.000
	0430-175-218	PIPE CULVERT, OPTIONAL MATERIAL, OTHER-ELIP/ARCH, 18"S/CD	LF	20.000

Call Order: 017 Proposal: T4560

ALT	Item	Description	Unit	Quantity
	0430-175-224	PIPE CULVERT,OPTIONAL MATERIAL,OTHER SHAPE-ELIP/ARCH, 24"S/CD	LF	20.000
	0430-524-100	STRAIGHT CONCRETE ENDWALLS, 24", SINGLE, 0 DEGREES, ROUND	EA	1.000
	0443- 70- 4	FRENCH DRAIN, 24"	LF	214.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	76.000
	0520- 3-	VALLEY GUTTER- CONCRETE	LF	59.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	161.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	178.000
	0524- 1- 1	CONCRETE DITCH PAVT, NON REINFORCED, 3"	SY	6.000
	0527- 2-	DETECTABLE WARNINGS	SF	80.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	1,553.000
	0590- 70-202	IRRIGATION SYSTEM- MODIFY EXISTING SYSTEM, PROJECT 440043-1-52-01 (44004315201)	LS	1.000
	0999- 16-	PARTNERING, DO NOT BID (44004315201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44004315201)	LS	1.000
Section 0003 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	6.000
	0700- 1- 31	SINGLE POST SIGN, F&I BRIDGE MOUNT INDEX 11870/700-012, UP TO 12 SF	AS	4.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	3.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	5.000
	0705- 10- 3	OBJECT MARKER, TYPE 3	EA	4.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44004315201)	LS	1.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	24.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.154
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.137
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.066
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.066
Section 0004 Lighting				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	190.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	55.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	4.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	90.000
	0715- 1- 11	LIGHTING CONDUCTORS, F&I, INSULATED, NO. 10 OR <	LF	2,667.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	1.000
	0715- 11- 26	LUMINAIRE- TRAFFIC RAILING MOUNT, F&I, PROJECT 440043-1-52-01	EA	18.000