

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

Letting:	CT210127	Call Order: 022	Proposal: T5708	District:05
Counties:	SUMTER			
Road Name:	SR 44			
Limits:	FROM THE CITRUS CO LINE TO W OF I-75			
Project(s):	44101415201(*)	Federal Aid No: D520016B		
Total Roadway Length:	8.062 Miles	Contract Days:	210	
Total Bridge Length:	0.000 Miles	Letting Date:	01/27/21	
Total Proposal Length:	8.062 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	30 Calendar Days	

Proposal Budget Estimate: \$8,526,534.00

Please read the full advertisement

**Description:**

The improvements under this contract consist of milling & resurfacing, shoulder treatment, drainage improvements, flexible pavement reconstruction, curb & gutter and signing/pavement markings on SR 44.

**Call Order: 022 Proposal: T5708**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Roadway</b>				
	0101- 1-	MOBILIZATION (44101415201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44101415201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	14,035.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	20,650.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	380.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	828.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	800.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	800.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	60.000
	0104- 10- 3	SEDIMENT BARRIER	LF	1,281.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	50.000
	0107- 1-	LITTER REMOVAL	AC	1,070.490
	0107- 2-	MOWING	AC	963.280
	0110- 1- 1	CLEARING & GRUBBING (44101415201)	LS	1.000
	0110- 7- 1	MAILBOX, F&I SINGLE	EA	21.000
	0120- 1-	REGULAR EXCAVATION	CY	766.500
	0120- 6-	EMBANKMENT	CY	467.400
	0160- 4-	TYPE B STABILIZATION	SY	4,384.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	433.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	1,351.000
	0285-710-	OPTIONAL BASE, BASE GROUP 10	SY	1,005.000
	0327- 70- 2	MILLING EXIST ASPH PAVT, 3 1/2" AVG DEPTH	SY	1,311.000
	0327- 70- 4	MILLING EXIST ASPH PAVT, 3" AVG DEPTH	SY	240,206.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	15,758.000
	0327- 70- 11	MILLING EXIST ASPH PAVT, 2 1/4" AVG DEPTH	SY	43,584.000

**Call Order: 022 Proposal: T5708**

ALT	Item	Description	Unit	Quantity
	0327- 70- 22	MILLING EXISTING ASPHALT PAVEMENT, 4 1/4" AVG DEPTH	SY	35,153.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	40,959.500
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	12,677.300
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	1,107.500
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	40.800
	0425- 1-551	INLETS, DT BOT, TYPE E, <10'	EA	1.000
	0425- 2- 73	MANHOLES, J-7, PARTIAL	EA	1.000
	0425- 7-	MANHOLE COVER- REPLACE	EA	1.000
	0430-174-115	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 15"SD	LF	16.000
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	28.000
	0430-174-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"SD	LF	32.000
	0430-984-123	MITERED END SECTION, OPTIONAL ROUND, 15" SD	EA	1.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	1.000
	0430-984-129	MITERED END SECTION, OPTIONAL ROUND, 24" SD	EA	1.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	573.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	44,479.000
	0570- 1- 3	PERFORMANCE TURF, SOD AND SOIL- SHOULDER TREATMENT INDEX 570-010	SY	23,540.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	91.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	75.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	3.000
	0695- 1- 1	TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL	EA	4.000
	0695- 6- 12	TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 2 LOOPS	EA	4.000
	0695- 7-162	TRAFFIC MONITORING SITE CABINET, F&I, TYPE 3, 2 PANE BACK, PEDESTAL MOUNT	EA	1.000
	0695- 7-600	TRAFFIC MONITORING SITE CABINET, REMOVE EXISTING CABINET	EA	2.000
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.393
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	554.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44101415201)	LS	1.000
<b>Section 0002 Signing</b>				
	0546- 72- 3	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL	GM	25.928
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	39.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	22.000
	0700- 1- 13	SINGLE POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	11.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	63.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	41.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	519.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44101415201)	LS	1.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	892.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	292.000

**Call Order: 022 Proposal: T5708**

ALT	Item	Description	Unit	Quantity
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	1.076
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	182.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	789.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	1.402
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	18.114
	0711- 15-102	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SOLID, 8"	GM	0.583
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	15.099
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	14.868
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.903
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.075
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.253
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.736
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	0.283