

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

|                           |  |                            |                  |             |
|---------------------------|--|----------------------------|------------------|-------------|
| Letting:                  | CT210127                                     | Call Order: 036            | Proposal: T7468  | District:07 |
| Counties:                 | HERNANDO                                     |                            |                  |             |
| Road Name:                | SR 45/US 41/BROAD ST                         |                            |                  |             |
| Limits:                   | FROM N OF INGRAM ST TO OAKS MOBILE HOME PARK |                            |                  |             |
| Project(s):               | 44138615201(*)                               | Federal Aid No: D720038B   |                  |             |
| Total Roadway Length:     | 1.952 Miles                                  | Contract Days:             | 498              |             |
| Total Bridge Length:      | 0.000 Miles                                  | Letting Date:              | 01/27/21         |             |
| Total Proposal Length:    | 1.952 Miles                                  | Contract Execution Days:   | 10               |             |
|                           |  | Special Start Date:        | N/A              |             |
|                           |  | Aquis/Flexible Start Time: | 90 Calendar Days |             |
| Proposal Budget Estimate: | \$8,950,000.00                               |                            |                  |             |

Please read the full advertisement

**Description:**

The improvements under this contract consist of milling and resurfacing, asphalt to concrete reconstruction, sidewalk improvements, signal upgrades, and signing and pavement markings on SR 45/US 41/Broad St.

**Call Order: 036 Proposal: T7468**

| ALT                         | Item         | Description  | Unit | Quantity    |
|-----------------------------|--------------|--|------|-------------|
| <b>Section 0001 Roadway</b> |              |  |      |             |
|                             | 0101- 1-     | MOBILIZATION (44138615201)   | LS   | 1.000       |
|                             | 0102- 1-     | MAINTENANCE OF TRAFFIC (44138615201)                                   | LS   | 1.000       |
|                             | 0102- 2-200  | SPECIAL DETOUR- TEMPORARY PAVEMENT (44138615201)                       | LS   | 1.000       |
|                             | 0102- 2-300  | SPECIAL DETOUR- TEMPORARY EARTHWORK/BASE (44138615201)                 | LS   | 1.000       |
|                             | 0102- 3-     | COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE                 | CY   | 201.000     |
|                             | 0102- 4-     | PEDESTRIAN SPECIAL DETOUR (44138615201)                                | LS   | 1.000       |
|                             | 0102- 14-    | TRAFFIC CONTROL OFFICER  | HR   | 552.000     |
|                             | 0102- 60-    | WORK ZONE SIGN   | ED   | 53,428.000  |
|                             | 0102- 61-    | BUSINESS SIGN  | EA   | 9.000       |
|                             | 0102- 71- 13 | TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE                          | LF   | 4,020.000   |
|                             | 0102- 71- 23 | TEMPORARY BARRIER, RELOCATE, LOW PROFILE CONCRETE                      | LF   | 3,480.000   |
|                             | 0102- 74- 1  | CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD                 | ED   | 203,352.000 |
|                             | 0102- 74- 8  | CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE) | FD   | 71,700.000  |
|                             | 0102- 75- 1  | TEMPORARY SEPARATOR, F&I REMOVE  | LF   | 4,650.000   |
|                             | 0102- 76-    | ARROW BOARD / ADVANCE WARNING ARROW PANEL                              | ED   | 1,372.000   |
|                             | 0102- 78-    | TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER                       | EA   | 6,459.000   |
|                             | 0102- 99-    | PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY                            | ED   | 1,904.000   |
|                             | 0102-104-    | TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION                  | ED   | 2,988.000   |
|                             | 0102-107- 1  | TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION              | ED   | 2,988.000   |
|                             | 0102-115-    | TYPE III BARRICADE   | ED   | 1,900.000   |
|                             | 0104- 10- 3  | SEDIMENT BARRIER   | LF   | 3,523.000   |
|                             | 0104- 15-    | SOIL TRACKING PREVENTION DEVICE  | EA   | 2.000       |
|                             | 0104- 18-    | INLET PROTECTION SYSTEM  | EA   | 101.000     |

**Call Order: 036 Proposal: T7468**

| ALT | Item         | Description   | Unit | Quantity   |
|-----|--------------|---|------|------------|
|     | 0107- 1-     | LITTER REMOVAL  | AC   | 169.860    |
|     | 0107- 2-     | MOWING  | AC   | 80.440     |
|     | 0110- 1- 1   | CLEARING & GRUBBING (44138615201)                               | LS   | 1.000      |
|     | 0110- 4- 10  | REMOVAL OF EXISTING CONCRETE                                    | SY   | 3,649.000  |
|     | 0110- 7- 1   | MAILBOX, F&I SINGLE   | EA   | 2.000      |
|     | 0120- 1-     | REGULAR EXCAVATION  | CY   | 32.000     |
|     | 0120- 6-     | EMBANKMENT  | CY   | 24.000     |
|     | 0160- 4-     | TYPE B STABILIZATION  | SY   | 26,741.000 |
|     | 0285-701-    | OPTIONAL BASE, BASE GROUP 01                                    | SY   | 21,364.000 |
|     | 0285-715-    | OPTIONAL BASE, BASE GROUP 15                                    | SY   | 677.000    |
|     | 0327- 70- 4  | MILLING EXIST ASPH PAVT, 3" AVG DEPTH                           | SY   | 90,381.000 |
|     | 0327- 70- 6  | MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH                       | SY   | 509.000    |
|     | 0334- 1- 13  | SUPERPAVE ASPHALTIC CONC, TRAFFIC C                             | TN   | 7,583.000  |
|     | 0337- 7- 83  | ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22  | TN   | 7,492.600  |
|     | 0350- 3- 9   | PLAIN CEMENT CONCRETE PAVEMENT, 10"                             | SY   | 21,309.000 |
|     | 0350- 5-     | CLEANING & SEALING JOINTS- CONCRETE PAVEMENT                    | LF   | 31,015.000 |
|     | 0352- 70-    | GRINDING CONCRETE PAVEMENT                                      | SY   | 21,309.000 |
|     | 0425- 1-351  | INLETS, CURB, TYPE P-5, <10'                                    | EA   | 1.000      |
|     | 0425- 1-355  | INLETS, CURB, TYPE P-5, PARTIAL                                 | EA   | 4.000      |
|     | 0425- 1-455  | INLETS, CURB, TYPE J-5, PARTIAL                                 | EA   | 4.000      |
|     | 0425- 1-465  | INLETS, CURB, TYPE J-6, PARTIAL                                 | EA   | 2.000      |
|     | 0425- 1-531  | INLETS, DITCH BOTTOM, TYPE C MODIFIED- BACK OF SIDEWALK, <10'   | EA   | 1.000      |
|     | 0425- 1-535  | INLETS, DITCH BOTTOM TYPE C MODIFIED- BACK OF SIDEWALK, PARTIAL | EA   | 1.000      |
|     | 0425- 1-711  | INLETS, GUTTER, TYPE V, <10'                                    | EA   | 1.000      |
|     | 0425- 2- 73  | MANHOLES, J-7, PARTIAL  | EA   | 2.000      |
|     | 0425- 5-     | MANHOLE, ADJUST   | EA   | 12.000     |
|     | 0430-174-118 | PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD                   | LF   | 122.000    |
|     | 0446- 1- 1   | EDGEDRAIN DRAINCRETE, STANDARD                                  | LF   | 4,030.000  |
|     | 0446- 71- 1  | EDGEDRAIN OUTLET PIPE, 4"                                       | LF   | 176.000    |
|     | 0515- 1- 1   | PIPE HANDRAIL - GUIDERAIL, STEEL                                | LF   | 30.000     |
|     | 0520- 1- 7   | CONCRETE CURB & GUTTER, TYPE E                                  | LF   | 4,397.000  |
|     | 0520- 1- 10  | CONCRETE CURB & GUTTER, TYPE F                                  | LF   | 4,410.000  |
|     | 0520- 5- 21  | TRAFFIC SEPARATOR - CONCRETE, TYPE II, 4' WIDE                  | LF   | 1,141.000  |
|     | 0520- 5- 22  | TRAFFIC SEPARATOR - CONCRETE, TYPE II, 6' WIDE                  | LF   | 738.000    |
|     | 0520- 70-    | CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH             | SY   | 298.000    |
|     | 0522- 1-     | CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK                       | SY   | 394.000    |
|     | 0522- 2-     | CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK                       | SY   | 896.000    |
|     | 0527- 2-     | DETECTABLE WARNINGS   | SF   | 624.000    |
|     | 0570- 1- 2   | PERFORMANCE TURF, SOD   | SY   | 5,093.000  |
|     | 0630- 2- 11  | CONDUIT, FURNISH & INSTALL, OPEN TRENCH                         | LF   | 245.000    |
|     | 0630- 2- 12  | CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE                    | LF   | 488.000    |
|     | 0635- 2- 11  | PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE                    | EA   | 7.000      |

**Call Order: 036 Proposal: T7468**

| ALT                         | Item         | Description   | Unit | Quantity   |
|-----------------------------|--------------|---|------|------------|
|                             | 0695- 1- 1   | TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL                        | EA   | 14.000     |
|                             | 0695- 6- 12  | TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 2 LOOPS                 | EA   | 14.000     |
|                             | 0695- 7-132  | TRAFFIC MONITORING SITE CABINET, FURNISH & INSTALL, TYPE 3, PEDESTAL MOUNT                  | EA   | 3.000      |
|                             | 0710- 11-101 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"                                       | GM   | 19.192     |
|                             | 0710- 11-102 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"      | GM   | 0.922      |
|                             | 0710- 11-123 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"         | LF   | 10,748.000 |
|                             | 0710- 11-124 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"              | LF   | 1,504.000  |
|                             | 0710- 11-125 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"           | LF   | 1,916.000  |
|                             | 0710- 11-131 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE                | GM   | 10.785     |
|                             | 0710- 11-141 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6" | GM   | 0.515      |
|                             | 0710- 11-160 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL                               | EA   | 43.000     |
|                             | 0710- 11-170 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS  | EA   | 258.000    |
|                             | 0710- 11-201 | PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"                                      | GM   | 12.355     |
|                             | 0710- 11-224 | PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"             | LF   | 1,874.000  |
|                             | 0710- 11-241 | PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6" | GM   | 1.379      |
|                             | 0710- 11-331 | PAINTED PAVEMENT MARKINGS, STANDARD, BLACK, SKIP, 6"  | GM   | 0.886      |
|                             | 0710- 11-341 | PAINTED PAVEMENT MARKINGS, STANDARD, BLACK, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6" | GM   | 0.149      |
|                             | 0999- 25-    | INITIAL CONTINGENCY AMOUNT, DO NOT BID (44138615201)  | LS   | 1.000      |
| <b>Section 0002 Signing</b> |              |   |      |            |
|                             | 0700- 1- 11  | SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF   | AS   | 19.000     |
|                             | 0700- 1- 12  | SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF  | AS   | 6.000      |
|                             | 0700- 1- 13  | SINGLE POST SIGN, F&I GROUND MOUNT, 21-30 SF  | AS   | 4.000      |
|                             | 0700- 1- 14  | SINGLE POST SIGN, F&I GROUND MOUNT, 31+ SF  | AS   | 2.000      |
|                             | 0700- 1- 50  | SINGLE POST SIGN, RELOCATE  | AS   | 5.000      |
|                             | 0700- 1- 60  | SINGLE POST SIGN, REMOVE  | AS   | 21.000     |
|                             | 0700- 2- 60  | MULTI- POST SIGN, REMOVE  | AS   | 1.000      |
|                             | 0700- 3-101  | SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF                                     | EA   | 82.000     |
|                             | 0700- 3-102  | SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 12-20 SF  | EA   | 5.000      |
|                             | 0700- 3-103  | SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 21-30 SF  | EA   | 2.000      |
|                             | 0700- 3-206  | SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 101-200 SF                                    | EA   | 1.000      |
|                             | 0700- 3-207  | SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 201-300 SF                                    | EA   | 1.000      |
|                             | 0700- 3-601  | SIGN PANEL, REMOVE, UP TO 12 SF   | EA   | 81.000     |
|                             | 0700- 3-602  | SIGN PANEL, REMOVE, 12-20 SF  | EA   | 5.000      |
|                             | 0700- 3-603  | SIGN PANEL, REMOVE, 21-30 SF  | EA   | 2.000      |
|                             | 0700- 3-626  | SIGN PANEL, REMOVE, 101-200 SF WITH LIGHTING  | EA   | 1.000      |
|                             | 0700- 3-627  | SIGN PANEL, REMOVE PANEL, 201-300 SF WITH LIGHTING  | EA   | 1.000      |

**Call Order: 036 Proposal: T7468**

| ALT                               | Item         | Description   | Unit | Quantity  |
|-----------------------------------|--------------|---|------|-----------|
|                                   | 0705- 10- 1  | OBJECT MARKER, TYPE 1   | EA   | 11.000    |
|                                   | 0705- 11- 1  | DELINEATOR, FLEXIBLE TUBULAR  | EA   | 3.000     |
|                                   | 0705- 11- 3  | DELINEATOR, FLEXIBLE HIGH VISIBILITY MEDIAN   | EA   | 13.000    |
|                                   | 0710- 11-190 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ISLAND NOSE                                     | SF   | 27.000    |
|                                   | 0710- 11-290 | PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE                                    | SF   | 349.000   |
|                                   | 0710- 90-    | PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44138615201)                                      | LS   | 1.000     |
|                                   | 0711- 11-123 | THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT                     | LF   | 5,374.000 |
|                                   | 0711- 11-124 | THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS                       | LF   | 752.000   |
|                                   | 0711- 11-125 | THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK                      | LF   | 843.000   |
|                                   | 0711- 11-141 | THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"                | GM   | 1.048     |
|                                   | 0711- 11-160 | THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL   | EA   | 5.000     |
|                                   | 0711- 11-170 | THERMOPLASTIC, STANDARD, WHITE, ARROW   | EA   | 74.000    |
|                                   | 0711- 11-224 | THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON                         | LF   | 937.000   |
|                                   | 0711- 11-241 | THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"      | GM   | 0.584     |
|                                   | 0711- 14-125 | THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK                                   | LF   | 3,526.000 |
|                                   | 0711- 14-141 | THERMOPLASTIC, PREFORMED, WHITE, 2-4 DOTTED GUIDELINE ON CONCRETE SURFACES                  | GM   | 0.125     |
|                                   | 0711- 14-160 | THERMOPLASTIC, PREFORMED, WHITE, MESSAGE  | EA   | 33.000    |
|                                   | 0711- 14-170 | THERMOPLASTIC, PREFORMED, WHITE, ARROW  | EA   | 33.000    |
|                                   | 0711- 14-341 | THERMOPLASTIC, PREFORMED, BLACK, 2-4 DOTTED GUIDELINE ON CONCRETE SURFACES                  | GM   | 0.125     |
|                                   | 0711- 14-560 | THERMOPLASTIC, PREFORMED, WHITE WITH BLACK CONTRAST ON CONCRETE PAVEMENT, MESSAGE OR SYMBOL | EA   | 7.000     |
|                                   | 0711- 14-570 | THERMOPLASTIC, PREFORMED, WHITE WITH BLACK CONTRAST, ARROW ON CONCRETE SURFACE              | EA   | 19.000    |
|                                   | 0711- 16-101 | THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"                                    | GM   | 6.116     |
|                                   | 0711- 16-102 | THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"                                    | GM   | 0.461     |
|                                   | 0711- 16-131 | THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP         | GM   | 4.358     |
|                                   | 0711- 16-201 | THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"                                   | GM   | 4.186     |
|                                   | 0711- 16-231 | THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"                                    | GM   | 0.300     |
|                                   | 0713-103-131 | PERMANENT TAPE, WHITE, SKIP/DOTTED, 6" FOR CONCRETE SURFACES                                | GM   | 1.307     |
|                                   | 0713-103-331 | PERMANENT TAPE, BLACK, SKIP/DOTTED, 6" FOR CONCRETE SURFACES                                | GM   | 1.307     |
| <b>Section 0003 Signalization</b> |              |   |      |           |
|                                   | 0630- 2- 11  | CONDUIT, FURNISH & INSTALL, OPEN TRENCH   | LF   | 551.000   |
|                                   | 0630- 2- 12  | CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE  | LF   | 957.000   |
|                                   | 0632- 7- 1   | SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL                          | PI   | 5.000     |
|                                   | 0632- 7- 6   | SIGNAL CABLE, REMOVE- INTERSECTION  | PI   | 5.000     |

**Call Order: 036 Proposal: T7468**

| ALT | Item        | Description  | Unit | Quantity |
|-----|-------------|--|------|----------|
|     | 0635- 2- 11 | PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE                                   | EA   | 36.000   |
|     | 0646- 1- 11 | ALUMINUM SIGNALS POLE, PEDESTAL  | EA   | 7.000    |
|     | 0646- 1- 12 | ALUMINUM SIGNALS POLE, FURNISH & INSTALL PEDESTRIAN DETECTOR POST              | EA   | 15.000   |
|     | 0646- 1- 60 | ALUMINUM SIGNALS POLE, REMOVE  | EA   | 6.000    |
|     | 0650- 1- 14 | VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY         | AS   | 34.000   |
|     | 0650- 1- 16 | VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 4 SECTION, 1 WAY         | AS   | 2.000    |
|     | 0650- 1- 19 | VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 5 SECTION CLUSTER, 1 WAY | AS   | 3.000    |
|     | 0650- 1- 60 | VEHICULAR TRAFFIC SIGNAL, REMOVE- POLES TO REMAIN                              | AS   | 36.000   |
|     | 0653- 1- 11 | PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY                      | AS   | 26.000   |
|     | 0653- 1- 60 | PEDESTRIAN SIGNAL, REMOVE PED SIGNAL- POLE/PEDESTAL TO REMAIN                  | AS   | 15.000   |
|     | 0660- 2-102 | LOOP ASSEMBLY, F&I, TYPE B   | AS   | 6.000    |
|     | 0660- 4- 11 | VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL CABINET EQUIPMENT           | EA   | 17.000   |
|     | 0660- 4- 12 | VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT      | EA   | 17.000   |
|     | 0660- 4- 60 | VEHICLE DETECTION SYSTEM- VIDEO, REMOVE  | EA   | 2.000    |
|     | 0665- 1- 11 | PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD                               | EA   | 26.000   |
|     | 0665- 1- 60 | PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN                           | EA   | 14.000   |
|     | 0670- 5-400 | TRAFFIC CONTROLLER ASSEMBLY, MODIFY  | AS   | 5.000    |
|     | 0700- 5- 22 | INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF       | EA   | 13.000   |