

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: CT210609 Call Order: 007 Proposal: T2808 District:02

Counties: DUVAL

Road Name: EDGEWOOD AVE SOUTH

Limits: FROM SR 15 (US 17/ROOSEVELT BLVD) TO SR 111 (CASSAT AVE)

Project(s): 44351715201(*) Federal Aid No: D220106B

Project(s): 44351715601 Federal Aid No: N/A

Total Roadway Length:	1.519 Miles	Contract Days:	365
Total Bridge Length:	0.000 Miles	Letting Date:	06/09/21
Total Proposal Length:	1.519 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	15 Days

Proposal Budget Estimate: \$3,918,617.00

Please read the full advertisement

Description:

JEA Standards. Table A -- Schedule of Values is required to be submitted with the bid, as per Technical Special Provision T1000-17.

Please upload completed Table A as a zip file within your EBSx File using the "File Attachment Upload" tab before submitting your bid.

Railroad insurance is required for this Proposal at time of contract execution. Please see the Specifications Package for more information.

The improvements under this contract consist of milling and resurfacing, base work, drainage grate replacement, curb and gutters, traffic and pedestrian signals, lighting for signalized pedestrian crosswalks, special bridge underdeck lighting, signing and pavement marking, bridge and retaining wall cleaning and coating, sidewalk replacement, new sidewalks, utilities, and other incidental construction on Edgewood Avenue South in Duval County from SR 15/US 17 Roosevelt to SR 111 (Cassat Ave).

Call Order: 007 Proposal: T2808

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44351715201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44351715201)	LS	1.000
	0102- 2-200	SPECIAL DETOUR- TEMPORARY PAVEMENT	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	156.000
	0102- 60-	WORK ZONE SIGN	ED	78,099.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	121,442.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	182,023.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	795.000
	0102- 78-	TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER	EA	22.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	756.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	2,555.000
	0102-115-	TYPE III BARRICADE	ED	10,410.000
	0102-913- 23	REMOVABLE TAPE, WHITE, 24" STOP BAR	LF	40.000
	0102-913- 24	REMOVABLE TAPE, WHITE, 12" CROSSWALK	LF	811.000
	0102-913- 29	REMOVABLE TAPE, WHITE, MESSAGE, SYMBOL OR ARROW	EA	4.000

Call Order: 007 Proposal: T2808

ALT	Item	Description	Unit	Quantity
	0102-913- 31	REMOVABLE TAPE, YELLOW, SOLID, 6"	GM	0.009
	0104- 10- 3	SEDIMENT BARRIER	LF	199.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	60.000
	0107- 1-	LITTER REMOVAL	AC	81.900
	0107- 2-	MOWING	AC	22.360
	0110- 1- 1	CLEARING & GRUBBING (44351715201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	2,068.000
	0110- 21-	TREE PROTECTION BARRIER	LF	216.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	472.000
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (44351715201)	LS	1.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	1,006.000
	0327- 70- 4	MILLING EXISTING ASPHALT PAVEMENT, 3" AVG DEPTH	SY	1,859.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	49,034.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	153.400
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	4,200.000
	0400-143-	CLEANING & COATING CONCRETE SURFACE, CLASS 5	SF	80,851.000
	0425- 5-	MANHOLE, ADJUST	EA	23.000
	0425- 5- 1	MANHOLE, ADJUST, UTILITIES	EA	29.000
	0425- 6-	VALVE BOXES, ADJUST	EA	38.000
	0425- 82-	REPLACE GRATE	EA	15.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	1,563.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	1,156.000
	0520- 2- 2	CONCRETE CURB, TYPE B	LF	28.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	276.000
	0520- 70-	CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH	SY	31.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	1,241.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	1,801.000
	0523- 1-	PATTERNED PAVEMENT, VEHICULAR AREAS	SY	226.000
	0526- 1- 2	PAVERS, ARCHITECTURAL, SIDEWALK	SY	25.000
	0527- 2-	DETECTABLE WARNINGS	SF	948.000
	0542- 70-	BUMPER GUARDS, CONCRETE	EA	47.000
	0563- 4-	ANTI-GRAFFITI COATING, NON-SACRIFICIAL	SF	24,435.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	2,181.000
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	28.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	16.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.169
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44351715201)	LS	1.000
Section 0002 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	30.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	4.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	26.000
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	1.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	23.000

Call Order: 007 Proposal: T2808

ALT	Item	Description	Unit	Quantity
	0705- 11- 2	DELINEATOR, NON-FLEXIBLE	EA	12.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	351.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44351715201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	3,172.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	2,625.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	1,113.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.270
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	22.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	65.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	786.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.258
	0711- 11-421	THERMOPLASTIC, STANDARD, BLUE, SOLID,6"	LF	741.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	1,293.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	67.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	57.000
	0711- 14-570	THERMOPLASTIC, PREFORMED, WHITE WITH BLACK CONTRAST, ARROW ON CONCRETE SURFACE	EA	8.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	5.519
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.348
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.053
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	2.708
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	0.875
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	1,274.000
	0713-107-	PREFORMED/PERMANENT TAPE, REMOVE	SF	1,256.000
Section 0003 Lighting				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	5.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	169.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	4.000
	0639- 1-121	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER FURNISHED BY POWER COMPANY	AS	1.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	1.000
	0641- 2- 11	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II PEDESTAL	EA	1.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	348.000
	0715- 52- 10	LIGHTING-SPECIAL, UNDERDECK LIGHTING ON EDGEWOOD AVENUE S, PROJECT 443517-1-52-01	LS	1.000
Section 0004 Signalization				
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	583.000
	0630- 2- 14	CONDUIT, FURNISH & INSTALL, ABOVEGROUND	LF	25.000

Call Order: 007 Proposal: T2808

ALT	Item	Description	Unit	Quantity
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	5.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	16.000
	0641- 2- 60	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- PEDESTAL/SERVICE POLE	EA	5.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	19.000
	0646- 1- 12	ALUMINUM SIGNALS POLE, FURNISH & INSTALL PEDESTRIAN DETECTOR POST	EA	2.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	4.000
	0650- 1- 70	VEHICULAR TRAFFIC SIGNAL, RELOCATE- INCLUDES REMOVAL AND REINSTALLATION	AS	15.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	22.000
	0653- 1- 12	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAYS	AS	6.000
	0653- 1- 60	PEDESTRIAN SIGNAL, REMOVE PED SIGNAL- POLE/PEDESTAL TO REMAIN	AS	17.000
	0654- 2- 21	MIDBLOCK CROSSWALK: RECTANGULAR RAPID FLASHING BEACON, FURNISH & INSTALL- SOLAR, COMPLETE SIGN ASSY- SINGLE DIRECTION	AS	4.000
	0654- 2- 22	MIDBLOCK CROSSWALK: RECTANGULAR RAPID FLASHING BEACON, FURNISH & INSTALL- SOLAR, COMPLETE SIGN ASSEMBLY- BACK TO BACK	AS	7.000
	0660- 1-104	LOOP DETECTOR, INDUCTIVE, F&I, TYPE 4, 2CHANNEL, SOLID STATE, SHELF MOUNTED, TIME DELAY	EA	21.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	29.000
	0660- 3- 11	VEHICLE DETECTION SYSTEM- MICROWAVE, FURNISH & INSTALL CABINET EQUIPMENT	EA	1.000
	0660- 3- 12	VEHICLE DETECTION SYSTEM- MICROWAVE, FURNISH & INSTALL, ABOVE GROUND EQUIPMENT	EA	4.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	32.000
	0665- 1- 50	PEDESTRIAN DETECTOR, ADJUST/MODIFY ON EXISTING POLE	EA	2.000
	0665- 1- 60	PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN	EA	13.000
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	3.000
Section 0005 Utilities				
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44351715601)	LS	1.000
	1000- 6-	UTILITY WORK- JPA/UTILITY AGREEMENT, WATER (44351715601)	LS	1.000
	1000- 7-	UTILITY WORK- JPA/UTILITY AGREEMENT, POWER (44351715201)	LS	1.000