

**Florida Department of Transportation
 Bid Solicitation Notice and Approximate Quantities**

Letting: CT210609 Call Order: 009 Proposal: T2855 District:02
 Counties: DUVAL
 Road Name: SR 103 (LANE AVE)
 Limits: FROM SR 208 (WILSON BLVD) TO SR 228 (NORMANDY BLVD)
 Project(s): 43935815201(*) Federal Aid No: D219137B
 Project(s): 43935815601 Federal Aid No: N/A
 Total Roadway Length: 2.517 Miles Contract Days: 350
 Total Bridge Length: 0.063 Miles Letting Date: 06/09/21
 Total Proposal Length: 2.580 Miles Contract Execution Days: 10
 Special Start Date: N/A
 Aquis/Flexible Start Time: 15 Calendar Days
 Proposal Budget Estimate: \$6,628,087.00

Please read the full advertisement

Description:

JEA Standards. Table A -- Schedule of Values is required to be submitted with the bid, as per Technical Special Provision T000-17.

Please upload completed Table A as a zip file within your EBSx File using the "File Attachment Upload" tab before submitting your bid.

The improvements under this contract consist of milling and resurfacing, base work, curb and gutters, sidewalk and bicycle path improvements, highway signing, traffic signal improvements, pedestrian signal upgrades, pedestrian lighting upgrades, and water main utility relocation along SR 103 (Lane Avenue) from SR 208 (Wilson Boulevard) to SR 228 (Normandy Boulevard) in Duval County.

Call Order: 009 Proposal: T2855

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (43935815201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43935815201)	LS	1.000
	0102- 2-200	SPECIAL DETOUR- TEMPORARY PAVEMENT (43935815201)	LS	1.000
	0102- 4-	PEDESTRIAN SPECIAL DETOUR (43935815201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	48.000
	0102- 60-	WORK ZONE SIGN	ED	42,855.000
	0102- 61-	BUSINESS SIGN	EA	46.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	2,364.000
	0102- 71- 23	TEMPORARY BARRIER, RELOCATE, LOW PROFILE CONCRETE	LF	360.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	66,635.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	192,432.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	335.000
	0102- 78-	TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER	EA	4,833.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	2,450.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	2,800.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	2,800.000
	0102-115-	TYPE III BARRICADE	ED	3,602.000

Call Order: 009 Proposal: T2855

ALT	Item	Description	Unit	Quantity
	0104- 10- 3	SEDIMENT BARRIER	LF	2,463.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	104.000
	0107- 1-	LITTER REMOVAL	AC	114.950
	0107- 2-	MOWING	AC	43.150
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (43935815201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (43935815201)	LS	1.000
	0110- 2- 2	SELECTIVE CLEARING AND GRUBBING, AREAS WITH TREES TO REMAIN	AC	0.010
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	1,388.000
	0110- 21-	TREE PROTECTION BARRIER	LF	1,203.000
	0120- 1-	REGULAR EXCAVATION	CY	16.400
	0160- 4-	TYPE B STABILIZATION	SY	272.000
	0285-710-	OPTIONAL BASE, BASE GROUP 10	SY	91.000
	0285-711-	OPTIONAL BASE, BASE GROUP 11	SY	3,893.000
	0327- 70- 4	MILLING EXISTING ASPHALT PAVEMENT, 3" AVG DEPTH	SY	103,819.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	529.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	8,558.000
	0337- 7- 81	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-12.5, PG 76-22	TN	8,602.000
	0425- 5-	MANHOLE, ADJUST	EA	7.000
	0425- 5- 1	MANHOLE, ADJUST, UTILITIES	EA	9.000
	0425- 6-	VALVE BOXES, ADJUST	EA	18.000
	0425- 82-	REPLACE GRATE	EA	5.000
	0515- 2-311	PEDESTRIAN/ BICYCLE RAILING, ALUMINUM ONLY, 42" TYPE 1	LF	288.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	284.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	618.000
	0520- 3-	VALLEY GUTTER- CONCRETE	LF	12.000
	0520- 5- 12	TRAFFIC SEPARATOR CONCRETE-TYPE I, 6' WIDE	LF	3.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	902.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	171.000
	0522- 3-	BUS BOARDING PAD- CONCRETE	SY	27.000
	0527- 2-	DETECTABLE WARNINGS	SF	991.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	516.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	14.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	12.077
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.177
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	10,635.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	6,088.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	8.371
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.094
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	18.000

Call Order: 009 Proposal: T2855

ALT	Item	Description	Unit	Quantity
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	81.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	9.714
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	1,025.000
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	1.300
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	2.459
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43935815201)	LS	1.000
Section 0002 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	12.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	1.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	8.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	55.000
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	17.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	54.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	2.000
	0710- 11-190	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ISLAND NOSE	SF	9.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	15.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43935815201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	6,470.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	1,503.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.022
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	14.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	120.000
	0711- 11-180	THERMOPLASTIC, STANDARD, WHITE, YIELD LINE	LF	36.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	714.000
	0711- 14-123	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 12" FOR CROSSWALK	LF	606.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	3,233.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	12.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	12.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	6.611
	0711- 15-102	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SOLID, 8"	GM	0.090
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	4.331
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	4.931
	0711- 15-231	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SKIP, 6"	GM	2.509
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	249.000

Call Order: 009 Proposal: T2855

ALT	Item	Description	Unit	Quantity
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.111
	0713-103-131	PERMANENT TAPE, WHITE, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	0.122
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.178
Section 0003 Lighting				
	1000- 7-	UTILITY WORK- JPA/UTILITY AGREEMENT, POWER (43935815201)	LS	1.000
Section 0004 Signalization				
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	710.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	8.000
	0632- 7- 6	SIGNAL CABLE, REMOVE- INTERSECTION	PI	8.000
	0634- 4-152	SPAN WIRE ASSEMBLY, F&I, TWO POINT, DIAGONAL	PI	1.000
	0634- 4-600	SPAN WIRE ASSEMBLY, REMOVE- POLES REMAIN	PI	1.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	9.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	6.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	6.000
	0653- 1- 12	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAYS	AS	2.000
	0653- 1- 60	PEDESTRIAN SIGNAL, REMOVE PED SIGNAL- POLE/PEDESTAL TO REMAIN	AS	10.000
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	8.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	70.000
	0660- 3- 11	VEHICLE DETECTION SYSTEM- MICROWAVE, FURNISH & INSTALL CABINET EQUIPMENT	EA	1.000
	0660- 3- 12	VEHICLE DETECTION SYSTEM- MICROWAVE, FURNISH & INSTALL, ABOVE GROUND EQUIPMENT	EA	1.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	21.000
	0665- 1- 60	PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN	EA	18.000
	0670- 5-400	TRAFFIC CONTROLLER ASSEMBLY, MODIFY	AS	8.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	29.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	5.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	66.000
	0700- 5- 21	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	20.000
	0700- 5- 22	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF	EA	8.000
	0700- 11-391	ELECTRONIC DISPLAY SIGN, FURNISH & INSTALL OVERHEAD MOUNT- AC POWERED, BLANK OUT SIGN, UP TO 12 SF	AS	5.000
	0700- 11-700	ELECTRONIC DISPLAY SIGN, REMOVE- OVERHEAD MOUNT	AS	3.000
Section 0005 Utilities				
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43935815601)	LS	1.000
	1000- 6-	UTILITY WORK- JPA/UTILITY AGREEMENT, WATER (43935815601)	LS	1.000