

Call Order: 012 Proposal: T3728

ALT	Item	Description	Unit	Quantity
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (21898425201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (21898425201)	LS	1.000
	0102- 2-128	SPECIAL DETOUR- TEMPORARY BRIDGE, PROJECT 218984-2-52-01 (21898425201)	LS	1.000
	0102- 2-200	SPECIAL DETOUR- TEMPORARY PAVEMENT (21898425201)	LS	1.000
	0102- 2-300	SPECIAL DETOUR- TEMPORARY EARTHWORK/BASE (21898425201)	LS	1.000
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	24.500
	0102- 60-	WORK ZONE SIGN	ED	14,608.000
	0102- 73-	TEMPORARY GUARDRAIL	LF	550.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	44,516.000
	0102- 78-	TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER	EA	1,856.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	840.000
	0102-115-	TYPE III BARRICADE	ED	7,520.000
	0104- 1-	ARTIFICIAL COVERINGS /ROLLED EROSION CONTROL PRODUCTS	SY	388.000
	0104- 10- 3	SEDIMENT BARRIER	LF	1,793.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	585.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	648.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	2.000
	0107- 1-	LITTER REMOVAL	AC	195.500
	0107- 2-	MOWING	AC	65.110
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (21898425201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (21898425201)	LS	1.000
	0120- 1-	REGULAR EXCAVATION	CY	6,441.800
	0120- 4-	SUBSOIL EXCAVATION	CY	3,438.000
	0120- 6-	EMBANKMENT	CY	8,453.300
	0160- 4-	TYPE B STABILIZATION	SY	3,876.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	1,249.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	2,290.000
	0286- 1-	TURNOUT CONSTRUCTION/DRIVEWAY BASE- OPTIONAL MATERIALS	SY	152.000
	0327- 70- 5	MILLING EXISTING ASPHALT PAVEMENT, 2" AVG DEPTH	SY	147.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	6,530.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	300.900
	0337- 7- 81	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-12.5, PG 76-22	TN	827.800
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	26.600
	0425- 1-701	INLETS, GUTTER, TYPE S, <10'	EA	4.000
	0430-174-218	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 18"SD	LF	88.000
	0430-175-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD	LF	68.000
	0430-175-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"S/CD	LF	58.000
	0430-982-129	MITERED END SECTION, OPTIONAL ROUND, 24" CD	EA	1.000
	0430-984-625	MITERED END SECT, OPTIONAL - ELLIPTICAL / ARCH, 18" SD	EA	2.000
	0520- 6-	SHOULDER GUTTER- CONCRETE	LF	157.000

Call Order: 012 Proposal: T3728

ALT	Item	Description	Unit	Quantity
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	32.100
	0530- 74-	BEDDING STONE	TN	23.100
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	669.000
	0536- 8-112	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-001, APPROACH TL-3	EA	4.000
	0536- 73-	GUARDRAIL REMOVAL	LF	558.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	4.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	37,897.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	7.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	1.916
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	39.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	2.401
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (21898425201)	LS	1.000
Section 0003 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	4.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	10.000
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	1.000
	0701- 18-101	PROFILED THERMOPLASTIC,STANDARD- ASPHALT SURFACES, WHITE, SOLID,6"	GM	0.880
	0701- 18-201	PROFILED THERMOPLASTIC,STANDARD- ASPHALT SURFACES, YELLOW, SOLID,6"	GM	0.405
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	3.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (21898425201)	LS	1.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	36.000
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	1.000
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.273
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	0.276
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	140.000
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.089
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.089