

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: CT210331 Call Order: 003 Proposal: T1795 District:01
 Counties: SARASOTA
 Road Name: SR 758
 Limits: AT VARIOUS LOCATIONS AS LISTED IN THE PLANS
 Project(s): 44012415201(*) Federal Aid No: D121015B
 Total Roadway Length: 3.044 Miles Contract Days: 100
 Total Bridge Length: 0.000 Miles Letting Date: 03/31/21
 Total Proposal Length: 3.044 Miles Contract Execution Days: 10
 Special Start Date: N/A
 Aquis/Flexible Start Time: 90 Days (Aqui Time)
 Proposal Budget Estimate: \$489,368.00

Please read the full advertisement

Description:

The improvements under this contract consist of construction of retrofit lighting systems at eight intersections along SR 758: S. Tamiami Trl., Shade Ave., Tuttle Ave., Murdock Ave., Lockwood Ridge Rd., Beneva Rd., Sawyer Rd., and McIntosh Rd. The project will include converting existing fixtures from HPS to LED and adding new light poles in Sarasota County.

Call Order: 003 Proposal: T1795

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44012415201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44012415201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	200.000
	0102- 60-	WORK ZONE SIGN	ED	1,900.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	6,100.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	54,500.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	200.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	200.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	800.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	800.000
	0102-115-	TYPE III BARRICADE	ED	300.000
	0104- 10- 3	SEDIMENT BARRIER	LF	194.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	29.000
	0107- 1-	LITTER REMOVAL	AC	0.610
	0107- 2-	MOWING	AC	0.130
	0110- 1- 1	CLEARING & GRUBBING (44012415201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	254.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	57.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	140.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	10.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	24.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44012415201)	LS	1.000

Call Order: 003 Proposal: T1795

ALT	Item	Description	Unit	Quantity
Section 0002 Lighting				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	124.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	2,983.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	37.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	11,673.000
	0715- 4- 11	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 30' MOUNTING HEIGHT	EA	3.000
	0715- 4- 12	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 35' MOUNTING HEIGHT	EA	1.000
	0715- 4- 13	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT	EA	3.000
	0715- 4- 14	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 45' MOUNTING HEIGHT	EA	1.000
	0715- 4- 22	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE SPECIAL FOUNDATION, 35' MOUNTING HEIGHT	EA	3.000
	0715- 4- 23	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE SPECIAL FOUNDATION, 40' MOUNTING HEIGHT	EA	2.000
	0715- 4- 24	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE SPECIAL FOUNDATION, 45' MOUNTING HEIGHT	EA	3.000
	0715- 4- 70	LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION	EA	2.000
	0715- 4-825	LIGHT POLE COMPLETE, FURNISH & INSTALL UTILITY CONFLICT POLE, INDEX 715-002 FOUND, 30' HT, PROJECT 440124-1-52-01	EA	2.000
	0715- 4-826	LIGHT POLE COMPLETE, FURNISH & INSTALL UTILITY CONFLICT POLE, SPECIAL FOUND, 30' HT, PROJECT 440124-1-52-01	EA	6.000
	0715- 11-211	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, COBRA HEAD	EA	15.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	24.000