

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

Letting:	CT210331	Call Order: 006	Proposal: T2782	District:02
Counties:	DUVAL			
Road Name:	US 1/US 17/SR 211/CR 211 (TALLEYRAND AVE)			
Limits:	JAXPORT TALLYRAND ITS			
Project(s):	43808425201(*)	Federal Aid No:	D219171B	
Project(s):	43808425601	Federal Aid No:	N/A	
Total Roadway Length:	5.425 Miles	Contract Days:	200	
Total Bridge Length:	0.000 Miles	Letting Date:	03/31/21	
Total Proposal Length:	5.425 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	120 Days	
Proposal Budget Estimate:	\$803,973.00			

Please read the full advertisement

**Description:**

JEA Standards. Table A -- Schedule of Values is required to be submitted with the bid, as per Technical Special Provision T1000-17.

Please upload completed Table A as a zip file within your EBS File using the "File Attachment Upload" tab before submitting your bid.

The improvements under this contract consist of ITS which includes Dynamic Message Signs (DMS) and CCTV cameras and other incidental construction on US1, US1 ALT and CR 211 (Talleyrand Avenue) in Duval County.

**Call Order: 006 Proposal: T2782**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Roadway</b>				
	0101- 1-	MOBILIZATION (43808425201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43808425201)	LS	1.000
	0102- 4-	PEDESTRIAN SPECIAL DETOUR (43808425201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	20.000
	0102- 60-	WORK ZONE SIGN	ED	478.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	447.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	1,572.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	56.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	56.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	10.000
	0107- 1-	LITTER REMOVAL	AC	9.440
	0107- 2-	MOWING	AC	7.310
	0110- 1- 1	CLEARING & GRUBBING (43808425201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	61.000
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	4.800
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	70.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	157.000
	0536- 85- 20	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE	EA	1.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	1.000

**Call Order: 006 Proposal: T2782**

ALT	Item	Description	Unit	Quantity
	0550- 10-221	FENCING, TYPE B, 5.1-6.0', W/ BARB WIRE ATTMT	LF	60.000
	0550- 10-238	FENCING, TYPE B, 6.1-7.0, RESET EXISTING	LF	20.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	95.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43808425201)	LS	1.000
<b>Section 0002 Utilities</b>				
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43808425601)	LS	1.000
	1000- 6-	UTILITY WORK- JPA/UTILITY AGREEMENT, WATER (43808425601)	LS	1.000
<b>Section 0003 Intelligent Transportation System</b>				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	133.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	549.000
	0630- 2- 14	CONDUIT, FURNISH & INSTALL, ABOVEGROUND	LF	45.000
	0632- 7- 2	SIGNAL CABLE- REPAIR/REPLACE/OTHER, FURNISH & INSTALL	LF	67.000
	0633- 1-320	FIBER OPTIC CABLE, INSTALL, UNDERGROUND	LF	220.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	13.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	7.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	7.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	899.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	6.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	9.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	1.000
	0670- 5-111	TRAFFIC CONTROLLER ASSEMBLY, F&I, NEMA, 1 PREEMPTION	AS	2.000
	0670- 5-600	TRAFFIC CONTROLLER ASSEMBLY, REMOVE CONTROLLER WITH CABINET	AS	2.000
	0676- 2-300	ITS CABINET, INSTALL	EA	7.000
	0682- 1-300	ITS CCTV CAMERA, INSTALL	EA	6.000
	0684- 1- 3	MANAGED FIELD ETHERNET SWITCH, INSTALL	EA	15.000
	0684- 6- 30	WIRELESS COMMUNICATION DEVICE, INSTALL	EA	15.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	2.000
	0700- 8-400	FRONT ACCESS DYNAMIC MESSAGE SIGN, INSTALL	EA	5.000
	0700- 10-121	DMS SUPPORT STRUCTURE, CANTILEVER, UP TO 20 FT	EA	2.000
	0700- 10-122	DMS SUPPORT STRUCTURE, CANTILEVER, 21-30 FT	EA	2.000
	0700- 10-123	DMS SUPPORT STRUCTURE, CANTILEVER, 31-40 FT	EA	1.000
	0700- 12- 11	SIGN BEACON, F&I GROUND MOUNT- AC POWERED, ONE BEACON	AS	1.000