

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	CT210331	Call Order: 012	Proposal: T3682	District:03
Counties:	HOLMES			
Road Name:	SR 81			
Limits:	PONCE DE LEON SCHOOL SIDEWALK			
Project(s):	43812915201(*)	Federal Aid No: D320032B		
Total Roadway Length:	0.380 Miles	Contract Days:	75	
Total Bridge Length:	0.000 Miles	Letting Date:	03/31/21	
Total Proposal Length:	0.380 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	15 Days Standard Acq	

Proposal Budget Estimate: \$315,525.00

Please read the full advertisement

Description:

BUSINESS DEVELOPMENT INITIATIVE -- Bidders must be a "Small Business" as defined by FDOT. Small business size standards can be found at <https://www.fdot.gov/equalopportunity/bdi.shtm>.

For more information about bidding on BDI projects, please see the training guide located at <http://www.cmdp-bgp.com/bdi-projects.html>

Prequalification per Rule 14-22 is not required.

Bidders must complete and submit the Small Business Affidavit (Form No. 275-000-01) for approval prior to receipt of bid documents. The form may be accessed at: <https://www.fdot.gov/equalopportunity/bdi.shtm>

It is only necessary to submit the Small Business Affidavit (SBA) form once per year.

Send a completed and notarized affidavit as an attachment to: fdot.bdi@dot.state.fl.us.

All Sublet work must be contracted to a small business or businesses as defined by the Department. The subcontractor must also submit a notarized Small Business Affidavit Form provided by the Department prior to the start of work.

Bidders must submit the BDI Reference Sheet (Form No. 275-000-02) with the bid unless bidder is prequalified in the project's major work type, per Rule 14-22, Florida Administrative Code.

Upload the completed BDI Reference Sheet (Form No. 275-000-02) as a zip file using the "File Attachment Upload" folder in the AASHTOWare Project Bids application.

BDI Reference Sheet may be found at: <https://www.fdot.gov/equalopportunity/bdi.shtm>

Proposal Guaranty of \$500 is required for bids over \$150,000 and may be in the form of a Cashier's Check, the BDI Bid or Proposal Bond (Form No. 375-020-16), or the standard Bid or Proposal Bond form, Form No. 375-020-09).

The improvements under this contract consist of Ponce De Leon School sidewalk improvements, curb and gutter additions, ditch regrading, and signing and pavement markings in Holmes County. ADA improvements will also be made by adding curb ramps, detectable warnings and a pedestrian island at the Ammons Rd intersection.

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Call Order: 012 Proposal: T3682

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (43812915201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43812915201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	600.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	1,200.000
	0104- 1-	ARTIFICIAL COVERINGS /ROLLED EROSION CONTROL PRODUCTS	SY	6,025.000
	0104- 10- 3	SEDIMENT BARRIER	LF	2,107.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	2.000
	0110- 1- 1	CLEARING & GRUBBING (43812915201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	93.000
	0120- 1-	REGULAR EXCAVATION	CY	220.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	259.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	99.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	605.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	1,692.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	85.000
	0527- 2-	DETECTABLE WARNINGS	SF	162.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	1,549.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43812915201)	LS	1.000
Section 0002 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	8.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	1.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43812915201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	347.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	53.000
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	2.000
	0711- 12-201	THERMOPLASTIC, REFURBISHMENT, YELLOW, SOLID, 6"	GM	0.046
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	323.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.011
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.013
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	65.000