

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: CT210331 Call Order: 014 Proposal: T3762 District:03
Counties: LEON
Road Name: SR 61 (US 319) (THOMASVILLE RD)
Limits: FROM S OF MACLAY RD TO TIMBERWOLF CROSSING
Project(s): 43972815201(*) Federal Aid No: D319173B
Project(s): 43972815202 Federal Aid No: N/A
Project(s): 43972815203 Federal Aid No: N/A
Project(s): 43972815204 Federal Aid No: N/A
Project(s): 43972815205 Federal Aid No: N/A
Total Roadway Length: 4.622 Miles Contract Days: 295
Total Bridge Length: 0.000 Miles Letting Date: 03/31/21
Total Proposal Length: 4.622 Miles Contract Execution Days: 10
Special Start Date: N/A
Aquis/Flexible Start Time: 120 Acquis.
Proposal Budget Estimate: \$6,879,936.00

Please read the full advertisement

Description:

439728-1-52-01 The improvements under this contract consist of milling and resurfacing, turn lane extension, ADA improvements, signing and pavement marking, and pedestrian signals on SR 61 (US 319) Thomasville Road from South of Maclay Road to Timberwolf Crossing in Leon County.
439728-1-52-02 The improvements under this contract consist of adjusting manholes and valve boxes owned by the City of Tallahassee-Water and Sewer.
439728-1-52-03 The improvements under this contract consist of adjusting valve boxes owned by the City of Tallahassee-Gas.
439728-1-52-04 The Improvements under this contract consist of adjusting manholes owned by the CenturyLink.
439728-1-52-05 The Improvements under this contract consist of adjusting manholes owned by the City of Tallahassee-Electric.

Call Order: 014 Proposal: T3762

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (43972815201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43972815201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	336.000
	0102- 60-	WORK ZONE SIGN	ED	26,471.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	377.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	53,957.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	9,108.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	217.000
	0102- 78-	TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER	EA	447.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	768.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	885.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	885.000
	0102-115-	TYPE III BARRICADE	ED	20.000
	0104- 10- 3	SEDIMENT BARRIER	LF	8,265.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	177.000
	0107- 1-	LITTER REMOVAL	AC	345.180

Call Order: 014 Proposal: T3762

ALT	Item	Description	Unit	Quantity
	0107- 2-	MOWING	AC	213.110
	0110- 1- 1	CLEARING & GRUBBING (43972815201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	7,301.000
	0110- 7- 1	MAILBOX, F&I SINGLE	EA	4.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	98.000
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (43972815201)	LS	1.000
	0160- 4-	TYPE B STABILIZATION	SY	832.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	723.000
	0286- 1-	TURNOUT CONSTRUCTION/DRIVEWAY BASE- OPTIONAL MATERIALS	SY	21.000
	0327- 70- 5	MILLING EXISTING ASPHALT PAVEMENT, 2" AVG DEPTH	SY	214,573.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	4,955.000
	0327- 70- 15	MILLING EXISTING ASPHALT PAVEMENT, 2 3/4" AVG DEPTH	SY	22,034.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	1,566.800
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	25,887.800
	0350- 5-	CLEANING & SEALING JOINTS- CONCRETE PAVEMENT	LF	29,912.000
	0400- 0- 11	CONCRETE CLASS NS, GRAVITY WALL INDEX 400-011	CY	75.400
	0425- 1-315	INLETS, CURB TYPE P-1, PARTIAL	EA	3.000
	0425- 1-325	INLETS, CURB, TYPE P-2, PARTIAL	EA	2.000
	0425- 1-365	INLETS, CURB, TYPE P-6, PARTIAL	EA	1.000
	0425- 1-521	INLETS, DT BOT, TYPE C, <10'	EA	1.000
	0425- 1-541	INLETS, DT BOT, TYPE D, <10'	EA	1.000
	0425- 1-701	INLETS, GUTTER, TYPE S, <10'	EA	1.000
	0425- 5-	MANHOLE, ADJUST	EA	20.000
	0425- 5- 1	MANHOLE, ADJUST, UTILITIES	EA	48.000
	0425- 6-	VALVE BOXES, ADJUST	EA	79.000
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	33.000
	0430-175-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD	LF	32.000
	0430-175-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"S/CD	LF	24.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	2.000
	0430-991-	MITERED END SECT, REPLACE SLAB- CONSTRUCTION USE	EA	2.000
	0515- 1- 2	PIPE HANDRAIL - GUIDERAIL, ALUMINUM	LF	30.000
	0515- 2-111	PEDESTRIAN / BICYCLE RAILING, NS, 42" TYPE 1	LF	400.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	390.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	2,994.000
	0520- 3-	VALLEY GUTTER- CONCRETE	LF	17.000
	0520- 5- 12	TRAFFIC SEPARATOR CONCRETE-TYPE I, 6' WIDE	LF	52.000
	0520- 6-	SHOULDER GUTTER- CONCRETE	LF	148.000
	0520- 70-	CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH	SY	322.000
	0521- 1- 12	MEDIAN CONCRETE BARRIER, SHORT GRADE-SEPARATED	LF	139.000
	0521- 1- 14	MEDIAN CONCRETE BARRIER, VARIABLE SECTION WIDTH FOR SIGN OR PIER SHIELDING	LF	170.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	4,257.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	1,347.000
	0524- 1- 2	CONCRETE DITCH PAVEMENT, NON REINFORCED, 4"	SY	60.000
	0527- 2-	DETECTABLE WARNINGS	SF	1,356.000

Call Order: 014 Proposal: T3762

ALT	Item	Description	Unit	Quantity
	0544- 3- 1	CRASH CUSHION, TL-3, NARROW	EA	2.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	3,265.000
	0570- 1- 3	PERFORMANCE TURF, SOD AND SOIL- SHOULDER TREATMENT INDEX 570-010	SY	701.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	1.240
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	2,085.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	468.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	0.720
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.202
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	3.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	44.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.669
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.120
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43972815201)	LS	1.000
Section 0002 Signing				
	0639- 1-610	ELECTRICAL POWER SERVICE, REMOVE OVERHEAD	AS	1.000
	0641- 2- 80	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- POLE 30' AND GREATER	EA	1.000
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	66.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	12.000
	0700- 1- 13	SINGLE POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	1.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	2.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	68.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	4.000
	0700- 3-211	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 601 SF AND GREATER	EA	1.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	2.000
	0700- 3-606	SIGN PANEL, REMOVE, 101-200 SF	EA	1.000
	0700- 3-607	SIGN PANEL, REMOVE, 201-300 SF	EA	1.000
	0700- 4-125	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, SPAN, 51-100 FT	EA	1.000
	0700- 4-620	OVERHEAD STATIC SIGN STRUCTURE, REMOVE SPAN	EA	1.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	97.000
	0705- 11- 2	DELINEATOR, NON-FLEXIBLE	EA	17.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	482.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43972815201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	7,256.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	844.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	1,398.000

Call Order: 014 Proposal: T3762

ALT	Item	Description	Unit	Quantity
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	4.667
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	8.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	151.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	170.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.519
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	1,582.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	111.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	111.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	16.344
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.602
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	16.289
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	9.625
	0711- 16-202	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 8"	GM	0.016
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	2,121.000
Section 0003 Signalization				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	260.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	2.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	2.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	6.000
	0646- 1- 12	ALUMINUM SIGNALS POLE, FURNISH & INSTALL PEDESTRIAN DETECTOR POST	EA	1.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	2.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	3.000
	0653- 1- 12	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAYS	AS	5.000
	0653- 1- 60	PEDESTRIAN SIGNAL, REMOVE PED SIGNAL- POLE/PEDESTAL TO REMAIN	AS	9.000
	0660- 1-110	LOOP DETECTOR INDUCTIVE, F&I, TYPE 10	EA	12.000
	0660- 2-101	LOOP ASSEMBLY- F&I, TYPE A	AS	21.000
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	30.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	12.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	13.000
	0665- 1- 60	PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN	EA	9.000
	0670- 5-400	TRAFFIC CONTROLLER ASSEMBLY, MODIFY	AS	2.000
	0695- 7-600	TRAFFIC MONITORING SITE CABINET, REMOVE EXISTING CABINET	EA	1.000