

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

Letting: CT210331 Call Order: 015 Proposal: T4578 District:04  
 Counties: BROWARD  
 Road Name: SR 820 (HOLLYWOOD BLVD)  
 Limits: AT SR 9 (I-95) AND S 28 AVE  
 Project(s): 43991115201(\*) Federal Aid No: D420091B  
 Total Roadway Length: 0.207 Miles Contract Days: 217  
 Total Bridge Length: 0.000 Miles Letting Date: 03/31/21  
 Total Proposal Length: 0.207 Miles Contract Execution Days: 10  
 Special Start Date: N/A  
 Aquis/Flexible Start Time: 120 Calendar Days

Proposal Budget Estimate: \$1,013,754.00

Please read the full advertisement

Description:

The improvements under this contract consist of, but not limited to, pavement widening, milling and resurfacing, drainage, signing, pavement markings, signalization and lighting on SR 820 (Hollywood Blvd.).

**Call Order: 015 Proposal: T4578**

| ALT                         | Item         | Description   | Unit | Quantity  |
|-----------------------------|--------------|---|------|-----------|
| <b>Section 0001 Roadway</b> |              |   |      |           |
|                             | 0101- 1-     | MOBILIZATION (43991115201)  | LS   | 1.000     |
|                             | 0102- 1-     | MAINTENANCE OF TRAFFIC (43991115201)  | LS   | 1.000     |
|                             | 0102- 14-    | TRAFFIC CONTROL OFFICER   | HR   | 144.000   |
|                             | 0102- 60-    | WORK ZONE SIGN  | ED   | 8,966.000 |
|                             | 0102- 71- 13 | TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE                                   | LF   | 151.000   |
|                             | 0102- 71- 15 | TEMPORARY BARRIER, F&I, ANCHORED  | LF   | 253.000   |
|                             | 0102- 74- 1  | CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD                          | ED   | 9,804.000 |
|                             | 0102- 74- 8  | CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)          | FD   | 1,870.000 |
|                             | 0102- 76-    | ARROW BOARD / ADVANCE WARNING ARROW PANEL                                       | ED   | 120.000   |
|                             | 0102- 78-    | TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER                                | EA   | 243.000   |
|                             | 0102- 89- 1  | TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION                                     | LO   | 1.000     |
|                             | 0102- 99-    | PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY                                     | ED   | 693.000   |
|                             | 0102-104-    | TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION                           | ED   | 217.000   |
|                             | 0102-107- 1  | TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION                       | ED   | 217.000   |
|                             | 0102-150- 1  | PORTABLE REGULATORY, SIGN   | ED   | 651.000   |
|                             | 0104- 10- 3  | SEDIMENT BARRIER  | LF   | 264.000   |
|                             | 0104- 18-    | INLET PROTECTION SYSTEM   | EA   | 13.000    |
|                             | 0107- 1-     | LITTER REMOVAL  | AC   | 17.890    |
|                             | 0107- 2-     | MOWING  | AC   | 12.520    |
|                             | 0108- 1-     | MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (43991115201) | LS   | 1.000     |
|                             | 0108- 2-     | MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (43991115201)                 | LS   | 1.000     |
|                             | 0110- 1- 1   | CLEARING & GRUBBING (43991115201)   | LS   | 1.000     |

**Call Order: 015 Proposal: T4578**

| ALT | Item         | Description   | Unit | Quantity  |
|-----|--------------|---|------|-----------|
|     | 0110- 4- 10  | REMOVAL OF EXISTING CONCRETE  | SY   | 322.000   |
|     | 0120- 1-     | REGULAR EXCAVATION  | CY   | 816.000   |
|     | 0120- 6-     | EMBANKMENT  | CY   | 12.000    |
|     | 0160- 4-     | TYPE B STABILIZATION  | SY   | 693.000   |
|     | 0285-706-    | OPTIONAL BASE, BASE GROUP 06  | SY   | 65.000    |
|     | 0285-709-    | OPTIONAL BASE, BASE GROUP 09  | SY   | 628.000   |
|     | 0327- 70- 6  | MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH   | SY   | 3,097.000 |
|     | 0327- 70- 15 | MILLING EXISTING ASPHALT PAVEMENT, 2 3/4" AVG DEPTH   | SY   | 5,683.000 |
|     | 0334- 1- 12  | SUPERPAVE ASPHALTIC CONC, TRAFFIC B   | TN   | 144.100   |
|     | 0334- 1- 14  | SUPERPAVE ASPHALTIC CONC, TRAFFIC D   | TN   | 472.700   |
|     | 0337- 7- 81  | ASPHALT CONCRETE FRICTION COURSE,TRAFFIC B, FC-12.5, PG 76-22                               | TN   | 250.700   |
|     | 0337- 7- 85  | ASPHALT CONCRETE FRICTION COURSE,TRAFFIC D, FC-12.5, PG 76-22                               | TN   | 484.600   |
|     | 0339- 1-     | MISCELLANEOUS ASPHALT PAVEMENT  | TN   | 1.100     |
|     | 0425- 1-361  | INLETS, CURB, TYPE P-6, <10'  | EA   | 1.000     |
|     | 0425- 5-     | MANHOLE, ADJUST   | EA   | 6.000     |
|     | 0425- 6-     | VALVE BOXES, ADJUST   | EA   | 2.000     |
|     | 0430-175-118 | PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD   | LF   | 30.000    |
|     | 0430-982-125 | MITERED END SECTION, OPTIONAL ROUND, 18" CD   | EA   | 1.000     |
|     | 0520- 1- 10  | CONCRETE CURB & GUTTER, TYPE F  | LF   | 696.000   |
|     | 0521- 72- 43 | SHOULDER CONCRETE BARRIER, CURB AND GUTTER BARRIER  | LF   | 121.000   |
|     | 0522- 1-     | CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK   | SY   | 45.000    |
|     | 0522- 2-     | CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK   | SY   | 47.000    |
|     | 0526- 1- 2   | PAVERS, ARCHITECTURAL, SIDEWALK   | SY   | 38.000    |
|     | 0527- 2-     | DETECTABLE WARNINGS   | SF   | 39.000    |
|     | 0536- 1- 1   | GUARDRAIL -ROADWAY, GENERAL TL-3  | LF   | 68.000    |
|     | 0536- 8-122  | GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I-INDEX 536-002, APPROACH TL-3          | EA   | 1.000     |
|     | 0536- 73-    | GUARDRAIL REMOVAL   | LF   | 374.000   |
|     | 0550- 10-220 | FENCING, TYPE B, 5.1-6.0', STANDARD   | LF   | 246.000   |
|     | 0570- 1- 2   | PERFORMANCE TURF, SOD   | SY   | 848.000   |
|     | 0710- 11-101 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"                                       | GM   | 1.429     |
|     | 0710- 11-102 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"      | GM   | 0.033     |
|     | 0710- 11-103 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE MARKINGS, 12"             | GM   | 0.506     |
|     | 0710- 11-125 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"           | LF   | 95.000    |
|     | 0710- 11-131 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE                | GM   | 0.115     |
|     | 0710- 11-141 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6" | GM   | 0.036     |
|     | 0710- 11-160 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL                               | EA   | 8.000     |
|     | 0710- 11-170 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS  | EA   | 23.000    |
|     | 0710- 11-180 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, YIELD LINE                                      | LF   | 13.000    |
|     | 0710- 11-201 | PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"                                      | GM   | 0.734     |

**Call Order: 015 Proposal: T4578**

| ALT                          | Item         | Description  | Unit | Quantity |
|------------------------------|--------------|--|------|----------|
|                              | 0710- 11-202 | PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"          | GM   | 0.072    |
|                              | 0710- 11-224 | PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"                  | LF   | 51.000   |
|                              | 0710- 11-241 | PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"      | GM   | 0.036    |
|                              | 0999- 25-    | INITIAL CONTINGENCY AMOUNT, DO NOT BID (43991115201)   | LS   | 1.000    |
| <b>Section 0002 Signing</b>  |              |  |      |          |
|                              | 0641- 2- 80  | PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- POLE 30' AND GREATER                           | EA   | 2.000    |
|                              | 0649- 21- 6  | STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 50'                                     | EA   | 1.000    |
|                              | 0700- 1- 11  | SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF  | AS   | 9.000    |
|                              | 0700- 1- 12  | SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF   | AS   | 1.000    |
|                              | 0700- 1- 13  | SINGLE POST SIGN, F&I GROUND MOUNT, 21-30 SF   | AS   | 2.000    |
|                              | 0700- 1- 60  | SINGLE POST SIGN, REMOVE   | AS   | 14.000   |
|                              | 0700- 2- 60  | MULTI- POST SIGN, REMOVE   | AS   | 2.000    |
|                              | 0700- 3-201  | SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF  | EA   | 4.000    |
|                              | 0700- 13- 12 | RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 2'  | EA   | 1.000    |
|                              | 0710- 90-    | PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43991115201)   | LS   | 1.000    |
|                              | 0711- 11-102 | THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND                       | GM   | 0.033    |
|                              | 0711- 11-103 | THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR INTERCHANGE MARKINGS                              | GM   | 0.049    |
|                              | 0711- 11-123 | THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT                          | LF   | 238.000  |
|                              | 0711- 11-125 | THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK                           | LF   | 170.000  |
|                              | 0711- 11-141 | THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"                     | GM   | 0.036    |
|                              | 0711- 11-160 | THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL  | EA   | 8.000    |
|                              | 0711- 11-170 | THERMOPLASTIC, STANDARD, WHITE, ARROW  | EA   | 25.000   |
|                              | 0711- 11-180 | THERMOPLASTIC, STANDARD, WHITE, YIELD LINE   | LF   | 13.000   |
|                              | 0711- 11-224 | THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON                              | LF   | 51.000   |
|                              | 0711- 14-125 | THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK  | LF   | 170.000  |
|                              | 0711- 16-101 | THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"   | GM   | 0.736    |
|                              | 0711- 16-131 | THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP              | GM   | 0.160    |
|                              | 0711- 16-133 | THERMOPLASTIC, STANDARD-OTHER SURFACES WHITE, SKIP, 12"- APPROACH TO TOLL PLAZA OR 3-9 LANE DROP | GM   | 0.112    |
|                              | 0711- 16-201 | THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"  | GM   | 0.369    |
|                              | 0711- 16-202 | THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 8"  | GM   | 0.032    |
| <b>Section 0003 Lighting</b> |              |  |      |          |
|                              | 0630- 2- 11  | CONDUIT, FURNISH & INSTALL, OPEN TRENCH  | LF   | 462.000  |
|                              | 0630- 2- 12  | CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE   | LF   | 104.000  |
|                              | 0635- 2- 11  | PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE   | EA   | 11.000   |

**Call Order: 015 Proposal: T4578**

| ALT                               | Item         | Description  | Unit | Quantity  |
|-----------------------------------|--------------|--|------|-----------|
|                                   | 0715- 1- 12  | LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6  | LF   | 2,346.000 |
|                                   | 0715- 1- 60  | LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS                                       | LF   | 1,830.000 |
|                                   | 0715- 4- 24  | LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE SPECIAL FOUNDATION, 45' MOUNTING HEIGHT | EA   | 5.000     |
|                                   | 0715- 4- 70  | LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION  | EA   | 3.000     |
|                                   | 0715- 11-211 | LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, COBRA HEAD         | EA   | 4.000     |
|                                   | 0715- 11-213 | LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, POLE TOP           | EA   | 1.000     |
|                                   | 0715-500- 1  | POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL                            | EA   | 9.000     |
| <b>Section 0004 Signalization</b> |              |  |      |           |
|                                   | 0630- 2- 11  | CONDUIT, FURNISH & INSTALL, OPEN TRENCH  | LF   | 83.000    |
|                                   | 0630- 2- 12  | CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE   | LF   | 557.000   |
|                                   | 0632- 7- 1   | SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL                           | PI   | 1.000     |
|                                   | 0633- 8- 1   | MULTI-CONDUCTOR COMMUNICATION CABLE, FURNISH & INSTALL                                       | LF   | 100.000   |
|                                   | 0635- 2- 11  | PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE   | EA   | 19.000    |
|                                   | 0646- 1- 11  | ALUMINUM SIGNALS POLE, PEDESTAL  | EA   | 3.000     |
|                                   | 0646- 1- 60  | ALUMINUM SIGNALS POLE, REMOVE  | EA   | 2.000     |
|                                   | 0649- 21- 26 | STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, DOUBLE ARM 78'-70'                             | EA   | 2.000     |
|                                   | 0649- 26- 5  | STEEL MAST ARM ASSEMBLY, REMOVE, DEEP FOUNDATION- BOLT ON ATTACHMENT                         | EA   | 2.000     |
|                                   | 0650- 1- 14  | VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY                       | AS   | 18.000    |
|                                   | 0653- 1- 11  | PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY                                    | AS   | 3.000     |
|                                   | 0660- 4- 12  | VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT                    | EA   | 5.000     |
|                                   | 0665- 1- 12  | PEDESTRIAN DETECTOR, FURNISH & INSTALL, ACCESSIBLE   | EA   | 4.000     |
|                                   | 0665- 1- 60  | PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN   | EA   | 1.000     |
|                                   | 0670- 5-400  | TRAFFIC CONTROLLER ASSEMBLY, MODIFY  | AS   | 1.000     |
|                                   | 0682- 1-400  | ITS CCTV CAMERA, RELOCATE  | EA   | 1.000     |
|                                   | 0700- 3-501  | SIGN PANEL, RELOCATE, UP TO 12 SF  | EA   | 1.000     |
|                                   | 0700- 5- 22  | INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF                     | EA   | 2.000     |