

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: CT210526 Call Order: 006 Proposal: T2803 District:02

Counties: DUVAL

Road Name: SR 134 (103RD ST)

Limits: FROM E OF I-295 TO EAST OF SR 21

Project(s): 44126115201(*) Federal Aid No: D220100B

Project(s): 44126115601 Federal Aid No: N/A

Total Roadway Length:	1.439 Miles	Contract Days:	325
Total Bridge Length:	0.000 Miles	Letting Date:	05/26/21
Total Proposal Length:	1.439 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	15 Days

Proposal Budget Estimate: \$4,330,331.00

Please read the full advertisement

Description:

JEA Standards. Table A -- Schedule of Values is required to be submitted with the bid, as per Technical Special Provision T1000-17.

Please upload completed Table A as a zip file within your EBS File using the "File Attachment Upload" tab before submitting your bid.

The improvements under this contract consist of milling and resurfacing, base work, curb and gutter, traffic signals, highway signing, sidewalks and other incidental construction on SR 134 in Duval County from east of I-295 to east of SR 21.

Call Order: 006 Proposal: T2803

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44126115201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44126115201)	LS	1.000
	0102- 2-200	SPECIAL DETOUR- TEMPORARY PAVEMENT	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	344.000
	0102- 60-	WORK ZONE SIGN	ED	19,400.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	23,500.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	3,800.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	650.000
	0102- 78-	TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER	EA	6,205.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,300.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	48.000
	0107- 1-	LITTER REMOVAL	AC	42.630
	0107- 2-	MOWING	AC	10.570
	0110- 1- 1	CLEARING & GRUBBING (44126115201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	1,742.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	50.000
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (44126115201)	LS	1.000
	0145- 2-	GEOSYNTHETIC REINFORCED FOUNDATION OVER SOFT SOIL	SY	67.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	1,406.000

Call Order: 006 Proposal: T2803

ALT	Item	Description	Unit	Quantity
	0327- 70- 4	MILLING EXISTING ASPHALT PAVEMENT, 3" AVG DEPTH	SY	68,443.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	5,686.500
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	5,646.500
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	681.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	414.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	32.000
	0520- 70-	CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH	SY	325.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	714.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	973.000
	0522- 3-	BUS BOARDING PAD- CONCRETE	SY	9.000
	0527- 2-	DETECTABLE WARNINGS	SF	396.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	421.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	69.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	194.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	3.000
	0695- 1- 1	TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL	EA	12.000
	0695- 6- 12	TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 2 LOOPS	EA	12.000
	0695- 7-162	TRAFFIC MONITORING SITE CABINET, F&I, TYPE 3, 2 PANE BACK, PEDESTAL MOUNT	EA	2.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	14.070
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	4,056.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	1,043.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	3.710
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	2.580
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	0.710
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44126115201)	LS	1.000
Section 0002 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	9.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	1.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	1.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	3.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	5.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	14.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	207.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44126115201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	4,056.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	1,043.000
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	14.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	76.000

Call Order: 006 Proposal: T2803

ALT	Item	Description	Unit	Quantity
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	10.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	2,873.000
	0711- 14-660	THERMOPLASTIC, PREFORMED, MULTI COLOR ROUTE SHIELD	EA	1.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	4.052
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6", 10'-30 SKIP OR 3-9 LANE DROP	GM	3.709
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	2.582
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	0.712
Section 0003 Signalization				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	94.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	3,244.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	6.000
	0632- 7- 6	SIGNAL CABLE, REMOVE- INTERSECTION	PI	6.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	54.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	18.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	9.000
	0650- 1- 14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	60.000
	0650- 1- 16	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 4 SECTION, 1 WAY	AS	15.000
	0650- 1- 60	VEHICULAR TRAFFIC SIGNAL, REMOVE- POLES TO REMAIN	AS	60.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	26.000
	0653- 1- 12	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAYS	AS	7.000
	0653- 1- 60	PEDESTRIAN SIGNAL, REMOVE PED SIGNAL- POLE/PEDESTAL TO REMAIN	AS	27.000
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	24.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	24.000
	0660- 3- 11	VEHICLE DETECTION SYSTEM- MICROWAVE, FURNISH & INSTALL CABINET EQUIPMENT	EA	3.000
	0660- 3- 12	VEHICLE DETECTION SYSTEM- MICROWAVE, FURNISH & INSTALL, ABOVE GROUND EQUIPMENT	EA	18.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	40.000
	0665- 1- 60	PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN	EA	27.000
	0670- 5-400	TRAFFIC CONTROLLER ASSEMBLY, MODIFY	AS	6.000
	0700- 3-602	SIGN PANEL, REMOVE, 12-20 SF	EA	21.000
	0700- 5- 22	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF	EA	21.000
Section 0004 Utilities				
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44126115601)	LS	1.000
	1000- 5-	UTILITY WORK- JPA/UTILITY AGREEMENT, SEWER (44126115601)	LS	1.000
	1000- 6-	UTILITY WORK- JPA/UTILITY AGREEMENT, WATER (44126115601)	LS	1.000