

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

Letting: CT210526 Call Order: 010 Proposal: T3741 District:03  
 Counties: ESCAMBIA  
 Road Name: SR 8 (I-10)  
 Limits: AT THE ESCAMBIA CO WELCOME CENTER  
 Project(s): 44159315201(\*) Federal Aid No: D320048B  
 Project(s): 44159315202 Federal Aid No: N/A  
 Total Roadway Length: 0.606 Miles Contract Days: 300  
 Total Bridge Length: 0.000 Miles Letting Date: 05/26/21  
 Total Proposal Length: 0.606 Miles Contract Execution Days: 10  
 Special Start Date: N/A  
 Aquis/Flexible Start Time: 15 Days Standard Acq  
 Proposal Budget Estimate: \$5,233,136.00

Please read the full advertisement

**Description:**

The improvements under this Contract, FPID # 441593-1-52-01, consists of milling and resurfacing portions of the exit and entrance ramps with asphalt pavement and replacing the existing perimeter wildlife fence at the SR 8 (I-10) Escambia County Welcome Center. Work also to be completed will be under FPID # 441593-1-52-02, consisting of reconstructing the existing semi-truck and car parking areas with concrete pavement. Additional improvements consist of new signing and pavement markings, construction of windshield washer stations for both passenger vehicles and semi-trucks, utility work and adjustments, drainage modifications, construction of edge drain, removal and reconstruction of curb and gutter and sidewalks, reconstruction of the existing stormwater management facility (SWMF) to increase the overall footprint to include modifications to existing outfall structure, and removal and replacement of new subterranean node vehicle sensors within the existing truck stalls. All work to be done in Escambia County.

**Call Order: 010 Proposal: T3741**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Roadway</b>				
	0101- 1-	MOBILIZATION (44159315201)	LS	1.000
	0101- 1-	MOBILIZATION (44159315202)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44159315201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44159315202)	LS	1.000
	0102- 2-200	SPECIAL DETOUR- TEMPORARY PAVEMENT (44159315202)	LS	1.000
	0102- 2-300	SPECIAL DETOUR- TEMPORARY EARTHWORK/BASE (44159315202)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	5,180.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	5,446.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	118,568.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	40.000
	0102- 78-	TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER	EA	540.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	644.000
	0102-115-	TYPE III BARRICADE	ED	1,920.000
	0104- 10- 3	SEDIMENT BARRIER	LF	2,927.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	611.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	4.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	6.000
	0107- 1-	LITTER REMOVAL	AC	221.730
	0107- 2-	MOWING	AC	194.730

**Call Order: 010 Proposal: T3741**

ALT	Item	Description	Unit	Quantity
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (44159315202)	LS	1.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (44159315202)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (44159315201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (44159315202)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	4,446.000
	0120- 1-	REGULAR EXCAVATION	CY	4,221.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	2,321.500
	0120- 4-	SUBSOIL EXCAVATION	CY	527.000
	0160- 4-	TYPE B STABILIZATION	SY	16,422.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	14,285.000
	0286- 1-	TURNOUT CONSTRUCTION/DRIVEWAY BASE- OPTIONAL MATERIALS	SY	15.000
	0327- 70- 5	MILLING EXISTING ASPHALT PAVEMENT, 2" AVG DEPTH	SY	1,889.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	2,085.000
	0327- 70- 10	MILLING EXISTING ASPHALT PAVEMENT, 5" AVG DEPTH	SY	9,475.000
	0327- 70- 11	MILLING EXISTING ASPHALT PAVEMENT, 2 1/4" AVG DEPTH	SY	3,126.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	1,042.300
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	431.100
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	125.000
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-12.5, PG 76-22	TN	207.800
	0350- 3- 6	PLAIN CEMENT CONCRETE PAVEMENT, 8.5"	SY	23,226.000
	0350- 5-	CLEANING & SEALING JOINTS- CONCRETE PAVEMENT	LF	42,828.000
	0352- 70-	GRINDING CONCRETE PAVEMENT	SY	23,226.000
	0425- 1-311	INLETS, CURB, TYPE P-1, <10'	EA	1.000
	0425- 1-315	INLETS, CURB TYPE P-1, PARTIAL	EA	6.000
	0425- 1-325	INLETS, CURB, TYPE P-2, PARTIAL	EA	1.000
	0425- 1-335	INLETS, CURB, TYPE P-3, PARTIAL	EA	1.000
	0425- 1-345	INLETS, CURB, TYPE P-4, PARTIAL	EA	7.000
	0425- 1-589	INLETS, DT BOT, TYPE H, MODIFY	EA	1.000
	0425- 1-910	INLETS, CLOSED FLUME	EA	2.000
	0425- 2- 43	MANHOLES, P-7, PARTIAL	EA	2.000
	0430-175-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	8.000
	0446- 1- 1	EDGEDRAIN DRAINCRETE, STANDARD	LF	3,753.000
	0446- 71- 1	EDGEDRAIN OUTLET PIPE, 4"	LF	385.000
	0519- 78-	BOLLARDS	EA	8.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	7,775.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	2,696.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	28.000
	0527- 2-	DETECTABLE WARNINGS	SF	362.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	13.400
	0550- 10-140	FENCING, TYPE A, 7.1-8.0', STANDARD	LF	4,253.000
	0550- 10-210	FENCING, TYPE B, 0.0-5.0', STANDARD FEATURES	LF	45.000
	0550- 60-112	FENCE GATE, TYPE A, SINGLE, 6.1-12.0' OPENING	EA	1.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	12,345.000

**Call Order: 010 Proposal: T3741**

ALT	Item	Description	Unit	Quantity
	0570- 1- 3	PERFORMANCE TURF, SOD AND SOIL- SHOULDER TREATMENT INDEX 570-010	SY	1,141.000
	0590- 70- 1	IRRIGATION SYSTEM REPAIRS (44159315202)	LS	1.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	328.000
	0635- 3- 40	JUNCTION BOX, RELOCATE	EA	1.000
	0641- 2- 11	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II PEDESTAL	EA	2.000
	0660- 5- 13	VEHICLE DETECTION SYSTEM- WIRELESS MAGNETOMETER, FURNISH & INSTALL, IN-ROAD ELECTRONICS	EA	52.000
	0676- 3- 10	SMALL EQUIPMENT ENCLOSURE, FURNISH AND INSTALL, LESS THAN 10"W X 13"H X 11" D	EA	2.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	0.916
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.026
	0710- 11-103	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE MARKINGS, 12"	GM	0.201
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	58.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	21.000
	0710- 11-133	PAINTED PAVEMENT MARKING, STANDARD, WHITE, 3'-9' SKIP DROP LINE AND APPROACH TO TOLL PLAZA, 12" WIDE,	GM	0.053
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.046
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	4.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	7.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.362
	0710- 11-421	PAINTED PAVEMENT MARKINGS, STANDARD, BLUE, SOLID FOR PARKING LOT- ACCESSIBLE MARKINGS, 6"	LF	198.000
	0751- 46-100	WINDSHIELD WASH STATION, PROJECT 441593-1-52-02	EA	2.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44159315201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44159315202)	LS	1.000
	1050- 41-201	UTILITY PIPE- POLYETHYLENE, FURNISH & INSTALL, WATER/SEWER, 1"	LF	371.000
<b>Section 0002 Signing</b>				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	26.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	2.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	26.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	5.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44159315202)	LS	1.000
	0711- 11-103	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR INTERCHANGE MARKINGS	GM	0.201
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	486.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	903.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	57.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.026

**Call Order: 010 Proposal: T3741**

ALT	Item	Description	Unit	Quantity
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	17.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	25.000
	0711- 11-421	THERMOPLASTIC, STANDARD, BLUE, SOLID,6"	LF	643.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	576.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	0.361
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.046
	0711- 15-133	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 12"- APPROACH TO TOLL PLAZA OR 3-9 LANE DROP	GM	0.053
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	0.041
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	2.221
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.057
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.664