

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	CT210526	Call Order: 004	Proposal: T7472	District:07
Counties:	HILLSBOROUGH			
Road Name:	SR 93 (I-275)			
Limits:	FROM N OF I-4 TO N OF MLK BLVD AND FROM N OF MLK TO N OF HILLSBOROUGH AVE			
Project(s):	43182125201(*)	Federal Aid No: D721012B		
Project(s):	44377015201	Federal Aid No: D721013B		
Total Roadway Length:	2.305 Miles	Contract Days:	1200	
Total Bridge Length:	0.159 Miles	Letting Date:	05/26/21	
Total Proposal Length:	2.464 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	60 Calendar Days	
Proposal Budget Estimate:	\$78,031,300.00			

Please read the full advertisement

Description:

For projects in excess of \$50 million, in addition to meeting all other qualification requirements of Section 337.14, Florida Statutes, and Rule Chapter 14-22, Florida Administrative Code, any Contractor who is not prequalified and in good standing with the Department as of January 1, 2019, must submit evidence which demonstrates satisfactory completion of at least two projects, each in excess of \$15 million, for the Florida Department of Transportation or for any other state department of transportation. Acceptability of the evidence related to the two projects is at the sole discretion of the Department.

The improvements under this contract consist of highway widening along SR 93 (I-275).

Call Order: 004 Proposal: T7472

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (43182125201)	LS	1.000
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (43182125201)	LS	1.000
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (44377015201)	LS	1.000
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (44377015201)	LS	1.000
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (44377015201)	LS	1.000
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (44377015201)	LS	1.000
	0400- 2- 4	CONC CLASS II, BRIDGE SUPERSTRUCTURE	CY	792.600
	0400- 2- 10	CONCRETE CLASS II, APPROACH SLABS	CY	299.500
	0400- 4- 5	CONCRETE CLASS IV, BRIDGE SUBSTRUCTURE	CY	381.200
	0400- 7- 1	BRIDGE DECK GROOVING	SY	3,842.000
	0400-143-	CLEANING & COATING CONCRETE SURFACE, CLASS 5	SF	65,014.000
	0400-147-	COMPOSITE NEOPRENE PADS	CF	28.800
	0415- 1- 4	REINFORCING STEEL - BRIDGE SUPERSTRUCTURE	LB	240,769.000
	0415- 1- 5	REINFORCING STEEL- BRIDGE SUBSTRUCTURE	LB	130,597.000
	0415- 1- 9	REINFORCING STEEL- APPROACH SLABS	LB	59,879.000
	0450- 1- 1	PRESTRESSED BEAMS, TYPE II	LF	83.000
	0450- 2- 36	PREST BEAMS: FLORIDA-I BEAM 36"	LF	2,447.000
	0455- 35-113	STEEL PILING, HP 14 X 89 WITH 100% DYNAMIC LOAD TESTING, PROJECTS 431821-2-52-01 & 443770-1-52-01	LF	2,655.000
	0455- 88- 5	DRILLED SHAFT, 48" DIA	LF	1,452.000
	0455-107- 5	DRILLED SHAFT CASING, 48" DIAMETER	LF	701.000

Call Order: 004 Proposal: T7472

ALT	Item	Description	Unit	Quantity
	0455-111-	CORE-PILOT HOLE, DRILLED SHAFT EXCAVATION	LF	1,713.000
	0455-122- 5	EXCAVATION UNCLASSIFIED SHAFT, 48" DIA	LF	1,810.000
	0455-147- 1	THERMAL INTEGRITY TESTING, UP TO 4' SHAFT DIAMETER	EA	22.000
	0458- 1- 11	BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&I POURED JOINT WITH BACKER ROD	LF	804.000
	0521- 5- 13	CONCRETE TRAFFIC RAILING- BRIDGE, 36" SINGLE-SLOPE	LF	20.000
	0521- 5- 22	CONCRETE TRAFFIC RAILING- BRIDGE, 8'-0" NOISE WALL	LF	2,217.000
	0524- 2- 2	CONCRETE SLOPE PAVEMENT, NON REINFORCED, 4"	SY	1,219.000
	0563- 4-	ANTI-GRAFFITI COATING, NON-SACRIFICIAL	SF	16,818.000
	0630- 2- 16	CONDUIT, FURNISH & INSTALL, EMBEDDED CONCRETE BARRIERS AND TRAFFIC RAILINGS	LF	1,334.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (43182125201)	LS	1.000
	0101- 1-	MOBILIZATION (44377015201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43182125201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44377015201)	LS	1.000
	0102- 2-200	SPECIAL DETOUR- TEMPORARY PAVEMENT (43182125201)	LS	1.000
	0102- 2-200	SPECIAL DETOUR- TEMPORARY PAVEMENT (44377015201)	LS	1.000
	0102- 2-300	SPECIAL DETOUR- TEMPORARY EARTHWORK/BASE (43182125201)	LS	1.000
	0102- 2-300	SPECIAL DETOUR- TEMPORARY EARTHWORK/BASE (44377015201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	6,240.000
	0102- 30- 23	TEMPORARY HIGHWAY LIGHTING, PROJECT 431821-2-52-01/443770- 1-52-01	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	303,300.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	1,076.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	26,802.000
	0102- 71- 16	TEMPORARY BARRIER, F&I, FREE STANDING	LF	15,163.000
	0102- 71- 25	TEMPORARY BARRIER, RELOCATE, ANCHORED	LF	20,519.000
	0102- 71- 26	TEMPORARY BARRIER, RELOCATE, FREE STANDING	LF	20,197.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	250,384.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	18,720.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	624.000
	0102- 78-	TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER	EA	14,622.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	54.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	3,867.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	4,800.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	4,800.000
	0102-115-	TYPE III BARRICADE	ED	13,362.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	600.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	600.000
	0104- 10- 3	SEDIMENT BARRIER	LF	28,378.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	4.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	174.000
	0107- 1-	LITTER REMOVAL	AC	2,290.340

Call Order: 004 Proposal: T7472

ALT	Item	Description	Unit	Quantity
	0107- 2-	MOWING	AC	538.910
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (43182125201)	LS	1.000
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (44377015201)	LS	1.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (43182125201)	LS	1.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (44377015201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (43182125201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (44377015201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	37,437.000
	0110- 21-	TREE PROTECTION BARRIER	LF	5,701.000
	0110- 22-	TREE ROOT AND BRANCH PRUNING	EA	12.000
	0120- 1-	REGULAR EXCAVATION	CY	60,464.100
	0120- 6-	EMBANKMENT	CY	34,922.700
	0160- 4-	TYPE B STABILIZATION	SY	118,588.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	98,502.000
	0285-702-	OPTIONAL BASE, BASE GROUP 02	SY	822.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	21,008.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	210.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	1,935.000
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	2,332.600
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	172.800
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	128.900
	0350- 3- 7	PLAIN CEMENT CONCRETE PAVEMENT, 9"	SY	96,877.000
	0350- 3- 17	PLAIN CEMENT CONCRETE PAVEMENT, 14"	SY	1,157.000
	0350- 5-	CLEANING & SEALING JOINTS- CONCRETE PAVEMENT	LF	225,243.000
	0352- 70-	GRINDING CONCRETE PAVEMENT	SY	89,731.000
	0353- 70-	CONCRETE PAVEMENT SLAB REPLACEMENT	CY	204.300
	0400- 0- 11	CONCRETE CLASS NS, GRAVITY WALL INDEX 400-011	CY	672.800
	0400- 4- 1	CONCRETE CLASS IV, CULVERTS	CY	18.100
	0400- 4- 11	CONC CLASS IV, RETAINING WALLS	CY	358.000
	0415- 1- 1	REINFORCING STEEL- ROADWAY	LB	2,456.000
	0415- 1- 3	REINFORCING STEEL- RETAINING WALL	LB	71,462.000
	0425- 1-351	INLETS, CURB, TYPE P-5, <10'	EA	4.000
	0425- 1-361	INLETS, CURB, TYPE P-6, <10'	EA	1.000
	0425- 1-452	INLETS, CURB, TYPE J-5, >10'	EA	1.000
	0425- 1-471	INLETS, CURB, TYPE 7, <10'	EA	1.000
	0425- 1-521	INLETS, DT BOT, TYPE C, <10'	EA	2.000
	0425- 1-529	INLETS, DT BOT, TYPE C, MODIFY	EA	12.000
	0425- 1-541	INLETS, DT BOT, TYPE D, <10'	EA	11.000
	0425- 1-543	INLETS, DITCH BOTTOM, TYPE D, J BOT, <10'	EA	1.000
	0425- 1-701	INLETS, GUTTER, TYPE S, <10'	EA	2.000
	0425- 1-781	INLETS, MEDIAN BARRIER, TYPE 1, <=10'	EA	8.000

Call Order: 004 Proposal: T7472

ALT	Item	Description	Unit	Quantity
	0425- 1-783	INLETS, MEDIAN BARRIER, TYPE 1, J BOT, <10'	EA	9.000
	0425- 1-790	INLETS, MEDIAN BARRIER, TYPE 2, < =10'	EA	31.000
	0425- 1-792	INLETS, MEDIAN BARRIER, TYPE 2, >10'	EA	1.000
	0425- 1-793	INLETS, MEDIAN BARRIER, TYPE 2, J BOT, <10'	EA	6.000
	0425- 1-921	INLETS, ADJACENT BARRIER, <=10'	EA	75.000
	0425- 1-922	INLETS, ADJACENT BARRIER, >10'	EA	6.000
	0425- 1-923	INLETS, ADJACENT BARRIER, J BOTTOM, < 10'	EA	6.000
	0425- 1-924	INLETS, ADJACENT BARRIER, J BOTTOM, >10'	EA	2.000
	0425- 2- 61	MANHOLES, P-8, <10'	EA	41.000
	0425- 2- 62	MANHOLES, P-8, >10'	EA	1.000
	0425- 2- 63	MANHOLES, P-8, PARTIAL	EA	1.000
	0425- 2- 91	MANHOLES, J-8, <10'	EA	5.000
	0425- 2- 92	MANHOLES, J-8, >10'	EA	3.000
	0430-174-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"SD	LF	17.000
	0430-174-130	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 30"SD	LF	10.000
	0430-175-112	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 12"S/CD	LF	271.000
	0430-175-115	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 15"S/CD	LF	484.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	7,658.000
	0430-175-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	973.000
	0430-175-130	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	LF	2,042.000
	0430-175-136	PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	LF	105.000
	0430-175-142	PIPE CULVERT, OPT MATERIAL, ROUND, 42"S/CD	LF	326.000
	0430-175-148	PIPE CULVERT, OPT MATERIAL, ROUND, 48"S/CD	LF	26.000
	0430-175-218	PIPE CULVERT,OPTIONAL MATERIAL,OTHER-ELIP/ARCH, 18"S/CD	LF	197.000
	0430-175-236	PIPE CULVERT, OPT MATERIAL, OTHER SHAPE - ELIP/ARCH, 36"S/C	LF	10.000
	0430-185-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, JACK & BORE, 24", STORM AND CROSS DRAIN	LF	175.000
	0430-518-102	STRAIGHT CONCRETE ENDWALLS, 18", SINGLE, 0 DEGREES, ELLIPTICAL	EA	1.000
	0430-524-100	STRAIGHT CONCRETE ENDWALLS, 24", SINGLE, 0 DEGREES, ROUND	EA	1.000
	0430-548-100	STRAIGHT CONCRETE ENDWALLS, 48", SINGLE, 0 DEGREES, ROUND	EA	1.000
	0430-611-125	U-ENDWALL WITH BAFFLES, INDEX 261/430-011, 1:4 SLOPE, 18"PIPE	EA	1.000
	0430-611-129	U-ENDWALL WITH BAFFLES, INDEX 261/430-011, 1:4 SLOPE, 24"PIPE	EA	1.000
	0430-611-325	U-ENDWALL WITH BAFFLES, INDEX 261/430-011, 1:2 SLOPE, 18"PIPE	EA	6.000
	0430-830-	PIPE FILLING AND PLUGGING- PLACE OUT OF SERVICE	CY	22.600
	0430-982-125	MITERED END SECTION, OPTIONAL ROUND, 18" CD	EA	9.000
	0430-982-133	MITERED END SECTION, OPTIONAL ROUND, 30" CD	EA	7.000
	0430-982-625	MITERED END SECTION, OPTIONAL - ELLIPTICAL / ARCH, 18" CD	EA	8.000
	0430-982-638	MITERED END SECTION, OPTIONAL - ELLIPTICAL / ARCH, 36" CD	EA	1.000
	0430-984-129	MITERED END SECTION, OPTIONAL ROUND, 24" SD	EA	2.000
	0430-984-133	MITERED END SECTION , OPTIONAL ROUND, 30" SD	EA	2.000
	0440- 1- 50	UNDERDRAIN, TYPE V	LF	170.000
	0440- 70-	UNDERDRAIN INSPECTION BOX	EA	4.000
	0440- 73- 2	UNDERDRAIN OUTLET PIPE, 6"	LF	46.000

Call Order: 004 Proposal: T7472

ALT	Item	Description	Unit	Quantity
	0446- 1- 1	EDGEDRAIN DRAINCRETE, STANDARD	LF	46,923.000
	0446- 71- 1	EDGEDRAIN OUTLET PIPE, 4"	LF	523.000
	0451- 70-	PREST SOIL ANCHORS	EA	165.000
	0451- 70- 1	PRESTRESSED SOIL ANCHOR, PERFORMANCE TEST	EA	165.000
	0451- 70- 2	PRESTRESSED SOIL ANCHOR, CREEP TEST	EA	19.000
	0455- 35- 6	STEEL PILING, HP 14 X 89	LF	5,412.000
	0455-133- 2	SHEET PILING STEEL, TEMPORARY-CRITICAL	SF	248,721.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	687.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	1,645.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	129.000
	0520- 6-	SHOULDER GUTTER- CONCRETE	LF	724.000
	0520- 7- 1	GRANITE CURB, FURNISH & INSTALL	LF	15.000
	0520- 7- 2	GRANITE CURB, RESET	LF	275.000
	0520- 70-	CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH	SY	48.000
	0521- 1- 11	MEDIAN CONCRETE BARRIER, 38" HEIGHT	LF	8,613.000
	0521- 1- 13	MEDIAN CONCRETE BARRIER, TALL GRADE-SEPARATED	LF	1,963.000
	0521- 1- 14	MEDIAN CONCRETE BARRIER, VARIABLE SECTION WIDTH FOR SIGN OR PIER SHIELDING	LF	770.000
	0521- 8- 11	CONCRETE BARRIER, WITH JUNCTION SLAB, 8'-0" NOISE WALL	LF	7,592.000
	0521- 72- 24	SHOULDER CONCRETE BARRIER WALL, 8' NOISE WALL	LF	349.000
	0521- 72- 27	SHOULDER CONCRETE BARRIER WALL, 14' NOISE WALL	LF	13,060.000
	0521- 72- 40	SHOULDER CONCRETE BARRIER, 38" OR 44" HEIGHT	LF	2,597.000
	0521- 72- 43	SHOULDER CONCRETE BARRIER, CURB AND GUTTER BARRIER	LF	220.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	6,473.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	41.000
	0524- 1- 2	CONCRETE DITCH PAVEMENT, NON REINFORCED, 4"	SY	1,775.000
	0526- 1- 1	PAVERS, ARCHITECTURAL, ROADWAY	SY	778.000
	0527- 2-	DETECTABLE WARNINGS	SF	57.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	14.400
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	1,388.000
	0536- 73-	GUARDRAIL REMOVAL	LF	18,607.000
	0536- 85- 20	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE	EA	3.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	7.000
	0538- 1-	GUARDRAIL RESET	LF	69.000
	0544- 3- 1	CRASH CUSHION, TL-3, NARROW	EA	5.000
	0546- 72- 1	GROUND-IN RUMBLE STRIPS, 16"	GM	2.327
	0548- 12-	RETAINING WALL SYSTEM, PERMANENT, EXCLUDING BARRIER	SF	101,171.000
	0548- 13-	RETAINING WALL SYSTEM, TEMPORARY, EXCLUDING BARRIER	SF	639.000
	0548- 14-	RETAINING WALL SYSTEM, PERMANENT-WIDENING, ATTACHED TO EXISTING WALL	SF	5,263.000
	0550- 10-220	FENCING, TYPE B, 5.1-6.0', STANDARD	LF	7,650.000
	0550- 10-222	FENCING, TYPE B, 5.1-6.0, W/ VINYL COATING	LF	2,334.000
	0550- 10-810	FENCING, MESH WITH COATING, 4' ON GRAVITY WALL, PROJECT 431821-2-1-52-01, ETC	LF	1,546.000
	0550- 10-811	FENCING, MESH WITH COATING, 6', PROJECT 431821-2-1-52-01, ETC	LF	624.000
	0550- 10-813	FENCING, MESH WITH COATING, 8', PROJECT 431821-2-1-52-01, ETC	LF	144.000

Call Order: 004 Proposal: T7472

ALT	Item	Description	Unit	Quantity
	0550- 60-212	FENCE GATE, TYPE B, SINGLE, 6.1 - 12.0' OPENING	EA	1.000
	0550- 60-612	FENCE GATE, TYPE B VINYL, SINGLE, 6.1 - 12.0' OPENING	EA	6.000
	0550- 60-623	FENCE GATE, TYPE B VINYL, DOUBLE, 12.1-18.0' OPENING	EA	2.000
	0550- 60-806	FENCE GATE, 4' HEIGHT ON GRAVITY WALL, SINGLE, 4' OPENING, PROJECT 431821-2-52-01, ETC	EA	4.000
	0550- 60-807	FENCE GATE, 6' HEIGHT, DOUBLE, 9' OPENING, PROJECT 431821-2-52-01, ETC	EA	5.000
	0563- 4-	ANTI-GRAFFITI COATING, NON-SACRIFICIAL	SF	59,915.000
	0570- 1- 1	PERFORMANCE TURF	SY	122,227.000
	0571- 1- 11	PLASTIC EROSION MAT, TURF REINFORCED MAT, TYPE 1	SY	22,287.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	267.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	525.000
	0630- 2- 16	CONDUIT, FURNISH & INSTALL, EMBEDDED CONCRETE BARRIERS AND TRAFFIC RAILINGS	LF	20,314.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	7.000
	0695- 1- 1	TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL	EA	28.000
	0695- 6- 12	TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 2 LOOPS	EA	28.000
	0695- 7-162	TRAFFIC MONITORING SITE CABINET, F&I, TYPE 3, 2 PANE BACK, PEDESTAL MOUNT	EA	5.000
	0695- 7-600	TRAFFIC MONITORING SITE CABINET, REMOVE EXISTING CABINET	EA	4.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	28.660
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.737
	0710- 11-103	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE MARKINGS, 12"	GM	5.956
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	4,828.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	150.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	19.075
	0710- 11-133	PAINTED PAVEMENT MARKING, STANDARD, WHITE, 3'-9' SKIP DROP LINE AND APPROACH TO TOLL PLAZA, 12" WIDE,	GM	2.934
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	52.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	75.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	25.432
	0710- 11-202	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.039
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	720.000
	0710- 11-331	PAINTED PAVEMENT MARKINGS, STANDARD, BLACK, SKIP, 6"	GM	18.602
	0710- 11-333	PAINTED PAVEMENT MARKING, STANDARD, BLACK, 3'-9' DOTTED LANE DROP AND APPROACH TO TOLL PLAZA, 12"	GM	0.242
	0999- 16-	PARTNERING, DO NOT BID (43182125201)	LS	1.000
	0999- 20- 1	DISPUTES REVIEW BOARD, MEETING- DO NOT BID	DA	40.000
	0999- 20- 2	DISPUTES REVIEW BOARD, HEARING- DO NOT BID	EA	2.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43182125201)	LS	1.000

Call Order: 004 Proposal: T7472

ALT	Item	Description	Unit	Quantity
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44377015201)	LS	1.000
Section 0003 Signing				
	0563- 4-	ANTI-GRAFFITI COATING, NON-SACRIFICIAL	SF	27,588.000
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	42.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	18.000
	0700- 1- 14	SINGLE POST SIGN, F&I GROUND MOUNT, 31+ SF	AS	1.000
	0700- 1- 22	SINGLE POST SIGN, F&I BARRIER MOUNT INDEX 11871/700-013, 12-20 SF	AS	3.000
	0700- 1- 31	SINGLE POST SIGN, F&I BRIDGE MOUNT INDEX 11870/700-012, UP TO 12 SF	AS	2.000
	0700- 1- 32	SINGLE POST SIGN, F&I BRIDGE MOUNT INDEX 11870/700-012, 12-20 SF	AS	13.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	83.000
	0700- 1- 74	SINGLE POST SIGN, F&I CUSTOM, 31+ SF	AS	6.000
	0700- 2- 14	MULTI- POST SIGN, F&I GROUND MOUNT, 31-50 SF	AS	1.000
	0700- 2- 18	MULTI- POST SIGN, F&I GROUND MOUNT, 301-400 SF	AS	1.000
	0700- 2- 50	MULTI- POST SIGN, GROUND MOUNT, RELOCATE	AS	4.000
	0700- 2- 60	MULTI- POST SIGN, REMOVE	AS	5.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	6.000
	0700- 3-203	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 21-30 SF	EA	28.000
	0700- 3-205	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 51-100 SF	EA	8.000
	0700- 3-206	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 101-200 SF	EA	8.000
	0700- 3-207	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 201-300 SF	EA	23.000
	0700- 3-208	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 301-400 SF	EA	2.000
	0700- 3-302	SIGN PANEL, FURNISH & INSTALL SINGLE POST BRIDGE MOUNT INDEX 11870/700-012, 12-20 SF	EA	7.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	5.000
	0700- 3-602	SIGN PANEL, REMOVE, 12-20 SF	EA	7.000
	0700- 3-603	SIGN PANEL, REMOVE, 21-30 SF	EA	21.000
	0700- 3-604	SIGN PANEL, REMOVE, 31-50 SF	EA	2.000
	0700- 3-605	SIGN PANEL, REMOVE, 51-100 SF	EA	3.000
	0700- 3-606	SIGN PANEL, REMOVE, 101-200 SF	EA	7.000
	0700- 3-607	SIGN PANEL, REMOVE, 201-300 SF	EA	20.000
	0700- 4-131	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, MONOTUBE, UP TO 20 FT	EA	1.000
	0700- 4-133	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, MONOTUBE, 31-40 FT	EA	4.000
	0700- 4-134	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, MONOTUBE, 41-50 FT	EA	3.000
	0700- 4-135	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, MONOTUBE- SPAN, 51-100 FT	EA	6.000
	0700- 4-136	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, MONOTUBE-SPAN, 101-150 FT	EA	1.000
	0700- 4-137	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, MONOTUBE-SPAN, 151-200 FT	EA	1.000
	0700- 4-140	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, OVERPASS BRIDGE MOUNT	EA	4.000
	0700- 4-630	OVERHEAD STATIC SIGN STRUCTURE, REMOVE MONOTUBE	EA	14.000

Call Order: 004 Proposal: T7472

ALT	Item	Description	Unit	Quantity
	0700- 4-640	OVERHEAD STATIC SIGN STRUCTURE, REMOVE BRIDGE MOUNT	EA	4.000
	0700- 13- 12	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 2'	EA	18.000
	0701- 17-101	PROFIED THERMOPLASTIC,STANDARD- CONCRETE SURFACES, WHITE, SOLID,6"	GM	1.888
	0701- 17-201	PROFIED THERMOPLASTIC,STANDARD- CONCRETE SURFACES, YELLOW, SOLID,6"	GM	4.195
	0705- 10- 3	OBJECT MARKER, TYPE 3	EA	4.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43182125201)	LS	1.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44377015201)	LS	1.000
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	0.139
	0711- 11-103	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR INTERCHANGE MARKINGS	GM	2.186
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	59.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	3,227.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	26.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	6.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	689.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	39.000
	0711- 14-560	THERMOPLASTIC, PREFORMED, WHITE WITH BLACK CONTRAST ON CONCRETE PAVEMENT, MESSAGE OR SYMBOL	EA	43.000
	0711- 14-570	THERMOPLASTIC, PREFORMED, WHITE WITH BLACK CONTRAST, ARROW ON CONCRETE SURFACE	EA	53.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	5.378
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.140
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.030
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	5.411
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.445
	0713-103-103	PERMANENT TAPE, WHITE, SOLID LANE DROP MARKING, 12" FOR CONCRETE BRIDGES	GM	0.243
	0713-103-131	PERMANENT TAPE, WHITE, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	13.228
	0713-103-133	PERMANENT TAPE, WHITE, SKIP, 12" WIDE 3'-9' DROP LANE ON CONCRETE SURFACES	GM	2.453
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.445
	0713-103-331	PERMANENT TAPE, BLACK, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	13.037
	0713-103-333	PERMANENT TAPE, BLACK, 3'-9' DROP LANE, 12" ON CONCRETE SURFACES	GM	1.228
Section 0004 Lighting				
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	3.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	16,364.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	5,480.000

Call Order: 004 Proposal: T7472

ALT	Item	Description	Unit	Quantity
	0630- 2- 14	CONDUIT, FURNISH & INSTALL, ABOVEGROUND	LF	1,170.000
	0630- 2- 15	CONDUIT, FURNISH & INSTALL, BRIDGE MOUNT	LF	65.000
	0630- 2- 65	CONDUIT, REMOVE, BRIDGE MOUNT	LF	280.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	147.000
	0635- 3- 11	JUNCTION BOX, FURNISH & INSTALL, AERIAL	EA	2.000
	0635- 3- 13	JUNCTION BOX, FURNISH & INSTALL, EMBEDDED	EA	73.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	3.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	70.000
	0715- 1- 11	LIGHTING CONDUCTORS, F&I, INSULATED, NO. 10 OR <	LF	9,434.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	95,011.000
	0715- 1- 13	LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2	LF	9,297.000
	0715- 1- 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	LF	58,710.000
	0715- 4- 15	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 50' MOUNTING HEIGHT	EA	102.000
	0715- 4- 25	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE SPECIAL FOUNDATION, 50' MOUNTING HEIGHT	EA	7.000
	0715- 4- 70	LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION	EA	83.000
	0715- 5- 51	LUMINAIRE & BRACKET ARM, REMOVE LUMINAIRE AND ARM; POLE REMAINS	EA	10.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	3.000
	0715- 11-125	LUMINAIRE, F&I, UNDER DECK, WALL MOUNT	EA	64.000
	0715- 11-213	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, POLE TOP	EA	4.000
	0715- 11-500	LUMINAIRE, REMOVE	EA	56.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	109.000
	0715-500- 3	POLE CABLE DISTRIBUTION SYSTEM, WALL MOUNT	EA	52.000
	0715-516-150	LIGHT POLE COMPLETE- SPECIAL DESIGN, F&I, POLE TOP MOUNT, ALUMINUM, 50'	EA	52.000
Section 0005 Intelligent Transportation System				
	0550- 10-236	FENCING, TYPE B, 6.1-7.0', WITH VINYL COATING AND BARBED WIRE ATTACHMENT	LF	188.000
	0550- 60-622	FENCE GATE, TYPE B WITH VINYL COATING, DOUBLE, 6.1-12.0' OPENING	EA	2.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	3,273.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	29,034.000
	0630- 2- 14	CONDUIT, FURNISH & INSTALL, ABOVEGROUND	LF	1,352.000
	0633- 1-121	FIBER OPTIC CABLE, F&I, UNDERGROUND,2-12 FIBERS	LF	11,020.000
	0633- 1-124	FIBER OPTIC CABLE, F&I, UNDERGROUND, 97 - 144 FIBERS	LF	42,970.000
	0633- 1-320	FIBER OPTIC CABLE, INSTALL, UNDERGROUND	LF	80.000
	0633- 1-620	FIBER OPTIC CABLE, REMOVE, UNDERGROUND	LF	16,053.000
	0633- 2- 31	FIBER OPTIC CONNECTION, INSTALL, SPLICE	EA	480.000
	0633- 3- 11	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE ENCLOSURE	EA	27.000
	0633- 3- 12	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE TRAY	EA	48.000
	0633- 3- 15	FIBER OPTIC CONNECTION HARDWARE, F&I, PRETERMINATED PATCH PANEL	EA	21.000

Call Order: 004 Proposal: T7472

ALT	Item	Description	Unit	Quantity
	0633- 8- 1	MULTI-CONDUCTOR COMMUNICATION CABLE, FURNISH & INSTALL	LF	1,005.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	59.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	67.000
	0635- 2- 13	PULL & SPLICE BOX, F&I, 30" X 60" RECTANGULAR OR 36" ROUND COVER SIZE	EA	30.000
	0639- 1-610	ELECTRICAL POWER SERVICE, REMOVE OVERHEAD	AS	3.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	13,607.000
	0639- 2- 6	ELECTRICAL SERVICE WIRE, REMOVE	LF	1,871.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	22.000
	0639- 5- 25	EMERGENCY GENERATOR- PERMANENT UP TO 25 KW, PROJECTS 443770-1-52-01/431821-2-52-01	EA	2.000
	0639- 6- 1	ELECTRICAL POWER SERVICE- TRANSFORMER FURNISH & INSTALL	EA	21.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	16.000
	0641- 2- 13	PRESTRESSED CONCRETE POLE, F&I, TYPE P-III	EA	7.000
	0641- 2- 60	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- PEDESTAL/SERVICE POLE	EA	9.000
	0641- 3-175	CONCRETE CCTV POLE, FURNISH & INSTALL WITH LOWERING DEVICE, 75'	EA	2.000
	0641- 3-186	CONCRETE CCTV POLE, FURNISH & INSTALL WITH LOWERING DEVICE, 86'	EA	2.000
	0649- 2-605	STEEL CCTV POLE, REMOVE POLE- COMPLETE/DEEP FOUNDATION REMOVAL, BOLT ON ATTACHMENT	EA	3.000
	0660- 3- 11	VEHICLE DETECTION SYSTEM- MICROWAVE, FURNISH & INSTALL CABINET EQUIPMENT	EA	12.000
	0660- 3- 12	VEHICLE DETECTION SYSTEM- MICROWAVE, FURNISH & INSTALL, ABOVE GROUND EQUIPMENT	EA	12.000
	0660- 3- 60	VEHICLE DETECTION SYSTEM - MICROWAVE, REMOVE, COMPLETE SYSTEM	EA	9.000
	0660- 7- 11	VEHICLE DETECTION SYSTEM- WRONG WAY FOR EXIT RAMP, 1 OR 2 LANES	EA	6.000
	0676- 2-122	ITS CABINET, FURNISH & INSTALL, POLE MOUNT WITH SUNSHIELD, 336S, 24" W X 46" H X 22" D	EA	6.000
	0676- 2-143	ITS CABINET, FURNISH & INSTALL, BASE MOUNT, 334, 24" W X 66" H X 30" D	EA	7.000
	0676- 2-600	ITS CABINET- REMOVE	EA	7.000
	0682- 1-113	ITS CCTV CAMERA, F&I, DOME PTZ ENCLOSURE - PRESSURIZED, IP, HIGH DEFINITION	EA	7.000
	0684- 1- 1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	EA	19.000
	0684- 2- 1	DEVICE SERVER, FURNISH & INSTALL	EA	13.000
	0684- 6- 40	WIRELESS COMMUNICATION DEVICE, RELOCATE	EA	2.000
	0685- 1- 11	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, LINE INTERACTIVE	EA	13.000
	0685- 2- 1	REMOTE POWER MANAGEMENT UNIT- RPMU, FURNISH AND INSTALL	EA	13.000
	0700- 6- 11	HIGHLIGHTED SIGN, F&I GROUND MOUNT- AC POWERED, UP TO 12 SF	AS	12.000
	0700- 9-137	WALK-IN DYNAMIC MESSAGE SIGN, FURNISH & INSTALL- WITH UPS FULL COLOR, 201-300 SF	EA	2.000
	0700- 9-600	WALK-IN DYNAMIC MESSAGE SIGN, REMOVE	EA	2.000