

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 08190226 Call Order: 001 Proposal: E8Q79 District:08

Counties: PALM BEACH

Road Name: TURNPIKE MAINLINE WIDENING

Limits: 93470000

Project(s): 40614415201(*) Federal Aid No: N/A

Project(s): 40614415202 Federal Aid No: N/A

Project(s): 40614415602 Federal Aid No: N/A

Total Roadway Length:	42.000 Miles	Contract Days:	1645
Total Bridge Length:	0.185 Miles	Letting Date:	02/26/19
Total Proposal Length:	42.185 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	30

Proposal Budget Estimate: \$173,672,165.00

Please read the full advertisement

Description:

Work consists of providing all labor, materials, equipment and incidentals necessary for widening approximately 7.6 miles of Floridas Turnpike mainline from four and six lanes to eight lanes from north of SR 804 (Boynton Beach Boulevard) (milepost 87.1) to north of SR 802 (Lake Worth Road) (milepost 94.7). The typical section consists of one future express lane and three general tolled lanes in each direction. This project proposes to realign the Turnpikes centerline to the west to prevent the proposed improvements from encroaching into the Florida Gas Transmission (FGT) facility specified width and mitigate the risk of possible triggering events. This project also includes the construction of the mainline AET toll facilities and partial reconstruction of the existing Lantana Toll Plaza to accommodate six through lanes, with the remainder of ticket lanes (four in each direction) to remain in operation. No Pre-Bid Conference. Contractor must be prequalified.

The summary of pay items for this project is listed in the Plans

Call Order: 001 Proposal: E8Q79

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (40614415201)	LS	1.000
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (40614415201)	LS	1.000
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (40614415201)	LS	1.000
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (40614415201)	LS	1.000
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (40614415201)	LS	1.000
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (40614415201)	LS	1.000
	0400- 2- 4	CONC CLASS II, BRIDGE SUPERSTRUCTURE	CY	1,566.000
	0400- 2- 10	CONCRETE CLASS II, APPROACH SLABS	CY	341.000
	0400- 4- 5	CONCRETE CLASS IV, BRIDGE SUBSTRUCTURE	CY	291.300
	0400- 4- 25	CONCRETE CLASS IV, MASS, SUBSTRUCTURE	CY	267.000
	0400- 7-	BRIDGE DECK GROOVING, LESS THAN 8.5"	SY	2,243.000
	0400- 9-	BRIDGE DECK GROOVING & PLANING, DECK 8.5" AND GREATER	SY	2,920.000
	0400-143-	CLEANING & COATING CONCRETE SURFACE, CLASS 5	SF	6,822.000
	0400-145-	CLEANING CONCRETE SURFACE	SF	53,430.000
	0400-147-	COMPOSITE NEOPRENE PADS	CF	26.700
	0415- 1- 4	REINFORCING STEEL - BRIDGE SUPERSTRUCTURE	LB	379,853.000
	0415- 1- 5	REINFORCING STEEL- BRIDGE SUBSTRUCTURE	LB	123,520.000

Call Order: 001 Proposal: E8Q79

ALT	Item	Description	Unit	Quantity
	0415- 1- 9	REINFORCING STEEL- APPROACH SLABS	LB	57,842.000
	0450- 2- 36	PREST BEAMS: FLORIDA-I BEAM 36"	LF	260.000
	0450- 2- 54	PREST BEAMS: FLORIDA-I BEAM 54"	LF	1,988.000
	0450- 2- 63	PREST BEAMS: FLORIDA-I BEAM 63"	LF	2,250.000
	0450- 2- 72	PREST BEAMS: FLORIDA-I BEAM 72"	LF	795.000
	0455- 34- 3	PRESTRESSED CONCRETE PILING, 18" SQ	LF	5,740.000
	0455- 34-309	PRESTRESSED CONCRETE PILING, INCLUDES 100% DYNAMIC TESTING, PROJECT 406144-1-52-01, SIZE 18"	LF	1,320.000
	0455-143- 3	TEST PILES-PRESTRESSED CONCRETE,18" SQ	LF	380.000
	0458- 1- 11	BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&I POURED JOINT WITH BACKER ROD	LF	621.000
	0458- 1- 21	BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITH BACKER ROD	LF	675.000
	0459- 71-	PILES, POLYETHYLENE SHEETING	SY	140.000
	0460- 71- 4	METAL TRAFFIC RAILING, RECTANGULAR TUBE RETROFIT	LF	333.000
	0521- 5- 12	CONCRETE TRAFFIC RAILING- BRIDGE, 36" MEDIAN SINGLE SLOPE	LF	977.000
	0521- 5- 13	CONCRETE TRAFFIC RAILING- BRIDGE, 36" SINGLE-SLOPE	LF	1,262.000
	0521- 5- 22	CONCRETE TRAFFIC RAILING- BRIDGE, 8'-0" NOISE WALL	LF	493.000
	0521- 6- 11	CONCRETE PARAPET, PEDESTRIAN/BICYCLE, 27" HEIGHT	LF	942.000
	0550- 10-353	FENCING, TYPE R, 8.1 - 10.0', WITH FULL ENCLOSURE	LF	942.000
	0630- 2- 15	CONDUIT, FURNISH & INSTALL, BRIDGE MOUNT	LF	522.000
	0630- 2- 16	CONDUIT, FURNISH & INSTALL, EMBEDDED CONCRETE BARRIERS AND TRAFFIC RAILINGS	LF	6,009.000
	0635- 3- 13	JUNCTION BOX, FURNISH & INSTALL, EMBEDDED	EA	20.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (40614415201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (40614415201)	LS	1.000
	0102- 2- 1	SPECIAL DETOUR 1 (40614415201)	LS	1.000
	0102- 2- 2	SPECIAL DETOUR 2 (40614415201)	LS	1.000
	0102- 2- 3	SPECIAL DETOUR 3 (40614415201)	LS	1.000
	0102- 2- 4	SPECIAL DETOUR 4 (40614415201)	LS	1.000
	0102- 2- 5	SPECIAL DETOUR 5 (40614415201)	LS	1.000
	0102- 2- 6	SPECIAL DETOUR 6 (40614415201)	LS	1.000
	0102- 2- 7	SPECIAL DETOUR 7 (40614415201)	LS	1.000
	0102- 2- 8	SPECIAL DETOUR 8 (40614415201)	LS	1.000
	0102- 2- 9	SPECIAL DETOUR 9 (40614415201)	LS	1.000
	0102- 30- 1	TEMPORARY HIGHWAY LIGHTING, PROJECT 406144-1-52-01	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	161,963.000
	0102- 62-	BARRIER MOUNTED WORK ZONE SIGN- INDEX 11871/700-013	ED	45,900.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	67,059.000
	0102- 71- 16	TEMPORARY BARRIER, F&I, FREE STANDING	LF	11,933.000
	0102- 71- 25	TEMPORARY BARRIER, RELOCATE, ANCHORED	LF	136,926.000
	0102- 71- 26	TEMPORARY BARRIER, RELOCATE, FREE STANDING	LF	13,540.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	253,118.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	890.000

Call Order: 001 Proposal: E8Q79

ALT	Item	Description	Unit	Quantity
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	88.000
	0102- 75- 3	TEMPORARY SEPARATOR, INSTALL	LF	2,219.000
	0102- 75- 4	TEMPORARY SEPARATOR, RELOCATE	LF	2,164.000
	0102- 75- 5	TEMPORARY SEPARATOR, REMOVE	LF	2,219.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	2,171.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	36,699.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	71.000
	0102- 94- 1	TEMPORARY GLARE SCREEN, F&I, WALL MATERIAL-CONCRETE	LF	1,629.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,367.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	694.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	434.000
	0102-911- 1	PAVEMENT MARKING REMOVABLE TAPE, WHITE OR BLACK, SKIP	LF	1,220.000
	0102-911- 2	PAVEMENT MARKING REMOVABLE TAPE, WHITE OR BLACK,SOLID	LF	2,834.000
	0102-912- 2	PAVEMENT MARKING REMOVABLE TAPE, YELLOW, SOLID	LF	2,316.000
	0104- 10- 3	SEDIMENT BARRIER	LF	60,391.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	14,412.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	5,386.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	9.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	473.000
	0107- 1-	LITTER REMOVAL	AC	4,040.000
	0107- 2-	MOWING	AC	3,150.000
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (40614415201)	LS	1.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (40614415201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (40614415201)	LS	1.000
	0110- 2- 2	SELECTIVE CLEARING AND GRUBBING, AREAS WITH TREES TO REMAIN	AC	10.080
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	8,912.000
	0120- 1-	REGULAR EXCAVATION	CY	203,883.000
	0120- 5-	CHANNEL EXCAVATION	CY	38,721.000
	0120- 6-	EMBANKMENT	CY	296,779.000
	0120- 72- 10	GRAVEL FILL- BERM, PROJECT 406144-1-52-01	CY	12,220.000
	0145- 2-	GEOSYNTHETIC REINFORCED FOUNDATION OVER SOFT SOIL	SY	45,653.000
	0160- 4-	TYPE B STABILIZATION	SY	440,992.000
	0162- 1- 11	PREPARED SOIL LAYER, FINISH SOIL LAYER, 6"	SY	8,324.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	1,004.000
	0285-702-	OPTIONAL BASE, BASE GROUP 02	SY	2,470.000
	0285-705-	OPTIONAL BASE, BASE GROUP 05	SY	145,897.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	2,183.000
	0285-711-	OPTIONAL BASE, BASE GROUP 11	SY	1,844.000
	0285-712-	OPTIONAL BASE, BASE GROUP 12	SY	171,319.000
	0285-713-	OPTIONAL BASE, BASE GROUP 13	SY	199.000
	0285-714-	OPTIONAL BASE, BASE GROUP 14	SY	67,132.000
	0285-715-	OPTIONAL BASE, BASE GROUP 15	SY	42,379.000

Call Order: 001 Proposal: E8Q79

ALT	Item	Description	Unit	Quantity
	0327- 70- 1	MILLING EXIST ASPH PAVT, 1" AVG DEPTH	SY	19,219.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	28,635.000
	0327- 70- 11	MILLING EXIST ASPH PAVT, 2 1/4" AVG DEPTH	SY	6,298.000
	0327- 70- 15	MILLING EXIST ASPH PAVT, 2 3/4" AVG DEPTH	SY	231,109.000
	0334- 1- 11	SUPERPAVE ASPHALTIC CONC, TRAFFIC A	TN	373.100
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	24,028.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	168.500
	0334- 1- 14	SUPERPAVE ASPHALTIC CONC, TRAFFIC D	TN	186,713.300
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	519.900
	0334- 1- 54	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC D, PG76-22	TN	49,794.000
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	16,324.000
	0337- 7- 82	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-9.5, PG 76-22	TN	741.400
	0337- 7- 85	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC D, FC-12.5, PG 76-22	TN	4,815.700
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	1,100.000
	0400- 0- 11	CONCRETE CLASS NS, GRAVITY WALL	CY	1,323.000
	0400- 1- 2	CONCRETE CLASS I, ENDWALLS	CY	139.200
	0400- 2- 2	CONCRETE CLASS II, ENDWALLS	CY	28.800
	0400- 4- 8	CONC CLASS IV, BULKHEAD	CY	10,111.00C
	0415- 1- 8	REINFORCING STEEL- BULKHEAD	LB	1,295,769.000
	0425- 1-545	INLETS, DITCH BOTTOM, TYPE D, PARTIAL	EA	1.000
	0425- 1-549	INLETS, DT BOT, TYPE D, MODIFY	EA	9.000
	0425- 1-575	INLETS, DITCH BOTTOM, TYPE G, PARTIAL	EA	2.000
	0425- 1-585	INLETS, DT BOT, TYPE H, PARTIAL	EA	2.000
	0425- 1-701	INLETS, GUTTER, TYPE S, <10'	EA	42.000
	0425- 1-781	INLETS, MEDIAN BARRIER, TYPE 1, <=10'	EA	5.000
	0425- 1-783	INLETS, MEDIAN BARRIER, TYPE 1, J BOT, <10'	EA	41.000
	0425- 1-791	INLETS, MEDIAN BARRIER, TYPE 2, J BOT, <=10'	EA	76.000
	0425- 1-793	INLETS, MEDIAN BARRIER, TYPE 2, J BOT, <10'	EA	25.000
	0425- 1-799	INLETS, MEDIAN BARRIER, TYPE 2, MODIFY	EA	2.000
	0425- 1-891	INLETS, BARRIER WALL, <=10'	EA	61.000
	0425- 1-893	INLETS, BARRIER WALL, J BOT, <10'	EA	23.000
	0425- 1-899	INLETS, BARRIER WALL, MODIFY	EA	132.000
	0425- 2- 41	MANHOLES, P-7, <10'	EA	10.000
	0425- 2- 43	MANHOLES, P-7, PARTIAL	EA	1.000
	0425- 2- 71	MANHOLES, J-7, <10'	EA	1.000
	0425- 2- 72	MANHOLES, J-7, >10'	EA	1.000
	0425- 3- 41	JUNCTION BOX, DRAINAGE, P-7, <10'	EA	1.000
	0425- 3- 43	JUNCTION BOX, DRAINAGE, P-7, PARTIAL	EA	1.000
	0425- 3- 61	JUNCTION BOXES, J-7, <10'	EA	1.000
	0425- 5- 1	MANHOLE, ADJUST, UTILITIES	EA	3.000
	0430- 94- 1	DESILTING PIPE, 0 - 24"	LF	14,437.000
	0430- 96-	DRAINAGE PIPE REPAIR- CONCRETE COLLAR AT JOINT	EA	24.000
	0430-175-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD	LF	26,773.000
	0430-175-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"S/CD	LF	5,888.000

Call Order: 001 Proposal: E8Q79

ALT	Item	Description	Unit	Quantity
	0430-175-130	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	LF	1,098.000
	0430-175-136	PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	LF	664.000
	0430-175-148	PIPE CULVERT, OPT MATERIAL, ROUND, 48"S/CD	LF	8.000
	0430-175-172	PIPE CULVERT, OPT MATERIAL, ROUND, 72"S/CD	LF	196.000
	0430-185-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, JACK & BORE, 24", STORM AND CROSS DRAIN	LF	81.000
	0430-200- 25	FLARED END SECTION, CONCRETE, 18"	EA	32.000
	0430-200- 29	FLARED END SECTION, CONCRETE, 24"	EA	2.000
	0430-611-125	U-ENDWALL WITH BAFFLES, INDEX 261/430-011, 1:4 SLOPE, 18"PIPE	EA	3.000
	0430-611-129	U-ENDWALL WITH BAFFLES, INDEX 261/430-011, 1:4 SLOPE, 24"PIPE	EA	2.000
	0430-611-133	U-ENDWALL WITH BAFFLES, INDEX 261/430-011,1:4 SLOPE,30"PIPE	EA	2.000
	0430-612-025	U-ENDWALL WITH GRATE, INDEX 261/430-011, 1:6 SLOPE, 18"PIPE	EA	15.000
	0430-613-033	U-ENDWALL, WITH BAFFLES & GRATE, INDEX 261/430-011,1:6 SLOPE, 30"	EA	2.000
	0430-821- 25	CLEANING & SEALING EXISTING PIPE JOINT, 18" STORM SEWER	EA	2.000
	0430-821- 29	CLEANING & SEALING EXISTING PIPE JOINT, 24" STORM SEWER	EA	4.000
	0430-830-	PIPE FILLING AND PLUGGING- PLACE OUT OF SERVICE	CY	27.000
	0430-890-100	SLIDE GATE, 72", PROJECT 406144-1-52-01	EA	1.000
	0430-982-125	MITERED END SECTION, OPTIONAL ROUND, 18" CD	EA	1.000
	0430-982-129	MITERED END SECTION, OPTIONAL ROUND, 24" CD	EA	4.000
	0431- 1-205	PIPE LINER,REPAIR BY SLIPLINING, 0-24", PROJECT 406144-1-52-01	LF	1,245.000
	0436- 1- 1	TRENCH DRAIN, STANDARD	LF	806.000
	0455- 34- 5	PRESTRESSED CONCRETE PILING, 24" SQ	LF	93,104.000
	0455-133- 2	SHEET PILING STEEL, TEMPORARY-CRITICAL	SF	68,569.000
	0455-143- 5	TEST PILES-PRESTRESSED CONCRETE,24" SQ	LF	500.000
	0460- 71- 4	METAL TRAFFIC RAILING, RECTANGULAR TUBE RETROFIT	LF	957.000
	0515- 1- 2	PIPE HANDRAIL - GUIDERAIL, ALUMINUM	LF	178.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	577.000
	0520- 6-	SHOULDER GUTTER- CONCRETE	LF	6,705.000
	0521- 1- 11	MEDIAN CONCRETE BARRIER, 38" HEIGHT	LF	19,073.000
	0521- 1- 12	MEDIAN CONCRETE BARRIER, SHORT GRADE-SEPARATED	LF	11,704.000
	0521- 1- 13	MEDIAN CONCRETE BARRIER, TALL GRADE-SEPARATED	LF	3,682.000
	0521- 1- 14	MEDIAN CONCRETE BARRIER, VARIABLE SECTION WIDTH FOR SIGN OR PIER SHIELDING	LF	1,906.000
	0521- 8- 7	CONCRETE BARRIER, WITH JUNCTION SLAB, 36" SINGLE SLOPE	LF	18,811.000
	0521- 8- 11	CONCRETE BARRIER, WITH JUNCTION SLAB, 8'-0" NOISE WALL	LF	14,804.000
	0521- 72- 24	SHOULDER CONCRETE BARRIER WALL, 8' NOISE WALL	LF	802.000
	0521- 72- 27	SHOULDER CONCRETE BARRIER WALL, 14' NOISE WALL	LF	18,746.000
	0521- 72- 40	SHOULDER CONCRETE BARRIER, 38" OR 44" HEIGHT	LF	2,296.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	46.000
	0524- 1- 49	CONCRETE DITCH PAVEMENT, 6", REINFORCED	SY	827.000
	0524- 2- 2	CONCRETE SLOPE PAVEMENT, NON REINFORCED, 4"	SY	6,298.000
	0530- 1-	RIPRAP, SAND-CEMENT	CY	140.200
	0530- 3- 3	RIPRAP- RUBBLE, BANK AND SHORE	TN	32,054.200
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	5,330.700
	0530- 74-	BEDDING STONE	TN	19,839.500

Call Order: 001 Proposal: E8Q79

ALT	Item	Description	Unit	Quantity
	0534- 72-101	SOUND/NOISE BARRIER-INC FOUNDATION, PERMANENT	SF	44,450.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	25,453.000
	0536- 1- 3	GUARDRAIL- ROADWAY, DOUBLE FACE	LF	256.000
	0536- 7- 3	SPECIAL GUARDRAIL POST- ENCASED POST FOR SHALLOW MOUNT	EA	3,709.000
	0536- 8- 11	APPROACH TRANSITION TO RIGID BARRIER CONNECTION, FURNISH & INSTALL	EA	6.000
	0536- 8- 13	APPROACH TRANSITION CONNECTION TO RIGID BARRIER, FURNISH AND INSTALL, TL-3	EA	18.000
	0536- 73-	GUARDRAIL REMOVAL	LF	60,198.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	15.000
	0536- 85- 25	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE TYPE II	EA	15.000
	0536- 85- 27	GUARDRAIL END TREATMENT- DOUBLE FACE APPROACH TERMINAL	EA	1.000
	0544- 75- 1	CRASH CUSHION	EA	16.000
	0546- 72- 1	GROUND-IN RUMBLE STRIPS, 16"	GM	17.004
	0548- 12-	RETAINING WALL SYSTEM, PERMANENT, EXCLUDING BARRIER	SF	248,329.000
	0548- 13-	RETAINING WALL SYSTEM,TEMPORARY, EXCLUDING BARRIER	SF	11,071.000
	0550- 10-221	FENCING, TYPE B, 5.1-6.0', W/ BARB WIRE ATTMT	LF	12,834.000
	0550- 60-211	FENCE GATE, TYPE B, SINGLE, 0- 6.0' OPENING	EA	2.000
	0550- 60-232	FENCE GATE, TYPE B, SLIDING/CANTILEVER, 6.1-12' OPENING	EA	2.000
	0570- 1- 1	PERFORMANCE TURF	SY	111,237.00C
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	199,144.000
	0639- 8- 3	ELECTRICAL POWER SERVICE- CONTRIBUTION IN AID OF CONSTRUCTION (CIAC), PROJECT 406144-1-52-01	LS	1.000
	0700- 2- 16	MULTI- POST SIGN, F&I GROUND MOUNT, 101-200 SF	AS	5.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	59.473
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	1.298
	0710- 11-103	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE MARKINGS, 12"	GM	8.890
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	47.024
	0710- 11-133	PAINTED PAVEMENT MARKING, STANDARD,WHITE, 3'-9' SKIP DROP LINE AND APPROACH TO TOLL PLAZA, 12" WIDE,	GM	2.215
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	1.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	1.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	44.339
	0710- 11-202	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.887
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	152.000
	0999- 16-	PARTNERING, DO NOT BID (40614415201)	LS	1.000
	0999- 20- 1	DISPUTES REVIEW BOARD, MEETING- DO NOT BID	DA	27.000
	0999- 20- 2	DISPUTES REVIEW BOARD, HEARING- DO NOT BID	EA	2.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (40614415201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (40614415202)	LS	1.000

Call Order: 001 Proposal: E8Q79

ALT	Item	Description	Unit	Quantity
Section 0003 Signing				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	824.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	60.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	4.000
	0639- 1-113	ELECTRICAL POWER SERVICE, F&I, OVERHEAD METER NOT REQUIRED	AS	1.000
	0676- 2-131	ITS CABINET, FURNISH & INSTALL, BASE MOUNT, 336, 24" W X 36" H X 20" D	EA	1.000
	0695- 1- 1	TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL	EA	12.000
	0695- 6- 12	TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 2 LOOPS	EA	12.000
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	41.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	29.000
	0700- 1- 13	SINGLE POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	2.000
	0700- 1- 14	SINGLE POST SIGN, F&I GROUND MOUNT, 31+ SF	AS	4.000
	0700- 1- 22	SINGLE POST SIGN, F&I BARRIER MOUNT INDEX 11871/700-013, 12-20 SF	AS	2.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	92.000
	0700- 2- 14	MULTI- POST SIGN, F&I GROUND MOUNT, 31-50 SF	AS	1.000
	0700- 2- 15	MULTI- POST SIGN, F&I GROUND MOUNT, 51-100 SF	AS	8.000
	0700- 2- 16	MULTI- POST SIGN, F&I GROUND MOUNT, 101-200 SF	AS	3.000
	0700- 2- 60	MULTI- POST SIGN, REMOVE	AS	28.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	1.000
	0700- 3-202	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 12-20 SF	EA	3.000
	0700- 3-203	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 21-30 SF	EA	11.000
	0700- 3-205	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 51-100 SF	EA	2.000
	0700- 3-206	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 101-200 SF	EA	11.000
	0700- 3-207	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 201-300 SF	EA	12.000
	0700- 3-208	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 301-400 SF	EA	1.000
	0700- 3-404	SIGN PANEL, INSTALL, 31-50 SF	EA	1.000
	0700- 3-603	SIGN PANEL, REMOVE, 21-30 SF	EA	8.000
	0700- 3-605	SIGN PANEL, REMOVE, 51-100 SF	EA	2.000
	0700- 3-606	SIGN PANEL, REMOVE, 101-200 SF	EA	5.000
	0700- 3-607	SIGN PANEL, REMOVE, 201-300 SF	EA	12.000
	0700- 4-112	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, CANTILEVER, 21-30 FT	EA	3.000
	0700- 4-113	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, CANTILEVER, 31-40 FT	EA	5.000
	0700- 4-122	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, SPAN, 21-30 FT	EA	1.000
	0700- 4-123	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, SPAN, 31-40 FT	EA	2.000
	0700- 4-125	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, SPAN, 51-100 FT	EA	4.000
	0700- 4-127	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, SPAN, 151-200 FT	EA	1.000

Call Order: 001 Proposal: E8Q79

ALT	Item	Description	Unit	Quantity
	0700- 4-140	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, OVERPASS BRIDGE MOUNT	EA	2.000
	0700- 4-610	OVERHEAD STATIC SIGN STRUCTURE, REMOVE CANTILEVER	EA	14.000
	0700- 4-620	OVERHEAD STATIC SIGN STRUCTURE, REMOVE SPAN	EA	1.000
	0700- 4-640	OVERHEAD STATIC SIGN STRUCTURE, REMOVE BRIDGE MOUNT	EA	2.000
	0700- 7-111	EMBEDDED DYNAMIC MESSAGE SIGN, FURNISH & INSTALL- WITH UPS, MONOCHROME, UP TO 12 SF	EA	4.000
	0701- 17-101	PROFILED THERMOPLASTIC,STANDARD- CONCRETE SURFACES, WHITE, SOLID,6"	GM	0.210
	0701- 17-201	PROFILED THERMOPLASTIC,STANDARD- CONCRETE SURFACES, YELLOW, SOLID,6"	GM	0.170
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	891.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (40614415201)	LS	1.000
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	5.270
	0711- 11-103	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR INTERCHANGE MARKINGS	GM	4.080
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	8,142.000
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	1.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	1.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	12,312.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	16.790
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	28.750
	0711- 15-133	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 12"- APPROACH TO TOLL PLAZA OR 3-9 LANE DROP	GM	0.510
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	16.750
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.760
	0713-103-102	PERMANENT TAPE, WHITE, SOLID, 8" EXIT LANE AT INTERCHANGE ON CONCRETE PAVEMENT	GM	0.290
	0713-103-131	PERMANENT TAPE, WHITE, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	0.660
	0713-103-133	PERMANENT TAPE, WHITE, SKIP, 12" WIDE 3'-9' DROP LANE ON CONCRETE SURFACES	GM	0.040
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.460
	0713-103-331	PERMANENT TAPE, BLACK, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	0.540
	0713-103-333	PERMANENT TAPE, BLACK, 3'-9' DROP LANE, 12" ON CONCRETE SURFACES	GM	0.040
Section 0004 Lighting				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	43,108.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	981.000
	0630- 2- 15	CONDUIT, FURNISH & INSTALL, BRIDGE MOUNT	LF	1,109.000
	0630- 2- 16	CONDUIT, FURNISH & INSTALL, EMBEDDED CONCRETE BARRIERS AND TRAFFIC RAILINGS	LF	29,110.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	264.000

Call Order: 001 Proposal: E8Q79

ALT	Item	Description	Unit	Quantity
	0635- 3- 12	JUNCTION BOX, FURNISH & INSTALL, MOUNTED	EA	44.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	47,589.000
	0715- 1- 13	LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2	LF	197,307.000
	0715- 1- 14	LIGHTING CONDUCTORS, F&I, INSULATED, NO 1 TO NO 0	LF	230,645.000
	0715- 1- 15	LIGHTING CONDUCTORS, F&I, NO.1/0 - 3/0 (0 to 000)	LF	680.000
	0715- 1- 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	LF	220,405.000
	0715- 4- 13	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT	EA	19.000
	0715- 4- 15	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 50' MOUNTING HEIGHT	EA	283.000
	0715- 4- 25	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE SPECIAL FOUNDATION, 50' MOUNTING HEIGHT	EA	43.000
	0715- 4- 70	LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION	EA	169.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	1.000
	0715- 7- 21	LOAD CENTER, REWORK, SECONDARY VOLTAGE	EA	2.000
	0715- 7- 41	LOAD CENTER, REMOVE, SECONDARY VOLTAGE	EA	2.000
	0715- 11-125	LUMINAIRE, F&I, UNDER DECK, WALL MOUNT	EA	12.000
	0715- 11-213	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, POLE TOP	EA	22.000
	0715- 19- 60	HIGH MAST LIGHT POLE, REMOVE POLE AND FOUNDATION	EA	2.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, CONVENTIONAL	EA	191.000
	0715-500- 3	POLE CABLE DISTRIBUTION SYSTEM, WALL MOUNT	EA	154.000
Section 0005 Utilities				
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (40614415202)	LS	1.000
	0400- 1- 2	CONCRETE CLASS I, ENDWALLS	CY	4.000
	1050- 16-004	UTILITY PIPE,REMOVE & DISPOSE, 8-19.9"	LF	365.000
	1050- 18-004	UTILITY PIPE,PLUG & PLACE OUT OF SERVICE, 8-19.9"	LF	600.000
	1050- 42-220	UTILITY PIPE- HIGH DENSITY POLYETHYLENE, FURNISH & INSTALL, WATER/SEWER, 20"	LF	688.000
	1050- 42-230	UTILITY PIPE- HIGH DENSITY POLYETHYLENE, FURNISH & INSTALL, WATER/SEWER, 30"	LF	745.000
	1050- 51-212	UTILITY PIPE- DUCTILE IRON/CAST IRON, FURNISH & INSTALL, WATER/SEWER, 12"	LF	160.000
	1050- 51-218	UTILITY PIPE- DUCTILE IRON/CAST IRON, FURNISH & INSTALL, WATER/SEWER, 18"	LF	24.000
	1050- 51-220	UTILITY PIPE- DUCTILE IRON/CAST IRON, FURNISH & INSTALL, WATER/SEWER, 20"	LF	130.000
	1055- 11-414	UTILITY FITTINGS, F&I, DI/CI, ELBOW, 8 - 19.9"	EA	5.000
	1055- 11-415	UTILITY FITTINGS, F&I, DI/CI, ELBOW, 20 - 49.9"	EA	4.000
	1055- 11-434	UTILITY FITTINGS, F&I, DI/CI, REDUCER, 8 - 19.9"	EA	2.000
	1055- 11-494	UTILITY FITTINGS, F&I, DI/CI, SPECIAL, 8.0-19.9"	EA	6.000
	1055- 51-118	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH & INSTALL ELBOW, 18"	EA	2.000
	1060- 11-211	UTILITY STRUCTURE, BELOW GROUND, F&I, WATER/SEWER, 0 - 80 FT3, 0 - 6'	EA	1.000
	1080- 21-112	UTILITY FIXTURE, VALVE/METER BOX, FURNISH & INSTALL, 12"	EA	4.000
	1080- 24-112	UTILITY FIXTURE, VALVE ASSEMBLY, FURNISH AND INSTALL, 12"	EA	2.000

Call Order: 001 Proposal: E8Q79

ALT	Item	Description	Unit	Quantity
	1080- 24-120	UTILITY FIXTURE, VALVE ASSEMBLY, FURNISH AND INSTALL, 20"	EA	2.000
	1080- 26-120	UTILITY FIXTURE, VAC/AIR ASSEMBLY, FURNISH & INSTALL 20"	EA	1.000
	1080- 29-112	UTILITY FIXTURE, MECHANICAL JOINT RESTRAINT, FURNISH & INSTALL, 12"	EA	16.000
	1080- 29-120	UTILITY FIXTURE, MECHANICAL JOINT RESTRAINT, FURNISH & INSTALL, 20"	EA	16.000
	1080- 32-112	UTILITY FIXTURE- SAMPLE POINT, FURNISH & INSTALL, 12"	EA	3.000
	1080- 32-116	UTILITY FIXTURE- SAMPLE POINT, FURNISH & INSTALL, 16"	EA	2.000
	1080- 33-112	UTILITY FIXTURE, PLUG VALVE, FURNISH AND INSTALL 12"	EA	2.000
Section 0006 Architectural				
	0110- 1- 1	CLEARING & GRUBBING (40614415201)	LS	1.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	71.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	27.000
	0735- 74-	TOLL PLAZA, SINGLE LOCATION (40614415201)	LS	1.000
	0735- 88-	TOLL PLAZA MODIFY EXISTING (40614415201)	LS	1.000
Section 0007 Intelligent Transportation System				
	0425- 2- 41	MANHOLES, P-7, <10'	EA	6.000
	0519- 78-	BOLLARDS	EA	2.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	57,076.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	1,575.000
	0630- 2- 14	CONDUIT, FURNISH & INSTALL, ABOVEGROUND	LF	113,410.000
	0630- 2- 15	CONDUIT, FURNISH & INSTALL, BRIDGE MOUNT	LF	1,630.000
	0633- 1-113	FIBER OPTIC CABLE, F&I, OVERHEAD,49-96 FIBERS	LF	37,560.000
	0633- 1-121	FIBER OPTIC CABLE, F&I, UNDERGROUND,2-12 FIBERS	LF	500.000
	0633- 1-122	FIBER OPTIC CABLE, F&I, UNDERGROUND,13-48 FIBERS	LF	15,761.000
	0633- 1-123	FIBER OPTIC CABLE, F&I, UNDERGROUND,49-96 FIBERS	LF	92,773.000
	0633- 1-124	FIBER OPTIC CABLE, F&I, UNDERGROUND, 97 - 144 FIBERS	LF	45,872.000
	0633- 1-420	FIBER OPTIC CABLE, RELOCATE, UNDERGROUND	LF	260.000
	0633- 1-620	FIBER OPTIC CABLE, REMOVE, UNDERGROUND	LF	89,044.000
	0633- 2- 31	FIBER OPTIC CONNECTION, INSTALL, SPLICE	EA	936.000
	0633- 2- 32	FIBER OPTIC CONNECTION, INSTALL, TERMINATION	EA	736.000
	0633- 3- 11	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE ENCLOSURE	EA	47.000
	0633- 3- 12	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE TRAY	EA	70.000
	0633- 3- 13	FIBER OPTIC CONNECTION HARDWARE, F&I, PRETERMINATED CONNECTOR ASSEMBLY	EA	2.000
	0633- 3- 14	FIBER OPTIC CONNECTION HARDWARE, F&I, BUFFER TUBE FAN OUT KIT	EA	44.000
	0633- 3- 15	FIBER OPTIC CONNECTION HARDWARE, F&I, PRETERMINATED PATCH PANEL	EA	45.000
	0633- 3- 17	FIBER OPTIC CONNECTION HARDWARE, F&I, CONNECTOR PANEL	EA	43.000
	0633- 8- 1	MULTI-CONDUCTOR COMMUNICATION CABLE, FURNISH & INSTALL	LF	200.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	164.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	109.000
	0635- 2- 13	PULL & SPLICE BOX, F&I, 30" X 60" RECTANGULAR OR 36" ROUND COVER SIZE	EA	23.000
	0635- 3- 12	JUNCTION BOX, FURNISH & INSTALL, MOUNTED	EA	48.000

Call Order: 001 Proposal: E8Q79

ALT	Item	Description	Unit	Quantity
	0639- 1-111	ELECTRICAL POWER SERVICE, F&I, OVERHEAD, METER FURNISHED BY POWER COMPANY	AS	4.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	75,357.000
	0639- 2- 6	ELECTRICAL SERVICE WIRE, REMOVE	LF	34,130.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	6.000
	0639- 3- 12	ELECTRICAL SERVICE DISCONNECT, F&I, CABINET	EA	43.000
	0639- 6- 1	ELECTRICAL POWER SERVICE- TRANSFORMER FURNISH & INSTALL	EA	4.000
	0641- 2- 13	PRESTRESSED CONCRETE POLE, F&I, TYPE P-III	EA	26.000
	0641- 2- 80	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- POLE 30' AND GREATER	EA	14.000
	0641- 3-169	CONCRETE CCTV POLE, FURNISH & INSTALL WITH LOWERING DEVICE, 69'	EA	10.000
	0641- 3-175	CONCRETE CCTV POLE, FURNISH & INSTALL WITH LOWERING DEVICE, 75'	EA	7.000
	0641- 3-186	CONCRETE CCTV POLE, FURNISH & INSTALL WITH LOWERING DEVICE, 86'	EA	1.000
	0641- 3-800	CONCRETE CCTV POLE, COMPLETE POLE REMOVAL	EA	8.000
	0660- 3- 11	VEHICLE DETECTION SYSTEM- MICROWAVE, FURNISH & INSTALL CABINET EQUIPMENT	EA	38.000
	0660- 3- 12	VEHICLE DETECTION SYSTEM- MICROWAVE, FURNISH & INSTALL, ABOVE GROUND EQUIPMENT	EA	38.000
	0660- 3- 60	VEHICLE DETECTION SYSTEM - MICROWAVE, REMOVE, COMPLETE SYSTEM	EA	21.000
	0660- 6-121	VEHICLE DETECTION SYSTEM- AVI, BLUETOOTH, FURNISH & INSTALL, CABINET EQUIPMENT	EA	5.000
	0660- 6-122	VEHICLE DETECTION SYSTEM- AVI, BLUETOOTH, FURNISH & INSTALL, ABOVE GROUND EQUIPMENT	EA	5.000
	0660- 6-600	VEHICLE DETECTION SYSTEM- AVI, REMOVE COMPLETE SYSTEM	EA	2.000
	0676- 2-122	ITS CABINET, FURNISH & INSTALL, POLE MOUNT WITH SUNSHIELD, 336S, 24" W X 46" H X 22" D	EA	41.000
	0676- 2-143	ITS CABINET, FURNISH & INSTALL, BASE MOUNT, 334, 24" W X 66" H X 30" D	EA	2.000
	0676- 2-600	ITS CABINET- REMOVE	EA	23.000
	0682- 1-133	ITS CCTV CAMERA, F&I, DOME ENCLOSURE - NON-PRESSURIZED, IP, HIGH DEFINITION	EA	19.000
	0682- 1-600	ITS CCTV CAMERA,, REMOVE & DISPOSAL	EA	8.000
	0684- 1- 1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	EA	42.000
	0684- 2- 1	DEVICE SERVER, FURNISH & INSTALL	EA	41.000
	0684- 6- 40	WIRELESS COMMUNICATION DEVICE, RELOCATE	EA	1.000
	0685- 1- 11	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, LINE INTERACTIVE	EA	43.000
	0700- 9-137	WALK-IN DYNAMIC MESSAGE SIGN, FURNISH & INSTALL- WITH UPS FULL COLOR, 201-300 SF	EA	2.000
	0700- 9-600	WALK-IN DYNAMIC MESSAGE SIGN, REMOVE	EA	1.000
	0700- 10-115	DMS SUPPORT STRUCTURE, FURNISH & INSTALL, SPAN, 51-100 FT	EA	2.000
	0700- 10-600	DMS SUPPORT STRUCTURE, REMOVE	EA	1.000