

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 08190212 Call Order: 001 Proposal: E8Q79 District:08

Counties: PALM BEACH

Road Name: TURNPIKE MAINLINE WIDENING

Limits: 93470000

Project(s): 40614415201(*) Federal Aid No: N/A

Project(s): 40614415202 Federal Aid No: N/A

Project(s): 40614415602 Federal Aid No: N/A

| | | | |
|------------------------|--------------|----------------------------|----------|
| Total Roadway Length: | 45.462 Miles | Contract Days: | 1645 |
| Total Bridge Length: | 0.185 Miles | Letting Date: | 02/12/19 |
| Total Proposal Length: | 45.647 Miles | Contract Execution Days: | 10 |
| | | Special Start Date: | N/A |
| | | Aquis/Flexible Start Time: | 30 |

Proposal Budget Estimate: \$173,672,165.00

Please read the full advertisement

Description:

Work consists of providing all labor, materials, equipment and incidentals necessary for the widening of approximately 7.6 miles of Turnpike mainline from four and six lanes to eight lanes from north of SR 804 (Boynton Beach Boulevard) (milepost 87.1) to north of SR 802 (Lake Worth Road) (milepost 94.7). The typical section consists of one express lane and three general tolled lanes in each direction. This project proposes to realign the mainline centerline to the west to prevent the proposed improvements from encroaching into the Florida Gas Transmission (FGT) facility specified width and mitigate the risk of possible triggering events. This project also includes the construction of the mainline AET toll facilities and partial reconstruction of the existing Lantana Toll Plaza to accommodate six through lanes, with the remainder of ticket lanes (four in each direction) to remain in operation. A second mainline tolling point is proposed at the egress/ingress point of express lane just south of Lantana Road. No Pre-Bid Conference. Contractor must be prequalified .

The summary of pay items for this project is listed in the Plans.

Call Order: 001 Proposal: E8Q79

| ALT | Item | Description | Unit | Quantity |
|--------------------------------|-------------|---|------|-------------|
| Section 0001 Structures | | | | |
| | 0110- 3- | REMOVAL OF EXISTING STRUCTURES/BRIDGES (40614415201) | LS | 1.000 |
| | 0110- 3- | REMOVAL OF EXISTING STRUCTURES/BRIDGES (40614415201) | LS | 1.000 |
| | 0110- 3- | REMOVAL OF EXISTING STRUCTURES/BRIDGES (40614415201) | LS | 1.000 |
| | 0110- 3- | REMOVAL OF EXISTING STRUCTURES/BRIDGES (40614415201) | LS | 1.000 |
| | 0110- 3- | REMOVAL OF EXISTING STRUCTURES/BRIDGES (40614415201) | LS | 1.000 |
| | 0110- 3- | REMOVAL OF EXISTING STRUCTURES/BRIDGES (40614415201) | LS | 1.000 |
| | 0400- 2- 4 | CONC CLASS II, BRIDGE SUPERSTRUCTURE | CY | 1,566.000 |
| | 0400- 2- 10 | CONCRETE CLASS II, APPROACH SLABS | CY | 341.000 |
| | 0400- 4- 5 | CONCRETE CLASS IV, BRIDGE SUBSTRUCTURE | CY | 291.300 |
| | 0400- 4- 25 | CONCRETE CLASS IV, MASS, SUBSTRUCTURE | CY | 267.000 |
| | 0400- 7- | BRIDGE DECK GROOVING, LESS THAN 8.5" | SY | 2,243.000 |
| | 0400- 9- | BRIDGE DECK GROOVING & PLANING, DECK 8.5" AND GREATER | SY | 2,920.000 |
| | 0400-143- | CLEANING & COATING CONCRETE SURFACE, CLASS 5 | SF | 6,822.000 |
| | 0400-145- | CLEANING CONCRETE SURFACE | SF | 53,430.000 |
| | 0400-147- | COMPOSITE NEOPRENE PADS | CF | 26.700 |
| | 0415- 1- 4 | REINFORCING STEEL - BRIDGE SUPERSTRUCTURE | LB | 379,853.000 |
| | 0415- 1- 5 | REINFORCING STEEL- BRIDGE SUBSTRUCTURE | LB | 123,520.000 |

Call Order: 001 Proposal: E8Q79

| ALT | Item | Description | Unit | Quantity |
|-----------------------------|--------------|--|------|-------------|
| | 0415- 1- 9 | REINFORCING STEEL- APPROACH SLABS | LB | 57,842.000 |
| | 0450- 2- 36 | PREST BEAMS: FLORIDA-I BEAM 36" | LF | 260.000 |
| | 0450- 2- 54 | PREST BEAMS: FLORIDA-I BEAM 54" | LF | 1,988.000 |
| | 0450- 2- 63 | PREST BEAMS: FLORIDA-I BEAM 63" | LF | 2,250.000 |
| | 0450- 2- 72 | PREST BEAMS: FLORIDA-I BEAM 72" | LF | 795.000 |
| | 0455- 34- 3 | PRESTRESSED CONCRETE PILING, 18" SQ | LF | 5,740.000 |
| | 0455- 34-309 | PRESTRESSED CONCRETE PILING, INCLUDES 100% DYNAMIC TESTING, PROJECT 406144-1-52-01, SIZE 18" | LF | 1,320.000 |
| | 0455-143- 3 | TEST PILES-PRESTRESSED CONCRETE,18" SQ | LF | 380.000 |
| | 0458- 1- 11 | BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&I Poured joint with backer rod | LF | 621.000 |
| | 0458- 1- 21 | BRIDGE DECK EXPANSION JOINT, REHABILITATION, Poured joint with backer rod | LF | 675.000 |
| | 0459- 71- | PILES, POLYETHYLENE SHEETING | SY | 140.000 |
| | 0460- 71- 4 | METAL TRAFFIC RAILING, RECTANGULAR TUBE RETROFIT | LF | 333.000 |
| | 0521- 5- 12 | CONCRETE TRAFFIC RAILING- BRIDGE, 36" MEDIAN SINGLE SLOPE | LF | 977.000 |
| | 0521- 5- 13 | CONCRETE TRAFFIC RAILING- BRIDGE, 36" SINGLE-SLOPE | LF | 1,262.000 |
| | 0521- 5- 22 | CONCRETE TRAFFIC RAILING- BRIDGE, 8'-0" NOISE WALL | LF | 493.000 |
| | 0521- 6- 11 | CONCRETE PARAPET, PEDESTRIAN/BICYCLE, 27" HEIGHT | LF | 942.000 |
| | 0550- 10-353 | FENCING, TYPE R, 8.1 - 10.0', WITH FULL ENCLOSURE | LF | 942.000 |
| | 0630- 2- 15 | CONDUIT, FURNISH & INSTALL, BRIDGE MOUNT | LF | 522.000 |
| | 0630- 2- 16 | CONDUIT, FURNISH & INSTALL, EMBEDDED CONCRETE BARRIERS AND TRAFFIC RAILINGS | LF | 6,009.000 |
| | 0635- 3- 13 | JUNCTION BOX, FURNISH & INSTALL, EMBEDDED | EA | 20.000 |
| Section 0002 Roadway | | | | |
| | 0101- 1- | MOBILIZATION (40614415201) | LS | 1.000 |
| | 0102- 1- | MAINTENANCE OF TRAFFIC (40614415201) | LS | 1.000 |
| | 0102- 2- 1 | SPECIAL DETOUR 1 (40614415201) | LS | 1.000 |
| | 0102- 2- 2 | SPECIAL DETOUR 2 (40614415201) | LS | 1.000 |
| | 0102- 2- 3 | SPECIAL DETOUR 3 (40614415201) | LS | 1.000 |
| | 0102- 2- 4 | SPECIAL DETOUR 4 (40614415201) | LS | 1.000 |
| | 0102- 2- 5 | SPECIAL DETOUR 5 (40614415201) | LS | 1.000 |
| | 0102- 2- 6 | SPECIAL DETOUR 6 (40614415201) | LS | 1.000 |
| | 0102- 2- 7 | SPECIAL DETOUR 7 (40614415201) | LS | 1.000 |
| | 0102- 2- 8 | SPECIAL DETOUR 8 (40614415201) | LS | 1.000 |
| | 0102- 2- 9 | SPECIAL DETOUR 9 (40614415201) | LS | 1.000 |
| | 0102- 30- 1 | TEMPORARY HIGHWAY LIGHTING, PROJECT 406144-1-52-01 | LS | 1.000 |
| | 0102- 60- | WORK ZONE SIGN | ED | 161,963.000 |
| | 0102- 62- | BARRIER MOUNTED WORK ZONE SIGN- INDEX 11871/700-013 | ED | 45,900.000 |
| | 0102- 71- 15 | TEMPORARY BARRIER, F&I, ANCHORED | LF | 67,059.000 |
| | 0102- 71- 16 | TEMPORARY BARRIER, F&I, FREE STANDING | LF | 11,933.000 |
| | 0102- 71- 25 | TEMPORARY BARRIER, RELOCATE, ANCHORED | LF | 136,926.000 |
| | 0102- 71- 26 | TEMPORARY BARRIER, RELOCATE, FREE STANDING | LF | 13,540.000 |
| | 0102- 74- 1 | CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD | ED | 253,118.000 |
| | 0102- 74- 2 | CHANNELIZING DEVICE, TYPE III, 6' | ED | 890.000 |

Call Order: 001 Proposal: E8Q79

| ALT | Item | Description | Unit | Quantity |
|-----|--------------|---|------|-------------|
| | 0102- 74- 7 | CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE) | LF | 88.000 |
| | 0102- 75- 3 | TEMPORARY SEPARATOR, INSTALL | LF | 2,219.000 |
| | 0102- 75- 4 | TEMPORARY SEPARATOR, RELOCATE | LF | 2,164.000 |
| | 0102- 75- 5 | TEMPORARY SEPARATOR, REMOVE | LF | 2,219.000 |
| | 0102- 76- | ARROW BOARD / ADVANCE WARNING ARROW PANEL | ED | 2,171.000 |
| | 0102- 78- | TEMPORARY RETROREFLECTIVE PAVEMENT MARKER | EA | 36,699.000 |
| | 0102- 89- 1 | TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION | LO | 71.000 |
| | 0102- 94- 1 | TEMPORARY GLARE SCREEN, F&I, WALL MATERIAL-CONCRETE | LF | 1,629.000 |
| | 0102- 99- | PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY | ED | 1,367.000 |
| | 0102-150- 1 | PORTABLE REGULATORY, SIGN | ED | 694.000 |
| | 0102-150- 2 | RADAR SPEED DISPLAY UNIT | ED | 434.000 |
| | 0102-911- 1 | PAVEMENT MARKING REMOVABLE TAPE, WHITE OR BLACK, SKIP | LF | 1,220.000 |
| | 0102-911- 2 | PAVEMENT MARKING REMOVABLE TAPE, WHITE OR BLACK,SOLID | LF | 2,834.000 |
| | 0102-912- 2 | PAVEMENT MARKING REMOVABLE TAPE, YELLOW, SOLID | LF | 2,316.000 |
| | 0104- 10- 3 | SEDIMENT BARRIER | LF | 60,391.000 |
| | 0104- 11- | FLOATING TURBIDITY BARRIER | LF | 14,412.000 |
| | 0104- 12- | STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC | LF | 5,386.000 |
| | 0104- 15- | SOIL TRACKING PREVENTION DEVICE | EA | 9.000 |
| | 0104- 18- | INLET PROTECTION SYSTEM | EA | 473.000 |
| | 0107- 1- | LITTER REMOVAL | AC | 4,040.000 |
| | 0107- 2- | MOWING | AC | 3,150.000 |
| | 0108- 1- | MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (40614415201) | LS | 1.000 |
| | 0108- 2- | MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (40614415201) | LS | 1.000 |
| | 0110- 1- 1 | CLEARING & GRUBBING (40614415201) | LS | 1.000 |
| | 0110- 2- 2 | SELECTIVE CLEARING AND GRUBBING, AREAS WITH TREES TO REMAIN | AC | 10.080 |
| | 0110- 4- 10 | REMOVAL OF EXISTING CONCRETE | SY | 8,912.000 |
| | 0120- 1- | REGULAR EXCAVATION | CY | 203,883.000 |
| | 0120- 5- | CHANNEL EXCAVATION | CY | 38,721.000 |
| | 0120- 6- | EMBANKMENT | CY | 296,779.000 |
| | 0120- 72- 10 | GRAVEL FILL- BERM, PROJECT 406144-1-52-01 | CY | 12,220.000 |
| | 0145- 2- | GEOSYNTHETIC REINFORCED FOUNDATION OVER SOFT SOIL | SY | 45,653.000 |
| | 0160- 4- | TYPE B STABILIZATION | SY | 440,992.000 |
| | 0162- 1- 11 | PREPARED SOIL LAYER, FINISH SOIL LAYER, 6" | SY | 8,324.000 |
| | 0285-701- | OPTIONAL BASE, BASE GROUP 01 | SY | 1,004.000 |
| | 0285-702- | OPTIONAL BASE, BASE GROUP 02 | SY | 2,470.000 |
| | 0285-705- | OPTIONAL BASE, BASE GROUP 05 | SY | 145,897.000 |
| | 0285-709- | OPTIONAL BASE, BASE GROUP 09 | SY | 2,183.000 |
| | 0285-711- | OPTIONAL BASE, BASE GROUP 11 | SY | 1,844.000 |
| | 0285-712- | OPTIONAL BASE, BASE GROUP 12 | SY | 171,319.000 |
| | 0285-713- | OPTIONAL BASE, BASE GROUP 13 | SY | 199.000 |
| | 0285-714- | OPTIONAL BASE, BASE GROUP 14 | SY | 67,132.000 |
| | 0285-715- | OPTIONAL BASE, BASE GROUP 15 | SY | 42,379.000 |

Call Order: 001 Proposal: E8Q79

| ALT | Item | Description | Unit | Quantity |
|-----|--------------|--|------|---------------|
| | 0327- 70- 1 | MILLING EXIST ASPH PAVT, 1" AVG DEPTH | SY | 19,219.000 |
| | 0327- 70- 6 | MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH | SY | 28,635.000 |
| | 0327- 70- 11 | MILLING EXIST ASPH PAVT, 2 1/4" AVG DEPTH | SY | 6,298.000 |
| | 0327- 70- 15 | MILLING EXIST ASPH PAVT, 2 3/4" AVG DEPTH | SY | 231,109.000 |
| | 0334- 1- 11 | SUPERPAVE ASPHALTIC CONC, TRAFFIC A | TN | 373.100 |
| | 0334- 1- 12 | SUPERPAVE ASPHALTIC CONC, TRAFFIC B | TN | 24,028.000 |
| | 0334- 1- 13 | SUPERPAVE ASPHALTIC CONC, TRAFFIC C | TN | 168.500 |
| | 0334- 1- 14 | SUPERPAVE ASPHALTIC CONC, TRAFFIC D | TN | 186,713.300 |
| | 0334- 1- 53 | SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22 | TN | 519.900 |
| | 0334- 1- 54 | SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC D, PG76-22 | TN | 49,794.000 |
| | 0337- 7- 25 | ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22 | TN | 16,324.000 |
| | 0337- 7- 82 | ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-9.5, PG 76-22 | TN | 741.400 |
| | 0337- 7- 85 | ASPHALT CONCRETE FRICTION COURSE, TRAFFIC D, FC-12.5, PG 76-22 | TN | 4,815.700 |
| | 0339- 1- | MISCELLANEOUS ASPHALT PAVEMENT | TN | 1,100.000 |
| | 0400- 0- 11 | CONCRETE CLASS NS, GRAVITY WALL | CY | 1,323.000 |
| | 0400- 1- 2 | CONCRETE CLASS I, ENDWALLS | CY | 139.200 |
| | 0400- 2- 2 | CONCRETE CLASS II, ENDWALLS | CY | 28.800 |
| | 0400- 4- 8 | CONC CLASS IV, BULKHEAD | CY | 10,111.000 |
| | 0415- 1- 8 | REINFORCING STEEL- BULKHEAD | LB | 1,295,769.000 |
| | 0425- 1-545 | INLETS, DITCH BOTTOM, TYPE D, PARTIAL | EA | 1.000 |
| | 0425- 1-549 | INLETS, DT BOT, TYPE D, MODIFY | EA | 9.000 |
| | 0425- 1-575 | INLETS, DITCH BOTTOM, TYPE G, PARTIAL | EA | 2.000 |
| | 0425- 1-585 | INLETS, DT BOT, TYPE H, PARTIAL | EA | 2.000 |
| | 0425- 1-701 | INLETS, GUTTER, TYPE S, <10' | EA | 42.000 |
| | 0425- 1-781 | INLETS, MEDIAN BARRIER, TYPE 1, J BOT, =10' | EA | 5.000 |
| | 0425- 1-783 | INLETS, MEDIAN BARRIER, TYPE 1, J BOT, <10' | EA | 40.000 |
| | 0425- 1-791 | INLETS, MEDIAN BARRIER, TYPE 2, J BOT, =10' | EA | 76.000 |
| | 0425- 1-793 | INLETS, MEDIAN BARRIER, TYPE 2, J BOT, <10' | EA | 23.000 |
| | 0425- 1-799 | INLETS, MEDIAN BARRIER, TYPE 2, MODIFY | EA | 5.000 |
| | 0425- 1-891 | INLETS, BARRIER WALL, <10' | EA | 62.000 |
| | 0425- 1-893 | INLETS, BARRIER WALL, J BOT, <10' | EA | 23.000 |
| | 0425- 1-899 | INLETS, BARRIER WALL, MODIFY | EA | 131.000 |
| | 0425- 2- 41 | MANHOLES, P-7, <10' | EA | 10.000 |
| | 0425- 2- 43 | MANHOLES, P-7, PARTIAL | EA | 1.000 |
| | 0425- 2- 71 | MANHOLES, J-7, <10' | EA | 1.000 |
| | 0425- 2- 72 | MANHOLES, J-7, >10' | EA | 1.000 |
| | 0425- 3- 41 | JUNCTION BOX, DRAINAGE, P-7, <10' | EA | 1.000 |
| | 0425- 3- 43 | JUNCTION BOX, DRAINAGE, P-7, PARTIAL | EA | 1.000 |
| | 0425- 3- 61 | JUNCTION BOXES, J-7, <10' | EA | 1.000 |
| | 0425- 5- 1 | MANHOLE, ADJUST, UTILITIES | EA | 3.000 |
| | 0430- 94- 1 | DESILTING PIPE, 0 - 24" | LF | 14,437.000 |
| | 0430- 96- | DRAINAGE PIPE REPAIR- CONCRETE COLLAR AT JOINT | EA | 24.000 |
| | 0430-175-118 | PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD | LF | 26,773.000 |
| | 0430-175-124 | PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"S/CD | LF | 5,888.000 |

Call Order: 001 Proposal: E8Q79

| ALT | Item | Description | Unit | Quantity |
|-----|--------------|--|------|------------|
| | 0430-175-130 | PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD | LF | 1,098.000 |
| | 0430-175-136 | PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD | LF | 664.000 |
| | 0430-175-148 | PIPE CULVERT, OPT MATERIAL, ROUND, 48"S/CD | LF | 8.000 |
| | 0430-175-172 | PIPE CULVERT, OPT MATERIAL, ROUND, 72"S/CD | LF | 196.000 |
| | 0430-185-124 | PIPE CULVERT,OPTIONAL MATERIAL,ROUND, JACK & BORE, 24", STORM AND CROSS DRAIN | LF | 81.000 |
| | 0430-200- 25 | FLARED END SECTION, CONCRETE, 18" | EA | 32.000 |
| | 0430-200- 29 | FLARED END SECTION, CONCRETE, 24" | EA | 2.000 |
| | 0430-611-125 | U-ENDWALL WITH BAFFLES, INDEX 261/430-011, 1:4 SLOPE, 18"PIPE | EA | 3.000 |
| | 0430-611-129 | U-ENDWALL WITH BAFFLES, INDEX 261/430-011, 1:4 SLOPE, 24"PIPE | EA | 2.000 |
| | 0430-611-133 | U-ENDWALL WITH BAFFLES, INDEX 261/430-011,1:4 SLOPE,30"PIPE | EA | 2.000 |
| | 0430-612-025 | U-ENDWALL WITH GRATE, INDEX 261/430-011, 1:6 SLOPE, 18"PIPE | EA | 15.000 |
| | 0430-613-033 | U-ENDWALL, WITH BAFFLES & GRATE, INDEX 261/430-011,1:6 SLOPE, 30" | EA | 2.000 |
| | 0430-821- 25 | CLEANING & SEALING EXISTING PIPE JOINT, 18" STORM SEWER | EA | 2.000 |
| | 0430-821- 29 | CLEANING & SEALING EXISTING PIPE JOINT, 24" STORM SEWER | EA | 4.000 |
| | 0430-830- | PIPE FILLING AND PLUGGING- PLACE OUT OF SERVICE | CY | 27.000 |
| | 0430-890-100 | SLIDE GATE, 72", PROJECT 406144-1-52-01 | EA | 1.000 |
| | 0430-982-125 | MITERED END SECTION, OPTIONAL ROUND, 18" CD | EA | 1.000 |
| | 0430-982-129 | MITERED END SECTION, OPTIONAL ROUND, 24" CD | EA | 4.000 |
| | 0431- 1-205 | PIPE LINER,REPAIR BY SLIPLINING, 0-24", PROJECT 406144-1-52-01 | LF | 1,245.000 |
| | 0436- 1- 1 | TRENCH DRAIN, STANDARD | LF | 806.000 |
| | 0455- 34- 5 | PRESTRESSED CONCRETE PILING, 24" SQ | LF | 93,104.000 |
| | 0455-133- 2 | SHEET PILING STEEL, TEMPORARY-CRITICAL | SF | 68,569.000 |
| | 0455-143- 5 | TEST PILES-PRESTRESSED CONCRETE,24" SQ | LF | 580.000 |
| | 0460- 71- 4 | METAL TRAFFIC RAILING, RECTANGULAR TUBE RETROFIT | LF | 957.000 |
| | 0515- 1- 2 | PIPE HANDRAIL - GUIDERAIL, ALUMINUM | LF | 178.000 |
| | 0520- 1- 10 | CONCRETE CURB & GUTTER, TYPE F | LF | 577.000 |
| | 0520- 6- | SHOULDER GUTTER- CONCRETE | LF | 6,705.000 |
| | 0521- 1- 11 | MEDIAN CONCRETE BARRIER, 38" HEIGHT | LF | 19,073.000 |
| | 0521- 1- 12 | MEDIAN CONCRETE BARRIER, SHORT GRADE-SEPARATED | LF | 11,704.000 |
| | 0521- 1- 13 | MEDIAN CONCRETE BARRIER, TALL GRADE-SEPARATED | LF | 3,682.000 |
| | 0521- 1- 14 | MEDIAN CONCRETE BARRIER, VARIABLE SECTION WIDTH FOR SIGN OR PIER SHIELDING | LF | 1,906.000 |
| | 0521- 8- 7 | CONCRETE BARRIER, WITH JUNCTION SLAB, 36" SINGLE SLOPE | LF | 18,811.000 |
| | 0521- 8- 11 | CONCRETE BARRIER, WITH JUNCTION SLAB, 8'-0" NOISE WALL | LF | 14,804.000 |
| | 0521- 72- 24 | SHOULDER CONCRETE BARRIER WALL, 8' NOISE WALL | LF | 802.000 |
| | 0521- 72- 27 | SHOULDER CONCRETE BARRIER WALL, 14' NOISE WALL | LF | 18,746.000 |
| | 0521- 72- 40 | SHOULDER CONCRETE BARRIER, 38" OR 44" HEIGHT | LF | 2,296.000 |
| | 0522- 2- | CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK | SY | 46.000 |
| | 0524- 1- 49 | CONCRETE DITCH PAVEMENT, 6", REINFORCED | SY | 827.000 |
| | 0524- 2- 2 | CONCRETE SLOPE PAVEMENT, NON REINFORCED, 4" | SY | 6,298.000 |
| | 0530- 1- | RIPRAP, SAND-CEMENT | CY | 140.200 |
| | 0530- 3- 3 | RIPRAP- RUBBLE, BANK AND SHORE | TN | 32,054.200 |
| | 0530- 3- 4 | RIPRAP, RUBBLE, F&I, DITCH LINING | TN | 5,330.700 |
| | 0530- 74- | BEDDING STONE | TN | 19,839.500 |

Call Order: 001 Proposal: E8Q79

| ALT | Item | Description | Unit | Quantity |
|-----------------------------|--------------|---|------|-------------|
| | 0534- 72-101 | SOUND/NOISE BARRIER-INC FOUNDATION, PERMANENT | SF | 44,450.000 |
| | 0536- 1- 1 | GUARDRAIL -ROADWAY, GENERAL TL-3 | LF | 25,453.000 |
| | 0536- 1- 3 | GUARDRAIL- ROADWAY, DOUBLE FACE | LF | 256.000 |
| | 0536- 7- 3 | SPECIAL GUARDRAIL POST- ENCASED POST FOR SHALLOW MOUNT | EA | 3,709.000 |
| | 0536- 8- 11 | APPROACH TRANSITION TO RIGID BARRIER CONNECTION, FURNISH & INSTALL | EA | 6.000 |
| | 0536- 8- 13 | APPROACH TRANSITION CONNECTION TO RIGID BARRIER, FURNISH AND INSTALL, TL-3 | EA | 18.000 |
| | 0536- 73- | GUARDRAIL REMOVAL | LF | 60,198.000 |
| | 0536- 85- 24 | GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL | EA | 15.000 |
| | 0536- 85- 25 | GUARDRAIL END TREATMENT- TRAILING ANCHORAGE TYPE II | EA | 15.000 |
| | 0536- 85- 27 | GUARDRAIL END TREATMENT- DOUBLE FACE APPROACH TERMINAL | EA | 1.000 |
| | 0544- 75- 1 | CRASH CUSHION | EA | 16.000 |
| | 0546- 72- 1 | GROUND-IN RUMBLE STRIPS, 16" | GM | 17.004 |
| | 0548- 12- | RETAINING WALL SYSTEM, PERMANENT, EXCLUDING BARRIER | SF | 248,329.000 |
| | 0548- 13- | RETAINING WALL SYSTEM, TEMPORARY, EXCLUDING BARRIER | SF | 11,071.000 |
| | 0550- 10-221 | FENCING, TYPE B, 5.1-6.0', W/ BARB WIRE ATTMT | LF | 12,834.000 |
| | 0550- 60-211 | FENCE GATE, TYPE B, SINGLE, 0- 6.0' OPENING | EA | 2.000 |
| | 0550- 60-232 | FENCE GATE, TYPE B, SLIDING/CANTILEVER, 6.1-12' OPENING | EA | 2.000 |
| | 0570- 1- 1 | PERFORMANCE TURF | SY | 111,237.000 |
| | 0570- 1- 2 | PERFORMANCE TURF, SOD | SY | 199,144.000 |
| | 0639- 8- 3 | ELECTRICAL POWER SERVICE- CONTRIBUTION IN AID OF CONSTRUCTION (CIAC), PROJECT 406144-1-52-01 | LS | 1.000 |
| | 0700- 2- 16 | MULTI- POST SIGN, F&I GROUND MOUNT, 101-200 SF | AS | 5.000 |
| | 0710- 11-101 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6" | GM | 59.473 |
| | 0710- 11-102 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8" | GM | 1.298 |
| | 0710- 11-103 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE MARKINGS, 12" | GM | 8.890 |
| | 0710- 11-131 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE | GM | 47.024 |
| | 0710- 11-133 | PAINTED PAVEMENT MARKING, STANDARD, WHITE, 3'-9' SKIP DROP LINE AND APPROACH TO TOLL PLAZA, 12" WIDE, | GM | 2.215 |
| | 0710- 11-160 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL | EA | 1.000 |
| | 0710- 11-170 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS | EA | 1.000 |
| | 0710- 11-201 | PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6" | GM | 44.339 |
| | 0710- 11-202 | PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8" | GM | 0.887 |
| | 0710- 11-224 | PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18" | LF | 152.000 |
| | 0999- 16- | PARTNERING, DO NOT BID (40614415201) | LS | 1.000 |
| | 0999- 20- 1 | DISPUTES REVIEW BOARD, MEETING- DO NOT BID | DA | 27.000 |
| | 0999- 20- 2 | DISPUTES REVIEW BOARD, HEARING- DO NOT BID | EA | 2.000 |
| | 0999- 25- | INITIAL CONTINGENCY AMOUNT, DO NOT BID (40614415201) | LS | 1.000 |
| Section 0003 Signing | | | | |
| | 0630- 2- 11 | CONDUIT, FURNISH & INSTALL, OPEN TRENCH | LF | 824.000 |
| | 0630- 2- 12 | CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE | LF | 60.000 |

Call Order: 001 Proposal: E8Q79

| ALT | Item | Description | Unit | Quantity |
|-----|-------------|---|------|----------|
| | 0635- 2- 11 | PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE | EA | 4.000 |
| | 0639- 1-113 | ELECTRICAL POWER SERVICE, F&I, OVERHEAD METER NOT REQUIRED | AS | 1.000 |
| | 0676- 2-131 | ITS CABINET, FURNISH & INSTALL, BASE MOUNT, 336, 24" W X 36" H X 20" D | EA | 1.000 |
| | 0695- 1- 1 | TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL | EA | 12.000 |
| | 0695- 6- 12 | TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 2 LOOPS | EA | 12.000 |
| | 0700- 1- 11 | SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF | AS | 41.000 |
| | 0700- 1- 12 | SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF | AS | 29.000 |
| | 0700- 1- 13 | SINGLE POST SIGN, F&I GROUND MOUNT, 21-30 SF | AS | 2.000 |
| | 0700- 1- 14 | SINGLE POST SIGN, F&I GROUND MOUNT, 31+ SF | AS | 4.000 |
| | 0700- 1- 22 | SINGLE POST SIGN, F&I BARRIER MOUNT INDEX 11871/700-013, 12-20 SF | AS | 2.000 |
| | 0700- 1- 60 | SINGLE POST SIGN, REMOVE | AS | 92.000 |
| | 0700- 2- 14 | MULTI- POST SIGN, F&I GROUND MOUNT, 31-50 SF | AS | 1.000 |
| | 0700- 2- 15 | MULTI- POST SIGN, F&I GROUND MOUNT, 51-100 SF | AS | 8.000 |
| | 0700- 2- 16 | MULTI- POST SIGN, F&I GROUND MOUNT, 101-200 SF | AS | 3.000 |
| | 0700- 2- 60 | MULTI- POST SIGN, REMOVE | AS | 28.000 |
| | 0700- 3-201 | SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF | EA | 1.000 |
| | 0700- 3-202 | SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 12-20 SF | EA | 3.000 |
| | 0700- 3-203 | SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 21-30 SF | EA | 11.000 |
| | 0700- 3-205 | SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 51-100 SF | EA | 2.000 |
| | 0700- 3-206 | SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 101-200 SF | EA | 11.000 |
| | 0700- 3-207 | SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 201-300 SF | EA | 12.000 |
| | 0700- 3-208 | SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 301-400 SF | EA | 1.000 |
| | 0700- 3-404 | SIGN PANEL, INSTALL, 31-50 SF | EA | 1.000 |
| | 0700- 3-603 | SIGN PANEL, REMOVE, 21-30 SF | EA | 8.000 |
| | 0700- 3-605 | SIGN PANEL, REMOVE, 51-100 SF | EA | 2.000 |
| | 0700- 3-606 | SIGN PANEL, REMOVE, 101-200 SF | EA | 5.000 |
| | 0700- 3-607 | SIGN PANEL, REMOVE, 201-300 SF | EA | 12.000 |
| | 0700- 4-112 | OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, CANTILEVER, 21-30 FT | EA | 3.000 |
| | 0700- 4-113 | OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, CANTILEVER, 31-40 FT | EA | 5.000 |
| | 0700- 4-122 | OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, SPAN, 21-30 FT | EA | 1.000 |
| | 0700- 4-123 | OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, SPAN, 31-40 FT | EA | 2.000 |
| | 0700- 4-125 | OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, SPAN, 51-100 FT | EA | 4.000 |
| | 0700- 4-127 | OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, SPAN, 151-200 FT | EA | 1.000 |
| | 0700- 4-140 | OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, OVERPASS BRIDGE MOUNT | EA | 2.000 |
| | 0700- 4-610 | OVERHEAD STATIC SIGN STRUCTURE, REMOVE CANTILEVER | EA | 14.000 |
| | 0700- 4-620 | OVERHEAD STATIC SIGN STRUCTURE, REMOVE SPAN | EA | 1.000 |

Call Order: 001 Proposal: E8Q79

| ALT | Item | Description | Unit | Quantity |
|------------------------------|--------------|---|------|-------------|
| | 0700- 4-640 | OVERHEAD STATIC SIGN STRUCTURE, REMOVE BRIDGE MOUNT | EA | 2.000 |
| | 0700- 7-111 | EMBEDDED DYNAMIC MESSAGE SIGN, FURNISH & INSTALL- WITH UPS, MONOCHROME, UP TO 12 SF | EA | 4.000 |
| | 0701- 17-101 | PROFIED THERMOPLASTIC,STANDARD- CONCRETE SURFACES, WHITE, SOLID,6" | GM | 0.210 |
| | 0701- 17-201 | PROFIED THERMOPLASTIC,STANDARD- CONCRETE SURFACES, YELLOW, SOLID,6" | GM | 0.170 |
| | 0705- 11- 1 | DELINEATOR, FLEXIBLE TUBULAR | EA | 891.000 |
| | 0710- 90- | PAINTED PAVEMENT MARKINGS, FINAL SURFACE (40614415201) | LS | 1.000 |
| | 0711- 11-102 | THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND | GM | 5.270 |
| | 0711- 11-103 | THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR INTERCHANGE MARKINGS | GM | 4.080 |
| | 0711- 11-124 | THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS | LF | 8,142.000 |
| | 0711- 11-160 | THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL | EA | 1.000 |
| | 0711- 11-170 | THERMOPLASTIC, STANDARD, WHITE, ARROW | EA | 1.000 |
| | 0711- 11-224 | THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON | LF | 12,312.000 |
| | 0711- 15-101 | THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6" | GM | 16.790 |
| | 0711- 15-131 | THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP | GM | 28.750 |
| | 0711- 15-133 | THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 12"- APPROACH TO TOLL PLAZA OR 3-9 LANE DROP | GM | 0.510 |
| | 0711- 15-201 | THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6" | GM | 16.750 |
| | 0713-103-101 | PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES | GM | 0.760 |
| | 0713-103-102 | PERMANENT TAPE, WHITE, SOLID, 8" EXIT LANE AT INTERCHANGE ON CONCRETE PAVEMENT | GM | 0.290 |
| | 0713-103-131 | PERMANENT TAPE, WHITE, SKIP/DOTTED, 6" FOR CONCRETE SURFACES | GM | 0.660 |
| | 0713-103-133 | PERMANENT TAPE, WHITE, SKIP, 12" WIDE 3'-9' DROP LANE ON CONCRETE SURFACES | GM | 0.040 |
| | 0713-103-201 | PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES | GM | 0.460 |
| | 0713-103-331 | PERMANENT TAPE, BLACK, SKIP/DOTTED, 6" FOR CONCRETE SURFACES | GM | 0.540 |
| | 0713-103-333 | PERMANENT TAPE, BLACK, 3'-9' DROP LANE, 12" ON CONCRETE SURFACES | GM | 0.040 |
| Section 0004 Lighting | | | | |
| | 0102- 30- 1 | TEMPORARY HIGHWAY LIGHTING, PROJECT 406144-1-52-01 | LS | 1.000 |
| | 0630- 2- 11 | CONDUIT, FURNISH & INSTALL, OPEN TRENCH | LF | 43,108.000 |
| | 0630- 2- 12 | CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE | LF | 981.000 |
| | 0630- 2- 15 | CONDUIT, FURNISH & INSTALL, BRIDGE MOUNT | LF | 1,109.000 |
| | 0630- 2- 16 | CONDUIT, FURNISH & INSTALL, EMBEDDED CONCRETE BARRIERS AND TRAFFIC RAILINGS | LF | 29,110.000 |
| | 0635- 2- 11 | PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE | EA | 264.000 |
| | 0635- 3- 12 | JUNCTION BOX, FURNISH & INSTALL, MOUNTED | EA | 44.000 |
| | 0715- 1- 12 | LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6 | LF | 47,589.000 |
| | 0715- 1- 13 | LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2 | LF | 197,307.000 |

Call Order: 001 Proposal: E8Q79

| ALT | Item | Description | Unit | Quantity |
|-------------------------------|--------------|---|------|-------------|
| | 0715- 1- 14 | LIGHTING CONDUCTORS, F&I, INSULATED, NO 1 TO NO 0 | LF | 230,645.000 |
| | 0715- 1- 15 | LIGHTING CONDUCTORS, F&I, NO.1/0 - 3/0 (0 to 000) | LF | 680.000 |
| | 0715- 1- 60 | LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS | LF | 220,405.000 |
| | 0715- 4- 13 | LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT | EA | 19.000 |
| | 0715- 4- 15 | LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 50' MOUNTING HEIGHT | EA | 283.000 |
| | 0715- 4- 25 | LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE SPECIAL FOUNDATION, 50' MOUNTING HEIGHT | EA | 43.000 |
| | 0715- 4- 70 | LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION | EA | 169.000 |
| | 0715- 7- 11 | LOAD CENTER, F&I, SECONDARY VOLTAGE | EA | 1.000 |
| | 0715- 7- 21 | LOAD CENTER, REWORK, SECONDARY VOLTAGE | EA | 2.000 |
| | 0715- 7- 41 | LOAD CENTER, REMOVE, SECONDARY VOLTAGE | EA | 2.000 |
| | 0715- 11-125 | LUMINAIRE, F&I, UNDER DECK, WALL MOUNT | EA | 12.000 |
| | 0715- 11-213 | LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, POLE TOP | EA | 22.000 |
| | 0715- 19- 60 | HIGH MAST LIGHT POLE, REMOVE POLE AND FOUNDATION | EA | 2.000 |
| | 0715-500- 1 | POLE CABLE DISTRIBUTION SYSTEM, CONVENTIONAL | EA | 191.000 |
| | 0715-500- 3 | POLE CABLE DISTRIBUTION SYSTEM, WALL MOUNT | EA | 154.000 |
| Section 0005 Utilities | | | | |
| | 0110- 3- | REMOVAL OF EXISTING STRUCTURES/BRIDGES (40614415202) | LS | 1.000 |
| | 0400- 1- 2 | CONCRETE CLASS I, ENDWALLS | CY | 4.000 |
| | 1050- 16-004 | UTILITY PIPE,REMOVE & DISPOSE, 8-19.9" | LF | 365.000 |
| | 1050- 18-004 | UTILITY PIPE,PLUG & PLACE OUT OF SERVICE, 8-19.9" | LF | 600.000 |
| | 1050- 42-220 | UTILITY PIPE- HIGH DENSITY POLYETHYLENE, FURNISH & INSTALL, WATER/SEWER, 20" | LF | 688.000 |
| | 1050- 42-230 | UTILITY PIPE- HIGH DENSITY POLYETHYLENE, FURNISH & INSTALL, WATER/SEWER, 30" | LF | 745.000 |
| | 1050- 51-212 | UTILITY PIPE- DUCTILE IRON/CAST IRON, FURNISH & INSTALL, WATER/SEWER, 12" | LF | 160.000 |
| | 1050- 51-218 | UTILITY PIPE- DUCTILE IRON/CAST IRON, FURNISH & INSTALL, WATER/SEWER, 18" | LF | 24.000 |
| | 1050- 51-220 | UTILITY PIPE- DUCTILE IRON/CAST IRON, FURNISH & INSTALL, WATER/SEWER, 20" | LF | 130.000 |
| | 1055- 11-414 | UTILITY FITTINGS, F&I, DI/CI, ELBOW, 8 - 19.9" | EA | 5.000 |
| | 1055- 11-415 | UTILITY FITTINGS, F&I, DI/CI, ELBOW, 20 - 49.9" | EA | 4.000 |
| | 1055- 11-434 | UTILITY FITTINGS, F&I, DI/CI, REDUCER, 8 - 19.9" | EA | 2.000 |
| | 1055- 11-494 | UTILITY FITTINGS, F&I, DI/CI, SPECIAL, 8.0-19.9" | EA | 6.000 |
| | 1055- 51-118 | UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH & INSTALL ELBOW, 18" | EA | 2.000 |
| | 1060- 11-211 | UTILITY STRUCTURE, BELOW GROUND, F&I, WATER/SEWER, 0 - 80 FT3, 0 - 6' | EA | 1.000 |
| | 1080- 21-112 | UTILITY FIXTURE, VALVE/METER BOX, FURNISH & INSTALL, 12" | EA | 4.000 |
| | 1080- 24-112 | UTILITY FIXTURE, VALVE ASSEMBLY, FURNISH AND INSTALL, 12" | EA | 2.000 |
| | 1080- 24-120 | UTILITY FIXTURE, VALVE ASSEMBLY, FURNISH AND INSTALL, 20" | EA | 2.000 |
| | 1080- 26-120 | UTILITY FIXTURE, VAC/AIR ASSEMBLY, FURNISH & INSTALL 20" | EA | 1.000 |
| | 1080- 29-112 | UTILITY FIXTURE, MECHANICAL JOINT RESTRAINT, FURNISH & INSTALL, 12" | EA | 16.000 |

Call Order: 001 Proposal: E8Q79

| ALT | Item | Description | Unit | Quantity |
|---|--------------|---|------|-------------|
| | 1080- 29-120 | UTILITY FIXTURE, MECHANICAL JOINT RESTRAINT, FURNISH & INSTALL, 20" | EA | 16.000 |
| | 1080- 32-112 | UTILITY FIXTURE- SAMPLE POINT, FURNISH & INSTALL, 12" | EA | 3.000 |
| | 1080- 32-116 | UTILITY FIXTURE- SAMPLE POINT, FURNISH & INSTALL, 16" | EA | 2.000 |
| | 1080- 33-112 | UTILITY FIXTURE, PLUG VALVE, FURNISH AND INSTALL 12" | EA | 2.000 |
| Section 0006 Architectural | | | | |
| | 0110- 1- 1 | CLEARING & GRUBBING (40614415201) | LS | 1.000 |
| | 0520- 1- 10 | CONCRETE CURB & GUTTER, TYPE F | LF | 71.000 |
| | 0520- 2- 4 | CONCRETE CURB, TYPE D | LF | 27.000 |
| | 0735- 74- | TOLL PLAZA, SINGLE LOCATION (40614415201) | LS | 1.000 |
| | 0735- 88- | TOLL PLAZA MODIFY EXISTING (40614415201) | LS | 1.000 |
| Section 0007 Intelligent Transportation System | | | | |
| | 0425- 2- 41 | MANHOLES, P-7, <10' | EA | 6.000 |
| | 0519- 78- | BOLLARDS | EA | 2.000 |
| | 0630- 2- 11 | CONDUIT, FURNISH & INSTALL, OPEN TRENCH | LF | 57,076.000 |
| | 0630- 2- 12 | CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE | LF | 1,575.000 |
| | 0630- 2- 14 | CONDUIT, FURNISH & INSTALL, ABOVEGROUND | LF | 113,410.000 |
| | 0630- 2- 15 | CONDUIT, FURNISH & INSTALL, BRIDGE MOUNT | LF | 1,630.000 |
| | 0633- 1-113 | FIBER OPTIC CABLE, F&I, OVERHEAD,49-96 FIBERS | LF | 37,560.000 |
| | 0633- 1-121 | FIBER OPTIC CABLE, F&I, UNDERGROUND,2-12 FIBERS | LF | 500.000 |
| | 0633- 1-122 | FIBER OPTIC CABLE, F&I, UNDERGROUND,13-48 FIBERS | LF | 15,761.000 |
| | 0633- 1-123 | FIBER OPTIC CABLE, F&I, UNDERGROUND,49-96 FIBERS | LF | 92,773.000 |
| | 0633- 1-124 | FIBER OPTIC CABLE, F&I, UNDERGROUND, 97 - 144 FIBERS | LF | 45,872.000 |
| | 0633- 1-420 | FIBER OPTIC CABLE, RELOCATE, UNDERGROUND | LF | 260.000 |
| | 0633- 1-620 | FIBER OPTIC CABLE, REMOVE, UNDERGROUND | LF | 89,044.000 |
| | 0633- 2- 31 | FIBER OPTIC CONNECTION, INSTALL, SPLICE | EA | 936.000 |
| | 0633- 2- 32 | FIBER OPTIC CONNECTION, INSTALL, TERMINATION | EA | 736.000 |
| | 0633- 3- 11 | FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE ENCLOSURE | EA | 47.000 |
| | 0633- 3- 12 | FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE TRAY | EA | 70.000 |
| | 0633- 3- 13 | FIBER OPTIC CONNECTION HARDWARE, F&I, PRETERMINATED CONNECTOR ASSEMBLY | EA | 2.000 |
| | 0633- 3- 14 | FIBER OPTIC CONNECTION HARDWARE, F&I, BUFFER TUBE FAN OUT KIT | EA | 44.000 |
| | 0633- 3- 15 | FIBER OPTIC CONNECTION HARDWARE, F&I, PRETERMINATED PATCH PANEL | EA | 45.000 |
| | 0633- 3- 17 | FIBER OPTIC CONNECTION HARDWARE, F&I, CONNECTOR PANEL | EA | 43.000 |
| | 0633- 8- 1 | MULTI-CONDUCTOR COMMUNICATION CABLE, FURNISH & INSTALL | LF | 200.000 |
| | 0635- 2- 11 | PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE | EA | 164.000 |
| | 0635- 2- 12 | PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE | EA | 109.000 |
| | 0635- 2- 13 | PULL & SPLICE BOX, F&I, 30" X 60" RECTANGULAR OR 36" ROUND COVER SIZE | EA | 23.000 |
| | 0635- 3- 12 | JUNCTION BOX, FURNISH & INSTALL, MOUNTED | EA | 48.000 |
| | 0639- 1-111 | ELECTRICAL POWER SERVICE, F&I, OVERHEAD, METER FURNISHED BY POWER COMPANY | AS | 4.000 |
| | 0639- 2- 1 | ELECTRICAL SERVICE WIRE, FURNISH & INSTALL | LF | 75,357.000 |
| | 0639- 2- 6 | ELECTRICAL SERVICE WIRE, REMOVE | LF | 34,130.000 |
| | 0639- 3- 11 | ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT | EA | 6.000 |

Call Order: 001 Proposal: E8Q79

| ALT | Item | Description | Unit | Quantity |
|-----|--------------|--|------|----------|
| | 0639- 3- 12 | ELECTRICAL SERVICE DISCONNECT, F&I, CABINET | EA | 43.000 |
| | 0639- 6- 1 | ELECTRICAL POWER SERVICE- TRANSFORMER FURNISH & INSTALL | EA | 4.000 |
| | 0641- 2- 13 | PRESTRESSED CONCRETE POLE, F&I, TYPE P-III | EA | 26.000 |
| | 0641- 2- 80 | PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- POLE 30' AND GREATER | EA | 14.000 |
| | 0641- 3-169 | CONCRETE CCTV POLE, FURNISH & INSTALL WITH LOWERING DEVICE, 69' | EA | 10.000 |
| | 0641- 3-175 | CONCRETE CCTV POLE, FURNISH & INSTALL WITH LOWERING DEVICE, 75' | EA | 7.000 |
| | 0641- 3-186 | CONCRETE CCTV POLE, FURNISH & INSTALL WITH LOWERING DEVICE, 86' | EA | 1.000 |
| | 0641- 3-800 | CONCRETE CCTV POLE, COMPLETE POLE REMOVAL | EA | 8.000 |
| | 0660- 3- 11 | VEHICLE DETECTION SYSTEM- MICROWAVE, FURNISH & INSTALL CABINET EQUIPMENT | EA | 38.000 |
| | 0660- 3- 12 | VEHICLE DETECTION SYSTEM- MICROWAVE, FURNISH & INSTALL, ABOVE GROUND EQUIPMENT | EA | 38.000 |
| | 0660- 3- 60 | VEHICLE DETECTION SYSTEM - MICROWAVE, REMOVE, COMPLETE SYSTEM | EA | 21.000 |
| | 0660- 6-121 | VEHICLE DETECTION SYSTEM- AVI, BLUETOOTH, FURNISH & INSTALL, CABINET EQUIPMENT | EA | 5.000 |
| | 0660- 6-122 | VEHICLE DETECTION SYSTEM- AVI, BLUETOOTH, FURNISH & INSTALL, ABOVE GROUND EQUIPMENT | EA | 5.000 |
| | 0660- 6-600 | VEHICLE DETECTION SYSTEM- AVI, REMOVE COMPLETE SYSTEM | EA | 2.000 |
| | 0676- 2-122 | ITS CABINET, FURNISH & INSTALL, POLE MOUNT WITH SUNSHIELD, 336S, 24" W X 46" H X 22" D | EA | 41.000 |
| | 0676- 2-143 | ITS CABINET, FURNISH & INSTALL, BASE MOUNT, 334, 24" W X 66" H X 30" D | EA | 2.000 |
| | 0676- 2-600 | ITS CABINET- REMOVE | EA | 23.000 |
| | 0682- 1-133 | ITS CCTV CAMERA, F&I, DOME ENCLOSURE - NON-PRESSURIZED, IP, HIGH DEFINITION | EA | 19.000 |
| | 0682- 1-600 | ITS CCTV CAMERA,, REMOVE & DISPOSAL | EA | 8.000 |
| | 0684- 1- 1 | MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL | EA | 42.000 |
| | 0684- 2- 1 | DEVICE SERVER, FURNISH & INSTALL | EA | 41.000 |
| | 0684- 6- 40 | WIRELESS COMMUNICATION DEVICE, RELOCATE | EA | 1.000 |
| | 0685- 1- 11 | UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, LINE INTERACTIVE | EA | 43.000 |
| | 0700- 9-137 | WALK-IN DYNAMIC MESSAGE SIGN, FURNISH & INSTALL- WITH UPS FULL COLOR, 201-300 SF | EA | 2.000 |
| | 0700- 9-600 | WALK-IN DYNAMIC MESSAGE SIGN, REMOVE | EA | 1.000 |
| | 0700- 10-115 | DMS SUPPORT STRUCTURE, FURNISH & INSTALL, SPAN, 51-100 FT | EA | 2.000 |
| | 0700- 10-600 | DMS SUPPORT STRUCTURE, REMOVE | EA | 1.000 |