

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

Letting: 08190312                      Call Order: 003      Proposal: E8R76                      District:08

Counties: ORANGE

Road Name: RECONSTRUCT TPK MAINLINE MP 269.4 - 273.3

Limits: 75470000

Project(s): 43945715201(\*)                      Federal Aid No: N/A

|                        |             |                            |          |
|------------------------|-------------|----------------------------|----------|
| Total Roadway Length:  | 4.101 Miles | Contract Days:             | 415      |
| Total Bridge Length:   | 0.000 Miles | Letting Date:              | 03/12/19 |
| Total Proposal Length: | 4.101 Miles | Contract Execution Days:   | 10       |
|                        |             | Special Start Date:        | N/A      |
|                        |             | Aquis/Flexible Start Time: | 15       |

Proposal Budget Estimate:                      \$12,673,526.00

Please read the full advertisement

**Description:**

Work consists of providing all labor, materials, equipment and incidentals necessary for the milling and resurfacing and pavement markings on SR 91 mainline from MP 269.400 to MP 273.300 located in Orange County. No Pre-Bid Conference. Contractor must be prequalified in Hot Plant-Mixed Bituminous Courses.

The summary of pay items for this project is listed in the Plans.

**Call Order: 003 Proposal: E8R76**

| ALT                         | Item         | Description  | Unit | Quantity   |
|-----------------------------|--------------|--|------|------------|
| <b>Section 0001 Roadway</b> |              |  |      |            |
|                             | 0101- 1-     | MOBILIZATION (43945715201)                             | LS   | 1.000      |
|                             | 0102- 1-     | MAINTENANCE OF TRAFFIC (43945715201)                   | LS   | 1.000      |
|                             | 0102- 2- 1   | SPECIAL DETOUR 1 (43945715201)                         | LS   | 1.000      |
|                             | 0102- 60-    | WORK ZONE SIGN   | ED   | 9,316.000  |
|                             | 0102- 62-    | BARRIER MOUNTED WORK ZONE SIGN- INDEX 11871/700-013    | ED   | 5,395.000  |
|                             | 0102- 74- 1  | CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD | ED   | 57,513.000 |
|                             | 0102- 76-    | ARROW BOARD / ADVANCE WARNING ARROW PANEL              | ED   | 1,082.000  |
|                             | 0102- 78-    | TEMPORARY RETROREFLECTIVE PAVEMENT MARKER              | EA   | 24,742.000 |
|                             | 0102- 99-    | PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY            | ED   | 429.000    |
|                             | 0102-150- 1  | PORTABLE REGULATORY, SIGN                              | ED   | 830.000    |
|                             | 0102-150- 2  | RADAR SPEED DISPLAY UNIT                               | ED   | 830.000    |
|                             | 0104- 10- 3  | SEDIMENT BARRIER                                       | LF   | 13,706.000 |
|                             | 0104- 18-    | INLET PROTECTION SYSTEM                                | EA   | 235.000    |
|                             | 0107- 1-     | LITTER REMOVAL   | AC   | 958.150    |
|                             | 0107- 2-     | MOWING   | AC   | 436.380    |
|                             | 0120- 71-    | REGULAR EXCAVATION (3-R PROJECTS ONLY) (43945715201)   | LS   | 1.000      |
|                             | 0327- 70- 1  | MILLING EXIST ASPH PAVT, 1" AVG DEPTH                  | SY   | 41,542.000 |
|                             | 0327- 70- 5  | MILLING EXIST ASPH PAVT, 2" AVG DEPTH                  | SY   | 23,294.000 |
|                             | 0327- 70- 8  | MILLING EXIST ASPH PAVT, 2 1/2" AVG DEPTH              | SY   | 39,156.000 |
|                             | 0327- 70- 11 | MILLING EXIST ASPH PAVT, 2 1/4" AVG DEPTH              | SY   | 76,962.000 |
|                             | 0327- 70- 13 | MILLING EXIST ASPH PAVT, 1 3/4" AVG DEPTH              | SY   | 640.000    |
|                             | 0327- 70- 19 | MILLING EXIST ASPH PAVT, 3/4" AVG DEPTH                | SY   | 10,293.000 |
|                             | 0327- 70- 20 | MILLING EXIST ASPH PAVT, 3 3/4" AVG DEPTH              | SY   | 51,023.000 |

**Call Order: 003 Proposal: E8R76**

| ALT                         | Item         | Description   | Unit | Quantity   |
|-----------------------------|--------------|---|------|------------|
|                             | 0327- 70- 42 | MILLING EXIST ASPH PAVT, 7 1/4" AVG DEPTH   | SY   | 95,885.000 |
|                             | 0334- 1- 12  | SUPERPAVE ASPHALTIC CONC, TRAFFIC B   | TN   | 10,231.000 |
|                             | 0334- 1- 14  | SUPERPAVE ASPHALTIC CONC, TRAFFIC D   | TN   | 4,209.400  |
|                             | 0334- 1- 58  | SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC D, HIGH POLYMER   | TN   | 44,872.700 |
|                             | 0337- 7- 26  | ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, HIGH POLYMER                                     | TN   | 9,596.900  |
|                             | 0546- 72- 1  | GROUND-IN RUMBLE STRIPS, 16"  | GM   | 15.100     |
|                             | 0570- 1- 2   | PERFORMANCE TURF, SOD   | SY   | 6,666.000  |
|                             | 0710- 11-101 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"   | GM   | 39.691     |
|                             | 0710- 11-102 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"            | GM   | 0.256      |
|                             | 0710- 11-103 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE MARKINGS, 12"                   | GM   | 0.114      |
|                             | 0710- 11-131 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE                      | GM   | 72.725     |
|                             | 0710- 11-160 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL                                     | EA   | 6.000      |
|                             | 0710- 11-170 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS  | EA   | 6.000      |
|                             | 0710- 11-201 | PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"  | GM   | 39.638     |
|                             | 0999- 16-    | PARTNERING, DO NOT BID (43945715201)  | LS   | 1.000      |
|                             | 0999- 25-    | INITIAL CONTINGENCY AMOUNT, DO NOT BID (43945715201)  | LS   | 1.000      |
| <b>Section 0002 Signing</b> |              |   |      |            |
|                             | 0710- 90-    | PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43945715201)  | LS   | 1.000      |
|                             | 0711- 11-103 | THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR INTERCHANGE MARKINGS                               | GM   | 0.458      |
|                             | 0711- 11-124 | THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS                             | LF   | 13.000     |
|                             | 0711- 11-160 | THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL   | EA   | 7.000      |
|                             | 0711- 11-170 | THERMOPLASTIC, STANDARD, WHITE, ARROW   | EA   | 7.000      |
|                             | 0711- 15-101 | THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"                             | GM   | 8.063      |
|                             | 0711- 15-131 | THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP | GM   | 24.538     |
|                             | 0711- 15-201 | THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"                           | GM   | 8.063      |
|                             | 0713-103-101 | PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES   | GM   | 0.138      |
|                             | 0713-103-131 | PERMANENT TAPE, WHITE, SKIP/DOTTED, 6" FOR CONCRETE SURFACES                                      | GM   | 0.372      |
|                             | 0713-103-201 | PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES  | GM   | 0.138      |
|                             | 0713-103-331 | PERMANENT TAPE, BLACK, SKIP/DOTTED, 6" FOR CONCRETE SURFACES                                      | GM   | 0.372      |
|                             | 0713-107-    | PREFORMED/PERMANENT TAPE, REMOVE  | SF   | 2,693.000  |