

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	08190312	Call Order: 005	Proposal: E8R78	District:08
Counties:	HERNANDO, HILLSBOROUGH, PASCO, POLK, TURNPIKE			
Road Name:	WRONG WAY SIGNING UPGRADES - ZONE 4			
Limits:	Midpoint			
Project(s):	19077315236(*)	Federal Aid No: N/A		
Total Roadway Length:	0.000 Miles	Contract Days:	100	
Total Bridge Length:	0.000 Miles	Letting Date:	03/12/19	
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	14	

Proposal Budget Estimate: \$300,000.00

Please read the full advertisement

Description:

The work specified in this contract consists of providing all labor, materials, equipment and incidentals necessary to provide thermoplastic pavement markings, retro-reflective pavement markers, and highway signing improvements such as installation and removal of signs at various locations on the Polk Parkway (SR 570), Milepost (MP) 0.0 to 24.4, Veterans Expressway (SR 589), MP 2.0 to 5.0 and Suncoast Parkway (SR 589), MP 13.5 to 54.9.

Prior to beginning work under this Contract, the Contractor shall submit to the Engineer for approval, two copies of the Contractor's proposed plan and methods for performing the work, including a listing of equipment and personnel anticipated for use.

No U-turns shall be permitted as a condition of this Contract, except at Service Plazas.

The Contractor shall perform all work during day and night hours in accordance with the Turnpike Lane Closure Policy.

All lane closures shall be during the hours of 9:00 P.M to 5:00 A.M. and in one direction for one lane only.

NO PRE-BID CONFERENCE WILL BE HELD FOR THIS PROJECT.

CONTRACTOR EXPERIENCE DOCUMENTATION: Expertise and Experience is required in the performance of Pavement Markings. The Experience in Pavement Markings form (850-070-06) must be filled out and submitted with the bid to be reviewed by the Department. If a Contractor is presently prequalified with the Department in Pavement Markings, it is not necessary to submit the form.

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Call Order: 005 Proposal: E8R78

ALT	Item	Description	Unit	Quantity
Section 0001 MAINTENANCE SUPPORT SERVICES (MH)				
	0101- 1-	MOBILIZATION	LS	1.000
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	132.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	39.000
	0700- 1- 13	SINGLE POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	39.000
	0700- 1- 14	SINGLE POST SIGN, F&I GROUND MOUNT, 31+ SF	AS	3.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	20.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	61.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	2.000
	0700- 3-102	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 12-20 SF	EA	1.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	1.000
	0700- 13- 12	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 2'	EA	54.000
	0706- 3-	RETRO-REFLECTIVE/RAISED PAVEMENT MARKERS	EA	408.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.040
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	49.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	68.000
	0711- 11-180	THERMOPLASTIC, STANDARD, WHITE, YIELD LINE	LF	30.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.750
	0711- 12-101	THERMOPLASTIC, REFURBISHMENT, WHITE, SOLID, 6"	GM	0.300
	0711- 12-122	THERMOPLASTIC, REFURBISHMENT, WHITE, SOLID, 8" FOR MAINTENANCE USE	LF	325.000
	0711- 12-124	THERMOPLASTIC, REFURBISHMENT, WHITE, SOLID, 18" FOR DIAGONAL OR CHEVRON, MAINTENANCE USE ONLY	LF	375.000
	0711- 12-125	THERMOPLASTIC, REFURBISHMENT, WHITE, SOLID, 24" FOR STOP LINE OR CROSSWALK, MAINTENANCE USE ONLY	LF	70.000
	0711- 12-141	THERMOPLASTIC, REFURBISHMENT, WHITE, 2-4 DOTTED GUIDELINE / 6-10 GAP EXTENSION, 6", MAINTENANCE USE ONLY	GM	0.200
	0711- 12-160	THERMOPLASTIC, REFURBISH, WHITE, MESSAGE	EA	5.000
	0711- 12-170	THERMOPLASTIC, REFURBISH, WHITE, ARROWS	EA	13.000
	0711- 12-201	THERMOPLASTIC, REFURBISHMENT, YELLOW, SOLID, 6"	GM	0.100
	0711- 12-241	THERMOPLASTIC, REFURBISHMENT, YELLOW 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6" MAINT USE ONLY	GM	0.025
	0711- 14-660	THERMOPLASTIC, PREFORMED, MULTI COLOR ROUTE SHIELD	EA	22.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	0.040
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.130
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	0.078
	0711- 17-	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS: NON-CONFLICTING ONLY	SF	600.000