

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

---

Letting:	08190312	Call Order: 006	Proposal: E8R79-R0	District:08
Counties:	BROWARD, MIAMI-DADE, PALM BEACH, TURNPIKE			
Road Name:	ASPHALT MAINTENANCE - ZONE 1			
Limits:	Midpoint			
Project(s):	19236817210(*)	Federal Aid No: N/A		
Total Roadway Length:	0.000 Miles	Contract Days:	365	
Total Bridge Length:	0.000 Miles	Letting Date:	03/12/19	
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	14	

Proposal Budget Estimate: \$500,000.00

Please read the full advertisement

**Description:**

The work specified in this contract consists of providing all labor, materials, equipment, and incidentals necessary to perform maintenance and repair of asphalt pavement deficiencies and defects, including replacing existing asphalt pavement, provide paint and thermoplastic pavement markings, and raised pavement markers at various locations on the Homestead Extension Florida's Turnpike (SR 821), Milepost (MP) 0.0 to 46.5; Florida's Turnpike (SR 91), MP 0.0X to 100.0, and Sawgrass Expressway (SR 869), MP 0.0 to 22.5.

Prior to beginning work under this Contract, the Contractor shall submit to the Engineer for approval, two copies of the Contractor's proposed plan and methods for performing the work, including a listing of equipment and personnel anticipated for use.

The Contractor shall perform all work during day and night hours in accordance with the Turnpike Lane Closure Policy.

No U-turns shall be permitted as a condition of this Contract, except at Service Plazas.

Night work shall be performed between the hours of 9:00 PM to 5:00 AM, Monday through Thursday.

**NO PRE-BID CONFERENCE WILL BE HELD FOR THIS PROJECT.**

**CONTRACTOR EXPERIENCE DOCUMENTATION:** Expertise and Experience is required in the performance of Asphalt Paving. The Experience in Asphalt Paving Form (850-070-01) must be filled out and submitted with the bid to be reviewed by the Department. If a Contractor is presently prequalified with the Department in Hot Plant Mix Bituminous Course, it is not necessary to submit the form.

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

**Call Order: 006 Proposal: E8R79-R0**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 ASPHALT REPAIR (MECHANICAL) (TN)</b>				
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	300.000
	0102- 60-	WORK ZONE SIGN	ED	500.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	3,000.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	50.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	50.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	20.000
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	750.000
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	10.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	1.600
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	1.600
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	1.600
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	200.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	100.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	100.000
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	10.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	10.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	1.600
	0711- 15-102	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SOLID, 8"	GM	0.500
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	2.500
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	1.600
	E101- 1- 1	MOBILIZATION	LO	12.000
	E101- 72-	MOBILIZATION (EMERGENCY RESPONSE)	EA	2.000
	E327- 73-	MILLING EXISTING ASPHALT PAVEMENT	TN	765.000
	E706- 1- 42	REFLECTIVE PAVEMENT MARKER(REMOVE AND REPLACE)(CLASS B)	EA	750.000