

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

---

Letting:	08190910	Call Order: 002	Proposal: E8R81	District:08
Counties:	LAKE			
Road Name:	RECONSTRUCT TPK (SR91) NB OUTSIDE TRAVEL LANE IN LAKE CNTY			
Limits:	11470000			
Project(s):	44132225201(*)	Federal Aid No: N/A		
Total Roadway Length:	0.500 Miles	Contract Days:	57	
Total Bridge Length:	0.000 Miles	Letting Date:	09/10/19	
Total Proposal Length:	0.500 Miles	Contract Execution Days:		
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	30	
Proposal Budget Estimate:	\$1,216,556.00			

Please read the full advertisement

**Description:**

Work consists of providing all labor, materials, equipment and incidentals necessary for the Milling & Resurfacing, Base Work, Shoulder Treatment, Drainage Improvements, and other incidental construction on the Turnpike from Turnpike MP 289.178 to Turnpike MP 290.009 in Lake County.

No Pre-Bid Conference.

**BUSINESS DEVELOPMENT INITIATIVE**

Bidders must be a "Small Business" as defined by FDOT. Small business size standards can be found at <http://www.fdot.gov/equalopportunityoffice/bdi.shtm>.

For more information about bidding on BDI projects, please see the training guide located at <http://www.cmdp-bgp.com/bdiprojects.html>

Prequalification per Rule 14-22 is not required.

Bidders must complete and submit the Small Business Affidavit (Form No. 275-000-01) for approval prior to receipt of bid documents.

The form may be accessed at: <http://www.fdot.gov/equalopportunityoffice/bdi.shtm>.

It is only necessary to submit the Small Business Affidavit (SBA) form once per year.

Send a completed and notarized affidavit as an attachment to: [fdot.bdi@dot.state.fl.us](mailto:fdot.bdi@dot.state.fl.us).

All Sublet work must be contracted to a small business or businesses as defined by the Department. The subcontractor must also submit a notarized Small Business Affidavit Form provided by the Department prior to the start of work.

Bidders must submit the BDI Reference Sheet (Form No. 275-000-02) with the bid. Upload the completed BDI Reference Sheet (Form No. 275-000-02) as a zip file using the "File Attachment Upload" folder in the Expedite application.

BDI Reference Sheet may be found at: <http://www.fdot.gov/equalopportunityoffice/bdi.shtm>.

Proposal Guaranty of \$500 is required for bids over \$150,000 and may be in the form of a Cashier's Check, the BDI Bid or Proposal Bond (Form No. 375-020-16), or the standard Bid or Proposal Bond form, Form No. 375-020-09).

For contracts over \$250,000.00, the Contractor shall supply to the Department and keep in force at all times during the term of this Contract, a Performance Bond provided by a surety authorized to do business in the State of Florida. A Performance Bond is not required for contracts \$250,000 and less.

The summary of pay items for this project is listed in the Plans.

**Call Order: 002 Proposal: E8R81**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Roadway</b>				
	0101- 1-	MOBILIZATION (44132225201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44132225201)	LS	1.000
	0102- 2- 1	SPECIAL DETOUR 1 (44132225201)	LS	1.000
	0102- 2- 2	SPECIAL DETOUR 2 (44132225201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	316.000
	0102- 60-	WORK ZONE SIGN	ED	1,220.000
	0102- 71- 16	TEMPORARY BARRIER, F&I, FREE STANDING	LF	1,260.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	6,517.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	32.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	57.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	394.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	1.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	96.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	114.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	114.000
	0102-912- 2	PAVEMENT MARKING REMOVABLE TAPE, YELLOW, SOLID	LF	2,773.000
	0104- 10- 3	SEDIMENT BARRIER	LF	3,992.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	8.000
	0107- 1-	LITTER REMOVAL	AC	28.730
	0107- 2-	MOWING	AC	24.210
	0110- 1- 1	CLEARING & GRUBBING (44132225201)	LS	1.000
	0120- 1-	REGULAR EXCAVATION	CY	1,827.000
	0120- 6-	EMBANKMENT	CY	64.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	3,264.000
	0285-736-	OPTIONAL BASE- GRADED AGGREGATE, 24" FOR PROJECT 441322-2 -52-01	SY	1,583.000
	0327- 70- 19	MILLING EXIST ASPH PAVT, 3/4" AVG DEPTH	SY	10,629.000
	0327- 70- 33	MILLING EXIST ASPH PAVT, 7 3/4" AVG DEPTH	SY	1,564.000
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	403.300
	0334- 1- 14	SUPERPAVE ASPHALTIC CONC, TRAFFIC D	TN	344.100
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	134.400
	0334- 1- 54	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC D, PG76-22	TN	172.100
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	490.700
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	0.700
	0440- 1- 20	UNDERDRAIN, TYPE II	LF	577.000
	0440- 70-	UNDERDRAIN INSPECTION BOX	EA	5.000
	0440- 73- 2	UNDERDRAIN OUTLET PIPE, 6"	LF	218.000
	0446- 1- 1	EDGEDRAIN DRAINCRETE, STANDARD	LF	12.000
	0446- 71- 1	EDGEDRAIN OUTLET PIPE, 4"	LF	42.000
	0538- 1-	GUARDRAIL RESET	LF	75.000
	0546- 72- 1	GROUND-IN RUMBLE STRIPS, 16"	GM	1.381
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	7,604.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	0.682
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44132225201)	LS	1.000

ALT	Item	Description	Unit	Quantity
<b>Section 0002 Signing</b>				
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44132225201)	LS	1.000
	0711- 11-103	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR INTERCHANGE MARKINGS	GM	0.145
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	0.553
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.854
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	0.833