

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: 08190910 Call Order: 007 Proposal: E8S12-R0 District:08

Counties: BROWARD, MIAMI-DADE, PALM BEACH, TURNPIKE

Road Name: CABLE BARRIER MAINTENANCE - ZONE 1

Limits: Midpoint

Project(s): 19286717218(*) Federal Aid No: N/A

Total Roadway Length:	0.000 Miles	Contract Days:	365
Total Bridge Length:	0.000 Miles	Letting Date:	09/10/19
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	14

Proposal Budget Estimate: \$100,000.00

Please read the full advertisement

Description:

The work specified in this contract consists of providing all labor, materials, equipment and incidentals necessary to perform cable safety barrier maintenance in accordance with the manufacturer's recommendations including the removal, annual inspection/repair, and/or replacement of damaged or destroyed sections with all associated components at various locations on the Homestead Extension of Florida's Turnpike, Milepost (MP) 0.0 to 46.5, and Florida's Turnpike, MP 0.0X to 100.0.

Prior to beginning work under this Contract, the Contractor shall submit to the Engineer for approval, two copies of the Contractor's proposed plan and methods for performing the work, including a listing of equipment and personnel anticipated for use.

The Department does not guarantee any maximum or minimum quantity, any range of quantities, or the exact quantities shown for each bid item.

No U-turns shall be permitted as a condition of this Contract, except at Service Plazas.

NO PRE-BID CONFERENCE WILL BE HELD FOR THIS PROJECT.

Call Order: 007 Proposal: E8S12-R0

ALT	Item	Description	Unit	Quantity
Section 0001 GUARDRAIL REPAIR (LF)				
	E101- 72-	MOBILIZATION (EMERGENCY RESPONSE)	EA	20.000
	E540- 0- 0	CABLE BARRIER INSPECTION	LS	1.000
	E540- 0- 22	PRE-STRETCHED GALVANIZED WIRE ROPE, INC INCIDENTALS TURNBUCKLES, TESTING AND RETENTIONING	LF	100.000
	E540- 0- 25	END ANCHOR REPAIR/REPLACE INCLUDES ALL INCIDENTALS FOUNDATION, GATING END TERMINALS & ASSOC HARDWARE	EA	2.000
	E540- 0- 26	CABLE BARRIER HAIRPIN AND LOCKPLATE ASSEMBLY	EA	350.000
	E540- 3- 1	GIBRALTAR TL 3 LINE POST REP INCL HAIRPIN & LOCKPLATE	EA	120.000
	E540- 3- 1	GIBRALTAR TL 3 LINE POST REP >4 INCL HAIRPIN & LOCKPLATE	EA	200.000
	E540- 3- 2	GIBRALTAR TERMINAL POST REP (INCL 1, 2, 3 & 4)	EA	25.000
	E540- 3- 3	GIBRALTAR ANCHOR POST REPLACEMENT	EA	5.000
	E540- 1 -01	CABLE SAFETY BARRIER (BRIFEN) STANDARD POST REPLACEMENT	EA	90.000
	E540- 1 -02	CABLE SAFETY BARRIER (BRIFEN) STANDARD POST REPLACEMENT	EA	225.000
		> 4		