

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

Letting: 08180911      Call Order: 001      Proposal: E8R14      District:08

Counties: LAKE

Road Name: ROADWAY IMPROVEMENTS TPK MAINLINE MP284.417 TO 284.512

Limits: 11470000

Project(s): 43716725201(\*)      Federal Aid No: N/A

Total Roadway Length:	0.095 Miles	Contract Days:	65
Total Bridge Length:	0.000 Miles	Letting Date:	09/11/18
Total Proposal Length:	0.095 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	30

Proposal Budget Estimate: \$881,602.00

Please read the full advertisement

**Description:**

Work consists of providing all labor, materials, equipment and incidentals necessary for the milling, placing overbuild, and resurfacing to correct travel lane and shoulder settlement, replacing guardrail, regrading the median ditch, and signing and pavement marking improvements on SR 91 (Florida's Turnpike) from MP 284.417 to MP 284.512 in Lake County. The summary of pay items for this project is listed in the Plans.

No Pre-Bid Conference. Contractor must be prequalified in Hot Plant-Mixed Bituminous Courses.

**Call Order: 001 Proposal: E8R14**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Roadway</b>				
	0101- 1-	MOBILIZATION (43716725201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43716725201)	LS	1.000
	0102- 2- 1	SPECIAL DETOUR 1 (43716725201)	LS	1.000
	0102- 2- 2	SPECIAL DETOUR 2 (43716725201)	LS	1.000
	0102- 2- 3	SPECIAL DETOUR 3 (43716725201)	LS	1.000
	0102- 2- 4	SPECIAL DETOUR 4 (43716725201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	650.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	100.000
	0102- 71- 16	TEMPORARY BARRIER, F&I, FREE STANDING	LF	1,000.000
	0102- 71- 25	TEMPORARY BARRIER, RELOCATE, ANCHORED	LF	100.000
	0102- 71- 26	TEMPORARY BARRIER, RELOCATE, FREE STANDING	LF	1,000.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	1,950.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	65.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	72.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	4.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	93.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	160.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	130.000
	0104- 1-	ARTIFICIAL COVERINGS /ROLLED EROSION CONTROL PRODUCTS	SY	562.000
	0104- 10- 3	SEDIMENT BARRIER	LF	2,402.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	1.000
	0107- 1-	LITTER REMOVAL	AC	5.340

**Call Order: 001 Proposal: E8R14**

ALT	Item	Description	Unit	Quantity
	0107- 2-	MOWING	AC	4.150
	0110- 1- 1	CLEARING & GRUBBING (43716725201)	LS	1.000
	0120- 1-	REGULAR EXCAVATION	CY	1.000
	0120- 6-	EMBANKMENT	CY	238.000
	0162- 1- 11	PREPARED SOIL LAYER, FINISH SOIL LAYER, 6"	SY	859.000
	0327- 70- 3	MILLING EXIST ASPH PAVT, 4 1/2" AVG DEPTH	SY	562.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	958.000
	0327- 70- 17	MILLING EXIST ASPH PAVT, 3 1/4" AVG DEPTH	SY	2,682.000
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	405.900
	0334- 1- 14	SUPERPAVE ASPHALTIC CONC, TRAFFIC D	TN	373.300
	0334- 1- 54	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC D, PG76-22	TN	402.800
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	113.200
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	93.100
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	1,000.000
	0536- 1- 3	GUARDRAIL- ROADWAY, DOUBLE FACE	LF	500.000
	0536- 5- 1	RUB RAIL FOR GUARDRAIL, SINGLE SIDED RUB RAIL	LF	500.000
	0536- 73-	GUARDRAIL REMOVAL	LF	1,500.000
	0546- 72- 1	GROUND-IN RUMBLE STRIPS, 16"	GM	0.380
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	2,000.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	0.570
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	0.558
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.567
	0999- 16-	PARTNERING, DO NOT BID (43716725201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43716725201)	LS	1.000
<b>Section 0002 Signing</b>				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	2.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	2.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43716725201)	LS	1.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	0.189
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.189
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	0.189