

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 08181115 Call Order: 002 Proposal: E8R53 District:08

Counties: SUMTER

Road Name: OKAHUMPKA SERVICE PLAZA (MP 299)- RAMP & SIGNING IMPROVEMENT

Limits: 18470000

Project(s): 44130615201(*) Federal Aid No: N/A

Total Roadway Length:	0.570 Miles	Contract Days:	151
Total Bridge Length:	0.000 Miles	Letting Date:	11/15/18
Total Proposal Length:	0.570 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	90

Proposal Budget Estimate: \$1,104,585.00

Please read the full advertisement

Description:

Work consists of providing all labor, materials, equipment and incidentals necessary for the milling, resurfacing and signage upgrade improvements for the Service Plaza Ramps and frontage roads for Turnpike's Okahumpka Service Plaza, MP 299 in Sumter County. No Pre-Bid Conference. Contractor must be prequalified in Hot Plant-Mixed Bituminous Courses.

The summary of pay items for this project is listed in the Plans.

Call Order: 002 Proposal: E8R53

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44130615201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44130615201)	LS	1.000
	0102- 2- 1	SPECIAL DETOUR 1 (44130615201)	LS	1.000
	0102- 2- 2	SPECIAL DETOUR 2 (44130615201)	LS	1.000
	0102- 2- 3	SPECIAL DETOUR 3 (44130615201)	LS	1.000
	0102- 2- 4	SPECIAL DETOUR 4 (44130615201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	4,568.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	16,683.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	416.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	2,690.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	652.000
	0104- 10- 3	SEDIMENT BARRIER	LF	5,540.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	4.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	15.000
	0107- 1-	LITTER REMOVAL	AC	7.410
	0107- 2-	MOWING	AC	9.880
	0110- 1- 1	CLEARING & GRUBBING (44130615201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	90.000
	0120- 1-	REGULAR EXCAVATION	CY	56.000
	0120- 6-	EMBANKMENT	CY	19.000
	0160- 4-	TYPE B STABILIZATION	SY	3,217.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	1,675.000

Call Order: 002 Proposal: E8R53

ALT	Item	Description	Unit	Quantity
	0327- 70- 2	MILLING EXIST ASPH PAVT, 3 1/2" AVG DEPTH	SY	1,713.000
	0327- 70- 18	MILLING EXIST ASPH PAVT, 5 1/2" AVG DEPTH	SY	9,378.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	1,031.500
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	1,403.000
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-12.5, PG 76-22	TN	1,052.200
	0400- 1- 2	CONCRETE CLASS I, ENDWALLS	CY	3.700
	0425- 1-910	INLETS, CLOSED FLUME	EA	8.000
	0430-175-115	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 15"S/CD	LF	24.000
	0430-175-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	16.000
	0430-982-123	MITERED END SECTION, OPTIONAL ROUND, 15" CD	EA	1.000
	0430-982-129	MITERED END SECTION, OPTIONAL ROUND, 24" CD	EA	2.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	403.000
	0524- 1- 2	CONCRETE DITCH PAVEMENT, NON REINFORCED, 4"	SY	15.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	5.300
	0570- 1- 1	PERFORMANCE TURF	SY	2,890.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	1.411
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.076
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	764.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	10.000
	0710- 11-180	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, YIELD LINE	LF	73.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.431
	0999- 16-	PARTNERING, DO NOT BID (44130615201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44130615201)	LS	1.000
Section 0002 Signing				
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	2.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	1.000
	0700- 2- 12	MULTI- POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	2.000
	0700- 2- 13	MULTI- POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	7.000
	0700- 2- 14	MULTI- POST SIGN, F&I GROUND MOUNT, 31-50 SF	AS	2.000
	0700- 2- 60	MULTI- POST SIGN, REMOVE	AS	11.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	2.000
	0700- 3-205	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 51-100 SF	EA	5.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	10.000
	0700- 3-605	SIGN PANEL, REMOVE, 51-100 SF	EA	5.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	40.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44130615201)	LS	1.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	416.000
	0711- 11-180	THERMOPLASTIC, STANDARD, WHITE, YIELD LINE	LF	28.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	10.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	0.705
	0711- 15-102	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SOLID, 8"	GM	0.023

Call Order: 002 Proposal: E8R53

ALT	Item	Description	Unit	Quantity
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	0.607