

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: 08181016 Call Order: 003 Proposal: E8R56 District:08

Counties: TURNPIKE

Road Name: TPK MAINLINE SHOULDER EVACUATION NB (MP 88 - 140)

Limits: 89470000

Project(s): 44290165201(*) Federal Aid No: N/A

Total Roadway Length:	105.620 Miles	Contract Days:	70
Total Bridge Length:	0.000 Miles	Letting Date:	10/16/18
Total Proposal Length:	105.620 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	30

Proposal Budget Estimate: \$801,324.00

Please read the full advertisement

Description:

Work consists of providing all labor, materials, equipment and incidentals necessary for the widening of northbound inside travel lane at MP 100.29, MP 113.29, and MP 115.510, widening of the northbound outside shoulder at MP 93.5, speed enforcement area MP 96.8 southbound, and northbound approach guardrail attachment to Bridge No. 930239 at MP 115.510 on Florida's Turnpike Mainline (SR 91) in Palm Beach County. The project includes milling and resurfacing and signing and pavement markings. The summary of pay items for this project is listed in the Plans.

No Pre-Bid Conference. Contractor must be prequalified in Hot Plant-Mixed Bituminous Courses.

Call Order: 003 Proposal: E8R56

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44290165201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44290165201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	640.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	2,986.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	59.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	94.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	129.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	118.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	118.000
	0102-911- 2	PAVEMENT MARKING REMOVABLE TAPE, WHITE OR BLACK,SOLID	LF	3,745.000
	0104- 10- 3	SEDIMENT BARRIER	LF	4,069.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	96.000
	0110- 1- 1	CLEARING & GRUBBING (44290165201)	LS	1.000
	0120- 1-	REGULAR EXCAVATION	CY	172.900
	0120- 6-	EMBANKMENT	CY	521.800
	0160- 4-	TYPE B STABILIZATION	SY	81.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	95.000
	0285-711-	OPTIONAL BASE, BASE GROUP 11	SY	307.000
	0285-712-	OPTIONAL BASE, BASE GROUP 12	SY	226.000
	0285-714-	OPTIONAL BASE, BASE GROUP 14	SY	552.000
	0285-715-	OPTIONAL BASE, BASE GROUP 15	SY	275.000
	0327- 70- 1	MILLING EXIST ASPH PAVT, 1" AVG DEPTH	SY	3,178.000

Call Order: 003 Proposal: E8R56

ALT	Item	Description	Unit	Quantity
	0327- 70- 5	MILLING EXIST ASPH PAVT, 2" AVG DEPTH	SY	46.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	913.000
	0327- 70- 11	MILLING EXIST ASPH PAVT, 2 1/4" AVG DEPTH	SY	4,904.000
	0327- 70- 19	MILLING EXIST ASPH PAVT, 3/4" AVG DEPTH	SY	4,624.000
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	297.700
	0334- 1- 14	SUPERPAVE ASPHALTIC CONC, TRAFFIC D	TN	382.100
	0334- 1- 54	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC D, PG76-22	TN	491.500
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	423.300
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	0.400
	0430-174-224	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 24"SD	LF	249.000
	0430-984-629	MITERED END SECT, OPTIONAL - ELLIPTICAL / ARCH, 24" SD	EA	6.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	38.000
	0536- 8- 13	APPROACH TRANSITION CONNECTION TO RIGID BARRIER, FURNISH AND INSTALL, TL-3	EA	2.000
	0536- 73-	GUARDRAIL REMOVAL	LF	227.000
	0546- 72- 1	GROUND-IN RUMBLE STRIPS, 16"	GM	1.416
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	1,019.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	0.709
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	0.709
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.709
	0999- 16-	PARTNERING, DO NOT BID (44290165201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44290165201)	LS	1.000
Section 0002 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	1.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44290165201)	LS	1.000
	0711- 11-103	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR INTERCHANGE MARKINGS	GM	0.007
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	0.709
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.708
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	0.708