

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 08181115 Call Order: 003 Proposal: E8R57 District:08

Counties: TURNPIKE

Road Name: TPK MAINLINE SHOULDER EVACUATION NB (MP 140 - 210)

Limits: 88470000

Project(s): 44290175201(*) Federal Aid No: N/A

Total Roadway Length:	70.383 Miles	Contract Days:	106
Total Bridge Length:	0.000 Miles	Letting Date:	11/15/18
Total Proposal Length:	70.383 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	15

Proposal Budget Estimate: \$536,492.00

Please read the full advertisement

Description:

Work consists of providing all labor, materials, equipment and incidentals necessary for widening of the northbound inside travel lane at MP 150.390 and MP 152.890, widening of the northbound outside shoulder at MP 152.490 and MP 198.200 and a speed enforcement area MP 187.710 on Florida's Turnpike Mainline (SR 91) in St. Lucie, Okeechobee and Osceola Counties. The project includes milling and resurfacing, guardrail, lighting, drainage improvements and signing and pavement markings. No Pre-Bid Conference. Contractor must be prequalified.

The summary of pay items for this project is listed in the Plans.

Call Order: 003 Proposal: E8R57

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44290175201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44290175201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	1,008.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	250.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	5,697.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	96.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	46.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	1.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	180.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	168.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	168.000
	0102-911- 2	PAVEMENT MARKING REMOVABLE TAPE, WHITE OR BLACK,SOLID	LF	1,811.000
	0104- 10- 3	SEDIMENT BARRIER	LF	2,986.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	2.000
	0107- 1-	LITTER REMOVAL	AC	9.550
	0107- 2-	MOWING	AC	8.030
	0110- 1- 1	CLEARING & GRUBBING (44290175201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	51.000
	0120- 1-	REGULAR EXCAVATION	CY	70.900
	0120- 6-	EMBANKMENT	CY	456.200
	0160- 4-	TYPE B STABILIZATION	SY	205.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	388.000

Call Order: 003 Proposal: E8R57

ALT	Item	Description	Unit	Quantity
	0285-711-	OPTIONAL BASE, BASE GROUP 11	SY	312.000
	0285-714-	OPTIONAL BASE, BASE GROUP 14	SY	267.000
	0285-715-	OPTIONAL BASE, BASE GROUP 15	SY	210.000
	0327- 70- 1	MILLING EXIST ASPH PAVT, 1" AVG DEPTH	SY	2,207.000
	0327- 70- 5	MILLING EXIST ASPH PAVT, 2" AVG DEPTH	SY	6.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	121.000
	0327- 70- 11	MILLING EXIST ASPH PAVT, 2 1/4" AVG DEPTH	SY	2,363.000
	0327- 70- 19	MILLING EXIST ASPH PAVT, 3/4" AVG DEPTH	SY	2,154.000
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	200.700
	0334- 1- 14	SUPERPAVE ASPHALTIC CONC, TRAFFIC D	TN	219.700
	0334- 1- 54	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC D, PG76-22	TN	234.300
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	205.100
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	9.200
	0425- 1-701	INLETS, GUTTER, TYPE S, <10'	EA	1.000
	0430-175-115	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 15"S/CD	LF	8.000
	0520- 6-	SHOULDER GUTTER- CONCRETE	LF	142.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	200.000
	0536- 8- 13	APPROACH TRANSITION CONNECTION TO RIGID BARRIER, FURNISH AND INSTALL, TL-3	EA	1.000
	0536- 73-	GUARDRAIL REMOVAL	LF	187.000
	0536- 85- 25	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE TYPE II	EA	1.000
	0546- 72- 1	GROUND-IN RUMBLE STRIPS, 16"	GM	0.686
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	1,413.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	0.343
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	0.343
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.343
	0999- 16-	PARTNERING, DO NOT BID (44290175201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44290175201)	LS	1.000
Section 0002 Signig				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	2.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	1.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44290175201)	LS	1.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	0.343
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.343
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	0.343
Section 0003 Lighting				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	242.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	1.000
	0715- 1- 13	LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2	LF	798.000
	0715- 1- 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	LF	735.000
	0715- 4- 60	LIGHT POLE COMPLETE, RELOCATE	EA	1.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, CONVENTIONAL	EA	1.000