

**BID SOLICITATION NOTICE – Turnpike
FLORIDA DEPARTMENT OF TRANSPORTATION
CONSTRUCTION AND MAINTENANCE PROGRAMS**
Florida Turnpike Headquarters
FL Turnpike MP 263, Building 5315
Ocoee, FL 34761

Ocoee, FL
March 13, 2020
Advertisement No. 1

All bids must be completed using **Project Bids** software available on the Bid Express website at <https://bidx.com/fl/main>.

Unless otherwise stipulated in the proposal description, bids for all projects listed in this Bid Solicitation Notice must be submitted using Bid Express only. No other means of submission of bids will be accepted. Please visit the Contracts Administration Website at: <http://www.fdot.gov/contracts/> for more information on Bid Express. Submitting bids through Bid Express requires a Digital ID. To obtain a Digital ID, please contact Bid Express at <http://www.bidx.com>. Allow up to 6 days to complete the Digital ID registration.

Bids for the projects in this Bid Solicitation Notice will be accepted by Bid Express until 02:30 PM Local Time on **Tuesday, April 14, 2020**.

Bid totals for each bid submitted will be read aloud for those present and will be available at 02:30 PM **April 14, 2020** in the Turnpike Headquarters, Building 5315, Ocoee, Florida.. Agenda: a) Opening Remarks; b) 15 minutes of public input; c) Reading of bids; d) Closing. Anyone needing special accommodations under the Americans with Disabilities Act of 1990 should send an e-mail to: contracts.admin@dot.state.fl.us or call telephone number (407)264-3885. Special accommodation requests under the Americans with Disabilities Act should be made at least seven days prior to the public meeting. Bidders may obtain preliminary bid results at: <https://fdotwp1.dot.state.fl.us/wTBidLetting/LettingMain>, select district then click on appropriate date.

DEADLINE FOR PROPOSALS AND PROPOSAL HOLDERS LIST

The deadline for obtaining bid packages shall be 24 hours prior to the scheduled letting date and time. A list of plan holders may be obtained by visiting the District Contracts Administration website at: www.fdot.gov/contracts/tp, click “[Letting and Project Information](#)” and select letting date from the Lettings Menu. For compliance with Florida Statute 337.168(2), additional bidders and plan and specifications holders are not published beginning three working days prior to the letting.

-----NOTE-----

Proposals will not be issued after 02:30 PM Local Time on Monday, April 13, 2020 .

Document Ordering Information

Orders for documents are placed using the Contract Proposal Processing Online Ordering System at <https://fdotwp1.dot.state.fl.us/contractproposalprocessingonlineordering/>. There is no charge for ordering/downloading documents. Online Ordering is available Monday through Friday from 6 AM. to 9 PM. and Saturday from 6 AM. to 7 PM.

To Place An Order

- A current State of Florida Vendor Number is required prior to first-time registration; please visit http://dms.myflorida.com/egovernment_tools/myflorida_marketplace for more information. Please allow 24 to 48 hours for receipt of a new vendor number.
- Prior to placing orders, an individual shall register and establish an Internet Subscriber Account with the Department of Transportation at <https://fdotwp1.dot.state.fl.us/contractproposalprocessingonlineordering/>. Please allow 48 to 72 hours (excluding weekends and holidays) for the registration and approval.

PREQUALIFICATION

Contractors must have a current certificate of qualification in accordance with Florida Statute 337.14(1) and Rule Chapter 14-22, Florida Administrative Code, on the date of the letting to bid on construction projects over \$250,000.00 as established by the Department’s budget. Maintenance contracts do not require a contractor to have a certificate of

qualification, unless stipulated in the project description and specifications. If deemed necessary by the Department, certain maintenance contracts will contain specific requirements for maintenance contractor eligibility.

PREQUALIFIED CONTRACTORS CURRENT CAPACITY

In order for the Department to have the information required to determine a prequalified bidder's Current Capacity, it is necessary that the prequalified contractor certify the total dollar amount of all work the contractor has underway. This certification shall be accomplished electronically by submitting the Certification of Work Underway (Online Web Application) http://www.fdot.gov/contracts/PreQual_Info/prequalified.shtm to the Department every 30 calendar days.

CONFLICT OF INTEREST

A contractor who performs a constructability review on a design contract or who participates in a value engineering study workshop or cost risk analysis workshop, is prohibited from bidding on the construction of that contract.

SCRUTINIZED COMPANIES

A company that is on the Scrutinized Companies with Activities in Sudan List, is on the Scrutinized Companies with Activities in the Iran Petroleum Energy Sector List, or is engaged in business operations in Syria, may not bid on, submit a proposal for, or enter into a contract with an agency or local government entity for goods or services of \$1 million or more.

A company that is on the Scrutinized Companies that Boycott Israel List or is engaged in a boycott of Israel may not bid on, submit a proposal for, or enter into a contract with an agency or local government entity for goods or services.

BID REJECTION

Bidders are hereby notified that all bids on any of the following projects are likely to be rejected if the lowest responsive bid received exceeds the engineer's estimate by more than ten percent (10%). In the event any of the bids are rejected for this reason, the project may be deferred for re-advertising. In addition, award of all federally funded projects will be subject to Federal Highway Administration concurrence.

PROTEST RIGHTS

Pursuant to Section 120.57, Florida Statutes, any person adversely affected by a **bid solicitation** shall file both a notice of protest and bond within 72 hours after posting of the Bid Solicitation Notice, and shall file a formal written protest within ten days after filing the notice of protest. Any person who files a notice of protest as to a bid solicitation pursuant to this rule shall post with the Department, at the time of filing the notice of protest, a bond payable to the Department in the following amounts: For an action protesting a bid solicitation that requires qualification of bidders, the bond shall be \$5,000. For an action protesting a bid solicitation for which bidders are not required to be prequalified by the Department to be eligible to bid, the bond shall be \$2,500. The required notice of protest, bond and formal protest must each be timely filed with the Clerk of Agency Proceedings, Florida Department of Transportation, Mail Station 58, Room 550, 605 Suwannee Street, Tallahassee, Florida 32399-0458, FAX (850) 414-5264. Failure to file a protest within the time prescribed in Section 120.57(3), F.S., or failure to post the bond or other security required by law within the time allowed for the filing a bond shall constitute a waiver of proceedings under Chapter 120, Florida Statutes.

Pursuant to Section 120.57, Florida Statutes, any person adversely affected by a **bid rejection or contract award** shall file both a notice of protest and bond within 72 hours after the posting of the Summary of Bids. If notice of intended decision is given by certified mail or express delivery, the adversely affected person must file both the notice of protest and bond within 72 hours after receipt of the notice of intent. A formal written protest must be filed within ten days after filing the notice of protest. Any person who files a notice of protest as to a bid rejection or contract award pursuant to this rule shall post with the Department, at the time of filing the notice of protest, a bond payable to the Department in the following amounts: For an action protesting a bid rejection or contract award that requires qualification of bidders, the Bond shall be equal to one percent of the lowest bid submitted or \$5,000, whichever is greater. For an action protesting a bid rejection or contract award for which bidders are not required to be prequalified by the Department to be eligible to bid, the bond shall be \$2,500. The required notice of protest, bond, and formal protest must each be timely filed with the Clerk of Agency Proceedings, Florida Department of Transportation, Mail Station 58, Room 550, 605 Suwannee Street,

Tallahassee, Florida 32399-0458, FAX (850) 414-5264. Failure to file a protest within the time prescribed in Section 120.57(3), Florida Statutes, shall constitute a waiver of proceedings under Chapter 120, Florida Statutes.

A protest is not timely filed unless the notice of protest, bond, and the formal protest are each received by the Clerk of Agency Proceedings within the required time limits. A protest which is filed prematurely will be deemed abandoned unless timely renewed.

Interested parties can visit our Internet web site at <http://www.fdot.gov/contracts/>. Information regarding projects posted with the Clerk of Agency Proceedings, Proposal holders, Plan and Special Provisions holders, preliminary letting results, and other noteworthy information is provided on this website. Please note that, for compliance with Florida Statute 337.168(2), the Proposal holder and the Plan and Special Provision holder listings are not published beginning three working days prior to the letting until after the letting.

In the event multiple responsive bidders submit identical proposals (bids), the Department will determine the order in which proposals are to be considered for Contract award in accordance with Florida Laws, and any applicable Rules.

INSURANCE

The successful bidder shall submit current general liability insurance and workman's compensation insurance certificates for the duration of the contract in the dollar amounts and manner specified in the most current edition of the Department's Standard Specifications for Road and Bridge Construction. Insurance companies must be authorized to do business in the State of Florida. Proof of such insurance shall be filed with the District Contracts and Procurement Office before the contract can be executed. BE SURE THAT THE CONTRACT NUMBER IS ON EACH INSURANCE CERTIFICATE.

ADDENDA

No negotiations, decisions, or actions will be initiated or executed by a potential bidder as a result of any oral discussion with a State employee. Only those communications which are in writing from the Department will be considered as a duly authorized expression on behalf of the Department. Notices of changes (addenda) will be posted on the Districts Contracts Administration website at: www.fdot.gov/contracts/tp, click "[Letting and Project Information](#)" and select letting date from the Lettings Menu. It is the responsibility of all potential bidders to monitor this site for any changing information prior to submitting their bid. **All addenda shall be acknowledged when submitting bids.**

BID QUESTIONS

All work is to be done in accordance with the Plans, Specifications, and Special Provisions of State of Florida Department of Transportation. Direct questions regarding the advertised projects by posting them to the Department website at the following URL address: <https://fdotwp1.dot.state.fl.us/BidQuestionsAndAnswers/Proposal.aspx/SearchProposal>.

PROPOSAL GUARANTY

For bids over \$150,000.00, the standard proposal guaranty of 5% of the bid will be required, unless otherwise stipulated in the proposal advertisement. A Proposal Guaranty of not less than five percent (5%) of the total actual bid in the form of either a certified check, cashier's check, trust company treasurer's check, bank draft of any national or state bank, or a Surety Proposal Guaranty made payable to the Florida Department of Transportation must be received for each bid in excess of **\$150,000.00**. A check or draft in an amount less than five percent (5%) of the actual bid will invalidate the bid. The guaranty amount shall include all bid items except construction days for A+B bidding and lane closure for Lane Rental Bidding. Proposal Guaranty shall substantially conform to DOT Form 375-020-09 furnished with the Proposal. Surety2000 or SurePath electronic Proposal Guaranty submittal may be used in conjunction with Bid Express internet bid submittal. For more information please visit <http://www.surety2000.com> for Surety2000 or <http://www.insurevision.com> for SurePath. Paper Proposal Guaranty will also be accepted for bids submitted through Bid Express provided they are received prior to the deadline for receiving bids, by the location(s) identified in this Bid Solicitation Notice. If an electronic proposal guaranty is not being submitted, the bidder must submit an original proposal guaranty. (A fax or a copy sent as an attachment will not be accepted.)

EXECUTION OF CONTRACT

Pursuant to Subsections 3-6 and 3-7 of the Standard Specifications, the successful bidder shall execute the necessary contract documents and return the agreement along with a satisfactory Performance and Payment Bond within ten (10) Calendar days of award, excluding Saturdays, Sundays, and state holidays, unless noted otherwise in the project specifications. A 100% Payment and Performance Bond will be required for all projects unless noted otherwise in the

project specifications. All work is to be done in accordance with the Plans, special Provisions of the State of Florida Department of Transportation.

Prior to execution of the contract with the Department, **a corporation must show proof that it is authorized to do business in the State of Florida.** Florida corporations should provide a copy of the certificate of Incorporation and foreign corporations should provide a copy of Certificate of Authority from the Florida Department of State.

Important Note: Actual commitment and final execution of the contract is contingent upon an approved legislative budget and funds availability.

DBE PARTICIPATION

Disadvantaged Business Enterprise (DBE) Availability Goal Information is contained in the Bid Solicitation Package. DBE Participation and Bidder Opportunity List for Prime Contractors shall be reported in the **Equal Opportunity Compliance (EOC)** system no later than 3 business days of submission of the bid. The EOC system is a web based application for Prime Contractors, statewide, to report their Bidder Opportunity List, DBE Commitments, and DBE/MBE Subpayments. Complete and submit the DBE Participation (i.e. DBE Commitments) and Bid Opportunity List in the EOC.

More information regarding EOC can be referenced at: <https://www.fdot.gov/equalopportunity/eoc.shtm>

DEBARMENT/SUSPENSION

All bids submitted to the Department shall include a statement that by signing and submitting this proposal, the bidder certifies that no principal (which includes officers, directors or executives) is presently debarred, suspended, proposed for debarment, declared ineligible or voluntarily excluded from participation in this transaction by any federal department or agency.

MANDATORY PRE-BID CONFERENCE

For projects with mandatory Pre-Bid Meeting, proposals (BIDDING DOCUMENTS) will be issued only to the attendees of the meeting. Prospective bidders ordering bidding documents prior to the Pre-Bid Meeting will be given access to download the bidding documents within 24 hours after the Pre-Bid Meeting. Those prospective bidders ordering the documents after the Pre-Bid Meeting will need to contact the office advertising the project to confirm attendance and receive access to download the bidding documents. Please contact the office at least two working days prior to the deadline for obtaining bidding documents to allow time for processing.

LATE ARRIVALS TO MANDATORY PRE-BID MEETINGS

All bidders must be present and signed in prior to the start of the mandatory pre-bid meeting. Anyone not signed in at the commencement of the meeting will be considered late and will not be allowed to bid on the project.

FIRST TIME BIDDERS

Bidders bidding for the first time with the Department can access the New Bidder's Orientation document at: https://fdotwww.blob.core.windows.net/sitefinity/docs/default-source/contracts/new-bidders-orientation.pdf?sfvrsn=aef131ae_2

POSTING NOTICE

The bid tabulation and intent to award will be posted on **April 28, 2020** or **May 12, 2020** at www.fdot.gov/contracts/tp, click the "**Letting and Project Information**" and select letting date from the Listings Menu. The posting provides notice of the Department's intent to award a contract or reject all bids. The Department's Notice of Intent regarding a project will be posted on only one of the alternate posting dates. Bidders are solely responsible for timely monitoring or otherwise verifying on which of the specified alternate posting dates the posting of award or rejection of all bids actually occurs.

If the posting dates are revised, all bidders for the subject project will be notified.

AFFIRMATIVE ACTION (EQUAL EMPLOYMENT OPPORTUNITY)

The Florida Department of Transportation (hereinafter referred to as the "Department"), in accordance with **Title VI of the Civil Rights Act of 1964, 42 USC 2000d to 2000d-4 and related authorities, Title 49, Code of Federal Regulations,**

U.S. Department of Transportation, Subtitle A, Office of the Secretary, Part 21, Nondiscrimination in Federally-assisted programs of the U.S. Department of Transportation issued pursuant to such Act, hereby notifies all bidders that the Department will affirmatively insure that in any contract entered into pursuant to this advertisement, minority and disadvantaged business enterprises will be afforded the full opportunity to submit bids in response to this invitation and will not be discriminated against on the basis of race, color, national origin, or sex in consideration for an award. Further, it is the policy of the Department to not discriminate against bidders on the grounds of race, color, national origin, religion, sex, age, or disability/handicap in consideration for an award. A bidder must have an approved DBE Affirmative Action (DBE/AA) Plan prior to contract award. Please use the following link <https://www.fdot.gov/contracts/cpp-online-ordering/bidder-assist.shtm>, Standard Specifications for Road and Bridge Construction and the Special Provisions for instructions for submission of a DBE/AA Plan. The DBE/AA Plan should be submitted for approval prior to the bidding.

MINIMUM WAGE

The minimum wage for all hours worked in Florida is available at <http://www.floridajobs.org>.

EMAIL SUBSCRIPTION LIST

To get on the e-mail subscription list, go to <http://fdotwp1.dot.state.fl.us/reportsubscriptions/> and fill out the necessary information to "Subscribe". To obtain information concerning other districts, go to <http://www.fdot.gov/contracts/distco.shtm>.

NOTICE TO ALL BIDDERS

To report bid rigging activities call: 1-800-424-9071

The U.S. Department of Transportation (DOT) operates the above toll-free "hotline" Monday through Friday, 8:00 A.M. to 5:00 P.M. Local Time. Anyone with knowledge of possible bid rigging, bidder collusion, or other fraudulent activities should use the "hotline" to report such activities. The "hotline" is part of the DOT's continuing effort to identify and investigate highway construction contract fraud and abuse and is operated under the direction of the DOT Inspector General. All information will be treated confidentially and caller anonymity will be respected.

By submitting a bid, the contractor/consultant/vendor agrees to comply with section 20.055(5).Florida Statute, and to incorporate in all subcontracts the obligation to comply with section 20.055(5) Florida Statute.

**Florida Department of Transportation
Notice to Contractors Index**

Published: March 13, 2020

Letting ID: 08200414

Please use the following proposal ID and the letting ID when ordering plans/proposal or specifications for the April 14, 2020 letting.

Page Number	Proposal Id	Proposal Notes	Fin Proj Numbers	County
7	E8S11		44029115201(*) 44029125201 44029135201	SEMINOLE
12	E8S18		44042315201(*) 44042325201	MIAMI-DADE
17	E8S19		44363415201 44387815201(*)	TURNPIKE
20	E8S45-R0		19077445205(*)	HERNANDO, HILLSBOROUGH, PASCO, POLK, TURNPIKE
22	E8S46-R0		19077445206(*)	INDIAN RIVER, MARTIN, OKEECHOBEE, OSCEOLA, PALM BEACH, ST LUCIE, TURNPIKE
24	E8S49-R0		40377617217(*)	BROWARD, MIAMI- DADE, PALM BEACH, TURNPIKE

Proposal Note Codes:

Note: () indicates lead project*

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 08200414 Call Order: 001 Proposal: E8S11 District:08

Counties: SEMINOLE

Road Name: RESURFACE SEMINOLE EXPRESSWAY MP 38 TO MP 44.5 - RESURFACING

Limits: 77470000

Project(s): 44029115201(*) Federal Aid No: N/A

Project(s): 44029125201 Federal Aid No: N/A

Project(s): 44029135201 Federal Aid No: N/A

Total Roadway Length:	19.500 Miles	Contract Days:	286
Total Bridge Length:	0.000 Miles	Letting Date:	04/14/20
Total Proposal Length:	19.500 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	30

Proposal Budget Estimate: \$14,941,053.00

Please read the full advertisement

Description:

Work consists of providing all labor, materials, equipment and incidentals necessary for milling and resurfacing with guardrail, guardrail reset, drainage improvements, signing and pavement markings, signalization, lighting, landscaping, and other incidental construction along the Seminole Expressway (SR 417) from MP 37.930 to MP 44.593 in Seminole County. No Pre-Bid Conference. Contractor must be prequalified in Hot Plant-Mixed Bituminous Courses.

The summary of pay items for this project is listed in the Plans.

Call Order: 001 Proposal: E8S11

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44029115201)	LS	1.000
	0101- 1-	MOBILIZATION (44029125201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44029115201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44029125201)	LS	1.000
	0102- 2- 1	SPECIAL DETOUR 1 (44029115201)	LS	1.000
	0102- 2- 2	SPECIAL DETOUR 2 (44029115201)	LS	1.000
	0102- 2- 3	SPECIAL DETOUR 3 (44029115201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	3,400.000
	0102- 60-	WORK ZONE SIGN	ED	35,770.000
	0102- 71- 16	TEMPORARY BARRIER, F&I, FREE STANDING	LF	5,532.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	36,108.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	380.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	1,042.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	16,292.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,779.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	572.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	572.000
	0104- 10- 3	SEDIMENT BARRIER	LF	326.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	224.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	40.000

Call Order: 001 Proposal: E8S11

ALT	Item	Description	Unit	Quantity
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	4.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	184.000
	0107- 1-	LITTER REMOVAL	AC	2,739.000
	0107- 2-	MOWING	AC	2,145.000
	0110- 1- 1	CLEARING & GRUBBING (44029115201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (44029125201)	LS	1.000
	0110- 2- 2	SELECTIVE CLEARING AND GRUBBING, AREAS WITH TREES TO REMAIN	AC	19.410
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	763.000
	0120- 1-	REGULAR EXCAVATION	CY	5,536.600
	0120- 6-	EMBANKMENT	CY	4,014.100
	0160- 4-	TYPE B STABILIZATION	SY	478.000
	0285-704-	OPTIONAL BASE, BASE GROUP 04	SY	478.000
	0285-711-	OPTIONAL BASE, BASE GROUP 11	SY	3,280.000
	0327- 70- 2	MILLING EXIST ASPH PAVT, 3 1/2" AVG DEPTH	SY	4,744.000
	0327- 70- 4	MILLING EXIST ASPH PAVT, 3" AVG DEPTH	SY	29,684.000
	0327- 70- 5	MILLING EXIST ASPH PAVT, 2" AVG DEPTH	SY	20,574.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	68,518.000
	0327- 70- 8	MILLING EXIST ASPH PAVT, 2 1/2" AVG DEPTH	SY	17,744.000
	0327- 70- 9	MILLING EXIST ASPH PAVT, 5 1/4" AVG DEPTH	SY	1,560.000
	0327- 70- 11	MILLING EXIST ASPH PAVT, 2 1/4" AVG DEPTH	SY	160,185.000
	0327- 70- 14	MILLING EXIST ASPH PAVT, 6 1/2" AVG DEPTH	SY	415.000
	0327- 70- 15	MILLING EXIST ASPH PAVT, 2 3/4" AVG DEPTH	SY	27,031.000
	0327- 70- 17	MILLING EXIST ASPH PAVT, 3 1/4" AVG DEPTH	SY	8,507.000
	0327- 70- 18	MILLING EXIST ASPH PAVT, 5 1/2" AVG DEPTH	SY	1,360.000
	0327- 70- 19	MILLING EXIST ASPH PAVT, 3/4" AVG DEPTH	SY	7,960.000
	0327- 70- 20	MILLING EXIST ASPH PAVT, 3 3/4" AVG DEPTH	SY	2,150.000
	0327- 70- 21	MILLING EXIST ASPH PAVT, 7" AVG DEPTH	SY	370.000
	0327- 70- 23	MILLING EXIST ASPH PAVT, 6" AVG DEPTH	SY	1,000.000
	0327- 70- 27	MILLING EXIST ASPH PAVT, 5 3/4" AVG DEPTH	SY	703.000
	0327- 70- 29	MILLING EXIST ASPH PAVT, 6 1/4" AVG DEPTH	SY	1,497.000
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	7,221.200
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	2,392.400
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	23,628.200
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	8,416.600
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	2,736.200
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	3,290.900
	0425- 4-	INLETS, ADJUST	EA	7.000
	0520- 6-	SHOULDER GUTTER- CONCRETE	LF	2,024.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	1,743.000
	0536- 1- 3	GUARDRAIL- ROADWAY, DOUBLE FACE	LF	29,978.000
	0536- 5- 1	RUB RAIL FOR GUARDRAIL, SINGLE SIDED RUB RAIL	LF	29,978.000
	0536- 8- 13	APPROACH TRANSITION CONNECTION TO RIGID BARRIER, FURNISH AND INSTALL, TL-3	EA	27.000
	0536- 73-	GUARDRAIL REMOVAL	LF	2,280.000

Call Order: 001 Proposal: E8S11

ALT	Item	Description	Unit	Quantity
	0536- 85- 20	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE	EA	1.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	1.000
	0536- 85- 27	GUARDRAIL END TREATMENT- DOUBLE FACE APPROACH TERMINAL	EA	4.000
	0538- 1-	GUARDRAIL RESET	LF	3,841.000
	0544- 3- 1	CRASH CUSHION, TL-3, NARROW	EA	7.000
	0546- 72- 1	GROUND-IN RUMBLE STRIPS, 16"	GM	22.249
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	61,375.000
	0571- 1- 11	PLASTIC EROSION MAT, TURF REINFORCED MAT, TYPE 1	SY	1,320.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	170.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	1.000
	0639- 8- 26	ELECTRICAL POWER SERVICE- CONTRIBUTION IN AID OF CONSTRUCTION (CIAC), PROJECT 440291-1-52-01 (DO NOT BID) (44029115201)	LS	1.000
	0695- 1- 1	TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL	EA	4.000
	0695- 6- 12	TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 2 LOOPS	EA	4.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	16.602
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	328.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	138.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	26.178
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	15.823
	0999- 16-	PARTNERING, DO NOT BID (44029115201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44029115201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44029125201)	LS	1.000
Section 0002 Signing				
	0101- 1-	MOBILIZATION (44029135201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44029135201)	LS	1.000
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	12.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	26.000
	0700- 1- 13	SINGLE POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	2.000
	0700- 1- 14	SINGLE POST SIGN, F&I GROUND MOUNT, 31+ SF	AS	5.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	39.000
	0700- 2- 13	MULTI- POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	3.000
	0700- 2- 14	MULTI- POST SIGN, F&I GROUND MOUNT, 31-50 SF	AS	7.000
	0700- 2- 15	MULTI- POST SIGN, F&I GROUND MOUNT, 51-100 SF	AS	21.000
	0700- 2- 16	MULTI- POST SIGN, F&I GROUND MOUNT, 101-200 SF	AS	19.000
	0700- 2- 60	MULTI- POST SIGN, REMOVE	AS	56.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	3.000
	0700- 3-106	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 101-200 SF	EA	2.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	1.000
	0700- 3-202	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 12-20 SF	EA	2.000
	0700- 3-205	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 51-100 SF	EA	14.000
	0700- 3-206	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 101-200 SF	EA	2.000

Call Order: 001 Proposal: E8S11

ALT	Item	Description	Unit	Quantity
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	1.000
	0700- 3-602	SIGN PANEL, REMOVE, 12-20 SF	EA	2.000
	0700- 3-605	SIGN PANEL, REMOVE, 51-100 SF	EA	14.000
	0700- 3-606	SIGN PANEL, REMOVE, 101-200 SF	EA	3.000
	0700- 3-626	SIGN PANEL, REMOVE, 101-200 SF WITH LIGHTING	EA	1.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	106.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44029115201)	LS	1.000
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	0.787
	0711- 11-103	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR INTERCHANGE MARKINGS	GM	2.564
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	328.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	1,642.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	138.000
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	45.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	70.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	214.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	291.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	5.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	15.140
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	13.031
	0711- 15-133	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 12"- APPROACH TO TOLL PLAZA OR 3-9 LANE DROP	GM	0.041
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	15.096
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	1.010
	0711- 16-131	THERMOPLASTIC, OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.030
	0711- 16-133	THERMOPLASTIC, STANDARD-OTHER SURFACES WHITE, SKIP, 12"- APPROACH TO TOLL PLAZA OR 3-9 LANE DROP	GM	0.063
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.804
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.695
	0713-103-103	PERMANENT TAPE, WHITE, SOLID LANE DROP MARKING, 12" FOR CONCRETE BRIDGES	GM	0.046
	0713-103-131	PERMANENT TAPE, WHITE, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	0.742
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.695
	0713-103-331	PERMANENT TAPE, BLACK, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	0.778
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44029135201)	LS	1.000
Section 0003 Lighting				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	20.000

Call Order: 001 Proposal: E8S11

ALT	Item	Description	Unit	Quantity
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	1,540.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	25.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	3.000
	0639- 1-620	ELECTRICAL POWER SERVICE, REMOVE UNDERGROUND	AS	3.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	365.000
	0639- 2- 6	ELECTRICAL SERVICE WIRE, REMOVE	LF	365.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	3.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	3.000
	0715- 1- 13	LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2	LF	6,092.000
	0715- 1- 15	LIGHTING CONDUCTORS, F&I, NO.1/0 - 3/0 (0 to 000)	LF	2,012.000
	0715- 1- 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	LF	1,595.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	3.000
	0715- 7- 41	LOAD CENTER, REMOVE, SECONDARY VOLTAGE	EA	3.000
Section 0004 Signalization				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	258.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	397.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	8.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	13.000

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	08200414	Call Order: 002	Proposal: E8S18	District:08
Counties:	MIAMI-DADE			
Road Name:	RESURFACING AND SAFETY IMPROVEMENTS - HEFT (MIAMI-DADE)			
Limits:	87471000			
Project(s):	44042315201(*)	Federal Aid No:	N/A	
Project(s):	44042325201	Federal Aid No:	N/A	
Total Roadway Length:	9.573 Miles	Contract Days:	322	
Total Bridge Length:	0.295 Miles	Letting Date:	04/14/20	
Total Proposal Length:	9.868 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	30	
Proposal Budget Estimate:	\$12,861,916.00			

Please read the full advertisement

Description:

Work consists of providing all labor, materials, equipment and incidentals necessary for milling and resurfacing, minor widening for auxiliary lanes, guardrail installation and resetting, highway signing and other incidental construction on the Homestead Extension of Floridas Turnpike (HEFT) (SR 821) in Miami-Dade County from Milepost (MP) 0.0 to MP 9.2. The project exception limits are from MP 2.5 to MP 3.75 and MP 5.1 to MP 9.2 for the mainline HEFT only. Improvements on all interchange ramps are included from Milepost 5.1 to 9.2. No Pre-Bid Conference. Contractor must be prequalified in Hot Plant-Mixed Bituminous Courses.

The summary of pay items for this project is listed in the Plans.

Call Order: 002 Proposal: E8S18

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0458- 1- 21	BRIDGE DECK EXPANSION JOINT, REHABILITATION, Poured JOINT WITH BACKER ROD	LF	977.000
	0458- 2-	POLYMER NOSING FOR BRIDGE DECK EXPANSION JOINT	CF	35.700
	0460- 71- 2	METAL TRAFFIC RAILING, STEEL POST AND RAIL	LF	3,116.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (44042315201)	LS	1.000
	0101- 1-	MOBILIZATION (44042325201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44042315201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44042325201)	LS	1.000
	0102- 2- 1	SPECIAL DETOUR 1 (44042315201)	LS	1.000
	0102- 2- 2	SPECIAL DETOUR 2 (44042315201)	LS	1.000
	0102- 2- 3	SPECIAL DETOUR 3 (44042315201)	LS	1.000
	0102- 2- 4	SPECIAL DETOUR 4 (44042315201)	LS	1.000
	0102- 2- 5	SPECIAL DETOUR 5 (44042315201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	2,576.000
	0102- 60-	WORK ZONE SIGN	ED	10,612.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	440.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	8,238.000
	0102- 71- 25	TEMPORARY BARRIER, RELOCATE, ANCHORED	LF	932.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	34,518.000

Call Order: 002 Proposal: E8S18

ALT	Item	Description	Unit	Quantity
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	538.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	552.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	4,177.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	4.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	840.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	958.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	840.000
	0102-913- 21	REMOVABLE TAPE, WHITE, SOLID 6"	GM	0.566
	0102-913- 22	REMOVABLE TAPE, WHITE, 10'-30', 3'-9', 6'-10', or 2'-4' SKIP, 6" WIDE	GM	0.504
	0102-913- 31	REMOVABLE TAPE, YELLOW, SOLID, 6"	GM	0.582
	0104- 10- 3	SEDIMENT BARRIER	LF	77,780.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	4.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	63.000
	0107- 1-	LITTER REMOVAL	AC	2,299.120
	0107- 2-	MOWING	AC	2,004.310
	0110- 1- 1	CLEARING & GRUBBING (44042315201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (44042325201)	LS	1.000
	0110- 2- 2	SELECTIVE CLEARING AND GRUBBING, AREAS WITH TREES TO REMAIN	AC	1.250
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	9.000
	0120- 1-	REGULAR EXCAVATION	CY	3,661.000
	0120- 6-	EMBANKMENT	CY	12,652.000
	0160- 4-	TYPE B STABILIZATION	SY	10,234.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	111.000
	0285-711-	OPTIONAL BASE, BASE GROUP 11	SY	9,393.000
	0327- 70- 4	MILLING EXIST ASPH PAVT, 3" AVG DEPTH	SY	1,538.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	48,759.000
	0327- 70- 11	MILLING EXIST ASPH PAVT, 2 1/4" AVG DEPTH	SY	150,454.000
	0327- 70- 13	MILLING EXIST ASPH PAVT, 1 3/4" AVG DEPTH	SY	24,382.000
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	5,819.200
	0334- 1- 14	SUPERPAVE ASPHALTIC CONC, TRAFFIC D	TN	1,217.700
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	2,108.800
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	6,387.600
	0334- 1- 54	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC D, PG76-22	TN	4,685.300
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	6,131.500
	0337- 7- 81	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-12.5, PG 76-22	TN	176.400
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	639.800
	0425- 1-701	INLETS, GUTTER, TYPE S, <10'	EA	9.000
	0430-173-118	PIPE CULVERT OPTIONAL MATERIAL, ROUND, 18", GUTTER DRAIN	LF	189.000
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	510.000
	0430-613-125	U-ENDWALL, WITH BAFFLES & GRATE, INDEX 261/430-011,1:4 SLOPE,18"PIPE	EA	1.000
	0430-613-225	U-ENDWALL, WITH BAFFLES & GRATE, INDEX 261/430-011,1:3 SLOPE,18"PIPE	EA	3.000
	0520- 2-106	CONCRETE CURB, RIBBON CURB, PROJECT 440423-1-52-01	LF	400.000

Call Order: 002 Proposal: E8S18

ALT	Item	Description	Unit	Quantity
	0520- 6-	SHOULDER GUTTER- CONCRETE	LF	843.000
	0521- 72- 56	SHOULDER CONCRETE BARRIER, 56" PIER PROTECTION BARRIER/CRASH WALL	LF	364.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	5,666.000
	0536- 1- 3	GUARDRAIL- ROADWAY, DOUBLE FACE	LF	3,509.000
	0536- 5- 2	RUBRAIL FOR GUARDRAIL, DOUBLE SIDED RUB RAIL	LF	3,509.000
	0536- 7- 3	SPECIAL GUARDRAIL POST- ENCASED POST FOR SHALLOW MOUNT	EA	5.000
	0536- 8- 13	APPROACH TRANSITION CONNECTION TO RIGID BARRIER, FURNISH AND INSTALL, TL-3	EA	7.000
	0536- 73-	GUARDRAIL REMOVAL	LF	1,515.000
	0536- 85- 20	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE	EA	3.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	7.000
	0536- 85- 27	GUARDRAIL END TREATMENT- DOUBLE FACE APPROACH TERMINAL	EA	1.000
	0546- 72- 1	GROUND-IN RUMBLE STRIPS, 16"	GM	11.197
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	38,678.000
	0581- 1- 1	RELOCATE TREES AND PALMS, PALM, <14' OF CLEAR TRUNK	EA	5.000
	0581- 1- 2	RELOCATE TREES AND PALMS, PALM, >=14' OF CLEAR TRUNK	EA	5.000
	0639- 8- 25	ELECTRICAL POWER SERVICE- CONTRIBUTION IN AID OF CONSTRUCTION (CIAC), PROJECT 440423-1-52-01 (DO NOT BID) (44042325201)	LS	1.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	20.603
	0710- 11-103	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE MARKINGS, 12"	GM	0.820
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	508.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	9.448
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.202
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	6.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	2.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	17.269
	0904-540- 11	HIGH TENSION CABLE BARRIER SYSTEM - REMOVE	LF	3,150.000
	0999- 16-	PARTNERING, DO NOT BID (44042315201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44042315201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44042325201)	LS	1.000
Section 0003 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	50.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	45.000
	0700- 1- 13	SINGLE POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	18.000
	0700- 1- 14	SINGLE POST SIGN, F&I GROUND MOUNT, 31+ SF	AS	5.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	90.000
	0700- 2- 14	MULTI- POST SIGN, F&I GROUND MOUNT, 31-50 SF	AS	6.000
	0700- 2- 15	MULTI- POST SIGN, F&I GROUND MOUNT, 51-100 SF	AS	4.000
	0700- 2- 16	MULTI- POST SIGN, F&I GROUND MOUNT, 101-200 SF	AS	14.000
	0700- 2- 17	MULTI- POST SIGN, F&I GROUND MOUNT, 201-300 SF	AS	1.000

Call Order: 002 Proposal: E8S18

ALT	Item	Description	Unit	Quantity
	0700- 2- 60	MULTI- POST SIGN, REMOVE	AS	26.000
	0700- 3-206	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 101-200 SF	EA	1.000
	0700- 3-207	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 201-300 SF	EA	3.000
	0700- 3-208	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 301-400 SF	EA	1.000
	0700- 3-626	SIGN PANEL, REMOVE, 101-200 SF WITH LIGHTING	EA	1.000
	0700- 3-627	SIGN PANEL, REMOVE PANEL, 201-300 SF WITH LIGHTING	EA	3.000
	0700- 3-628	SIGN PANEL, REMOVE PANEL, 301-400 SF WITH LIGHTING	EA	1.000
	0700- 12- 21	SIGN BEACON, F&I GROUND MOUNT- SOLAR POWERED, ONE BEACON	AS	2.000
	0700- 12- 22	SIGN BEACON, F&I GROUND MOUNT- SOLAR POWERED, TWO BEACONS	AS	1.000
	0700- 13- 12	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 2'	EA	16.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44042315201)	LS	1.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44042325201)	LS	1.000
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	0.031
	0711- 11-103	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR INTERCHANGE MARKINGS	GM	1.095
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	679.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	509.000
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	7.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	24.000
	0711- 11-180	THERMOPLASTIC, STANDARD, WHITE, YIELD LINE	LF	38.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	449.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	10.754
	0711- 15-102	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SOLID, 8"	GM	0.292
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	7.231
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	10.204
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.364
	0713-103-131	PERMANENT TAPE, WHITE, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	0.377
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.289
Section 0004 Lighting				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	14,425.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	897.000
	0630- 2- 15	CONDUIT, FURNISH & INSTALL, BRIDGE MOUNT	LF	560.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	96.000
	0635- 3- 13	JUNCTION BOX, FURNISH & INSTALL, EMBEDDED	EA	74.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	1.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	266.000

Call Order: 002 Proposal: E8S18

ALT	Item	Description	Unit	Quantity
	0639- 3- 60	ELECTRICAL SERVICE DISCONNECT, REMOVE- POLE OR CABINET TO REMAIN	EA	1.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	6,167.000
	0715- 1- 13	LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2	LF	9,717.000
	0715- 1- 14	LIGHTING CONDUCTORS, F&I, INSULATED, NO 1 TO NO 0	LF	53,503.000
	0715- 1- 15	LIGHTING CONDUCTORS, F&I, NO.1/0 - 3/0 (0 to 000)	LF	6,128.000
	0715- 1- 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	LF	59,877.000
	0715- 4- 13	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT	EA	23.000
	0715- 4- 70	LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION	EA	5.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	1.000
	0715- 7- 41	LOAD CENTER, REMOVE, SECONDARY VOLTAGE	EA	2.000
	0715- 11-225	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE, ROADWAY, WALL MOUNT	EA	74.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	23.000
Section 0005 Signalization				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	54.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	324.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	14.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	5.000
	0670- 5-400	TRAFFIC CONTROLLER ASSEMBLY, MODIFY	AS	4.000
Section 0006 Intelligent Transportation System				
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	6.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	15.000
	0630- 2- 30	CONDUIT, FURNISH & INSTALL, RETROFIT/REPLACE ROUTE MARKER, PROJECT 440423-2-52-01	EA	55.000

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: 08200414 Call Order: 003 Proposal: E8S19 District:08

Counties: TURNPIKE

Road Name: NEW DMS SIGNS AND CCTV CAMERA INSTALLATIONS

Limits: 86470000

Project(s): 44363415201 Federal Aid No: N/A

Project(s): 44387815201(*) Federal Aid No: N/A

Total Roadway Length:	121.754 Miles	Contract Days:	290
Total Bridge Length:	0.000 Miles	Letting Date:	04/14/20
Total Proposal Length:	121.754 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	30

Proposal Budget Estimate: \$3,997,478.00

Please read the full advertisement

Description:

Work consists of providing all labor, materials, equipment and incidentals necessary for New DMS Sign Installations at Southern Service Plazas (SR821 and SR91 MM 18 - 185.4) in Miami-Dade County, Broward County, Palm Beach County, St. Lucie County, and Okeechobee County; and Southern Turnpike CCTV Camera Installation (SR91 MM 51 – 106.7 and SR869 MM 0.3 – 1.0) in Broward County and Palm Beach County. No Pre-Bid Conference. Contractor must be prequalified.

The summary of pay items for this project is listed in the Plans.

Call Order: 003 Proposal: E8S19

ALT	Item	Description	Unit	Quantity
Section 0001 Intelligent Transportation System				
	0101- 1-	MOBILIZATION (44363415201)	LS	1.000
	0101- 1-	MOBILIZATION (44387815201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44363415201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44387815201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	302.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	878.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	3.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	14.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	242.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	20.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	20.000
	0104- 10- 3	SEDIMENT BARRIER	LF	5,425.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	1.000
	0110- 2- 2	SELECTIVE CLEARING AND GRUBBING, AREAS WITH TREES TO REMAIN	AC	0.030
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	24,865.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	3,985.000
	0630- 2- 14	CONDUIT, FURNISH & INSTALL, ABOVEGROUND	LF	1,820.000
	0633- 1-121	FIBER OPTIC CABLE, F&I, UNDERGROUND,2-12 FIBERS	LF	3,653.000
	0633- 1-122	FIBER OPTIC CABLE, F&I, UNDERGROUND,13-48 FIBERS	LF	20,441.000
	0633- 1-420	FIBER OPTIC CABLE, RELOCATE, UNDERGROUND	LF	25.000
	0633- 2- 31	FIBER OPTIC CONNECTION, INSTALL, SPLICE	EA	604.000

Call Order: 003 Proposal: E8S19

ALT	Item	Description	Unit	Quantity
	0633- 2- 32	FIBER OPTIC CONNECTION, INSTALL, TERMINATION	EA	60.000
	0633- 3- 11	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE ENCLOSURE	EA	4.000
	0633- 3- 12	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE TRAY	EA	56.000
	0633- 3- 13	FIBER OPTIC CONNECTION HARDWARE, F&I, PRETERMINATED CONNECTOR ASSEMBLY	EA	516.000
	0633- 3- 16	FIBER OPTIC CONNECTION HARDWARE, F&I, PATCH PANEL- FIELD TERMINATED	EA	19.000
	0633- 3- 17	FIBER OPTIC CONNECTION HARDWARE, F&I, CONNECTOR PANEL	EA	48.000
	0633- 3- 42	FIBER OPTIC CONNECTION HARDWARE, RELOCATE SPLICE TRAY	EA	1.000
	0633- 3- 43	FIBER OPTIC CONNECTION HARDWARE, RELOCATE PRETERMINATED CONNECTOR ASSEMBLY	EA	12.000
	0633- 3- 46	FIBER OPTIC CONNECTION HARDWARE, RELOCATE PATCH PANEL- FIELD TERMINATED	EA	1.000
	0633- 3- 51	FIBER OPTIC CONNECTION HARDWARE, ADJUST/MODIFY SPLICE ENCLOSURE	EA	12.000
	0633- 3- 52	FIBER OPTIC CONNECTION HARDWARE, ADJUST/MODIFY SPLICE TRAY	EA	8.000
	0633- 8- 1	MULTI-CONDUCTOR COMMUNICATION CABLE, FURNISH & INSTALL	LF	638.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	132.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	58.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	12.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	25,245.000
	0639- 2- 6	ELECTRICAL SERVICE WIRE, REMOVE	LF	1,868.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	37.000
	0639- 3- 60	ELECTRICAL SERVICE DISCONNECT, REMOVE- POLE OR CABINET TO REMAIN	EA	4.000
	0639- 6- 1	ELECTRICAL POWER SERVICE- TRANSFORMER FURNISH & INSTALL	EA	14.000
	0639- 8- 28	ELECTRICAL POWER SERVICE- CONTRIBUTION IN AID OF CONSTRUCTION (CIAC), PROJECT 443878-1-52-01 (DO NOT BID) (44387815201)	LS	1.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	21.000
	0641- 2- 70	PRESTRESSED CONCRETE POLE, SHALLOW POLE REMOVAL- POLE 30' AND GREATER	EA	1.000
	0641- 3-163	CONCRETE CCTV POLE, FURNISH & INSTALL WITH LOWERING DEVICE, 63'	EA	6.000
	0641- 3-169	CONCRETE CCTV POLE, FURNISH & INSTALL WITH LOWERING DEVICE, 69'	EA	10.000
	0641- 3-175	CONCRETE CCTV POLE, FURNISH & INSTALL WITH LOWERING DEVICE, 75'	EA	2.000
	0660- 3- 41	VEHICLE DETECTION SYSTEM- MICROWAVE, RELOCATE CABINET EQUIPMENT	EA	1.000
	0660- 3- 42	VEHICLE DETECTION SYSTEM - MICROWAVE, RELOCATE, ABOVE GROUND EQUIPMENT	EA	1.000
	0676- 2-122	ITS CABINET, FURNISH & INSTALL, POLE MOUNT WITH SUNSHIELD, 336S, 24" W X 46" H X 22" D	EA	10.000
	0676- 2-600	ITS CABINET- REMOVE	EA	1.000
	0676- 2-800	ITS CABINET, FURNISH & INSTALL, BASE MOUNT WITH SUNSHIELD, P4400/332D, 44" W x 56" H x 29" D, PROJECT 443878-1-52-01	EA	10.000

Call Order: 003 Proposal: E8S19

ALT	Item	Description	Unit	Quantity
	0676- 3- 10	SMALL EQUIPMENT ENCLOSURE, FURNISH AND INSTALL, LESS THAN 10"W X 13"H X 11" D	EA	1.000
	0682- 1-133	ITS CCTV CAMERA, F&I, DOME ENCLOSURE - NON-PRESSURIZED, IP, HIGH DEFINITION	EA	18.000
	0684- 1- 1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	EA	19.000
	0684- 1- 4	MANAGED FIELD ETHERNET SWITCH, RELOCATE	EA	1.000
	0684- 2- 4	DEVICE SERVER, RELOCATE	EA	1.000
	0685- 1- 12	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, ONLINE/DOUBLE CONVERSION	EA	20.000
	0685-511-	SYSTEM AUXILIARIES, POWER DISTRIBUTION UNIT- 443878-1-52-01, ETC	EA	20.000
	0700- 8-135	FRONT ACCESS DYNAMIC MESSAGE SIGN, FURNISH & INSTALL- WITH UPS, FULL COLOR, 51-100 SF	EA	10.000
	0700- 10-121	DMS SUPPORT STRUCTURE, CANTILEVER, UP TO 20 FT	EA	3.000
	0700- 10-122	DMS SUPPORT STRUCTURE, CANTILEVER, 21-30 FT	EA	6.000
	0700- 10-123	DMS SUPPORT STRUCTURE, CANTILEVER, 31-40 FT	EA	1.000
	0999- 16-	PARTNERING, DO NOT BID (44387815201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44363415201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44387815201)	LS	1.000

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	08200414	Call Order: 004	Proposal: E8S45-R0	District:08
Counties:	HERNANDO, HILLSBOROUGH, PASCO, POLK, TURNPIKE			
Road Name:	ASPHALT REPAIRS - ZONE 4			
Limits:	Midpoint			
Project(s):	19077445205(*)	Federal Aid No: N/A		
Total Roadway Length:	0.000 Miles	Contract Days:	365	
Total Bridge Length:	0.000 Miles	Letting Date:	04/14/20	
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	14	

Proposal Budget Estimate: \$250,000.00

Please read the full advertisement

Description:

The work specified in this contract consists of providing all labor, materials, equipment, and incidentals necessary to perform maintenance and repair of asphalt pavement deficiencies and defects, including replacing existing asphalt pavement, providing painted pavement markings, and raised pavement markers at various locations on the Polk Parkway, Milepost (MP) 0.0 to 24.4, Veterans Spur, MP 0.0 to 3.0, and Suncoast Parkway MP 17.5 to 54.9.

Prior to beginning work under this Contract, the Contractor shall submit to the Engineer for approval, two copies of the Contractor's proposed plan and methods for performing the work, including a listing of equipment and personnel anticipated for use.

The Contractor shall perform all work during day and night hours in accordance with the Turnpike Lane Closure Policy.

No U-turns shall be permitted as a condition of this Contract, except at Service Plazas.

Night work shall be performed between the hours of 9:00 PM to 5:00 AM, Monday through Thursday.

Mobilization item shall be full compensation for mobilization/demobilization per Location, for a routine response authorized by a work order. A Location is defined as item/items of work authorized by a single work order for work to be accomplished within a two (2)-mile length of highway.

NO PRE-BID CONFERENCE WILL BE HELD FOR THIS PROJECT.

CONTRACTOR EXPERIENCE DOCUMENTATION: Expertise and Experience is required in the performance of Asphalt Paving. The Experience in Asphalt Paving Form (850-070-01) must be filled out and submitted with the bid to be reviewed by the Department. "If a Contractor is presently prequalified with the Department in Hot Plant Mix Bituminous Course, it is not necessary to submit the form."

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Call Order: 004 Proposal: E8S45-R0

ALT	Item	Description	Unit	Quantity
Section 0001 MAINTENANCE SUPPORT SERVICES (MH)				
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	120.000
	0327- 70- 1	MILLING EXIST ASPH PAVT, 1" AVG DEPTH	SY	3,650.000
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	150.000
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	5.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	0.500
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	0.500
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.500
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	10.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	10.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	0.500
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.500
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	0.500
	E101- 1- 1	MOBILIZATION	LO	5.000
	E101- 72-	MOBILIZATION (EMERGENCY RESPONSE)	EA	1.000
	E102- 1- 3	MAINTENANCE OF TRAFFIC (SITE SPECIFIC)	LO	6.000
	E706- 1- 42	REFLECTIVE PAVEMENT MARKER(REMOVE AND REPLACE)(CLASS B)	EA	250.000

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	08200414	Call Order: 005	Proposal: E8S46-R0	District:08
Counties:	INDIAN RIVER, MARTIN, OKEECHOBEE, OSCEOLA, PALM BEACH, ST LUCIE, TURNPIKE			
Road Name:	ASPHALT REPAIRS - ZONE 2			
Limits:	Midpoint			
Project(s):	19077445206(*)	Federal Aid No: N/A		
Total Roadway Length:	0.000 Miles	Contract Days:	365	
Total Bridge Length:	0.000 Miles	Letting Date:	04/14/20	
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	14	

Proposal Budget Estimate: \$300,000.00

Please read the full advertisement

Description:

The work specified in this contract consists of providing all labor, materials, equipment, and incidentals necessary to perform maintenance and repair of asphalt pavement deficiencies and defects, including replacing existing asphalt pavement, providing painted pavement markings, and raised pavement markers at various locations on the Florida's Turnpike (SR-91), Mile Post (MP) 100.0 to 200.0.

Prior to beginning work under this Contract, the Contractor shall submit to the Engineer for approval, two copies of the Contractor's proposed plan and methods for performing the work, including a listing of equipment and personnel anticipated for use.

The Contractor shall perform all work during day and night hours in accordance with the Turnpike Lane Closure Policy.

No U-turns shall be permitted as a condition of this Contract, except at Service Plazas.

Night work shall be performed between the hours of 9:00 PM to 5:00 AM, Monday through Thursday.

Mobilization item shall be full compensation for mobilization/demobilization per Location, for a routine response authorized by a work order. A Location is defined as item/items of work authorized by a single work order for work to be accomplished within a two (2)-mile length of highway.

NO PRE-BID CONFERENCE WILL BE HELD FOR THIS PROJECT.

CONTRACTOR EXPERIENCE DOCUMENTATION: Expertise and Experience is required in the performance of Asphalt Paving. The Experience in Asphalt Paving Form (850-070-01) must be filled out and submitted with the bid to be reviewed by the Department. "If a Contractor is presently prequalified with the Department in Hot Plant Mix Bituminous Course, it is not necessary to submit the form."

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Call Order: 005 Proposal: E8S46-R0

ALT	Item	Description	Unit	Quantity
Section 0001 MAINTENANCE SUPPORT SERVICES (MH)				
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	150.000
	0327- 70- 1	MILLING EXIST ASPH PAVT, 1" AVG DEPTH	SY	7,300.000
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	265.000
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	5.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	1.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	1.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	1.000
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	10.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	10.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	1.000
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	1.000
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	1.000
	E101- 1- 1	MOBILIZATION	LO	4.000
	E101- 72-	MOBILIZATION (EMERGENCY RESPONSE)	EA	1.000
	E102- 1- 3	MAINTENANCE OF TRAFFIC (SITE SPECIFIC)	LO	5.000
	E706- 1- 42	REFLECTIVE PAVEMENT MARKER(REMOVE AND REPLACE)(CLASS B)	EA	650.000

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: 08200414 Call Order: 006 Proposal: E8S49-R0 District:08
 Counties: BROWARD, MIAMI-DADE, PALM BEACH, TURNPIKE
 Road Name: HERBICIDE APPLICATION - ROADWAY & BRIDGES - ZONE 1
 Limits: Midpoint
 Project(s): 40377617217(*) Federal Aid No: N/A
 Total Roadway Length: 0.000 Miles Contract Days: 365
 Total Bridge Length: 0.000 Miles Letting Date: 04/14/20
 Total Proposal Length: 0.000 Miles Contract Execution Days: 10
 Special Start Date: N/A
 Aquis/Flexible Start Time: 14

Proposal Budget Estimate: \$125,000.00

Please read the full advertisement

Description:

The work specified in this contract consists of providing all labor, materials, equipment, and incidentals necessary to control weeds and grass by chemical vegetation control associated with roadway and bridge structures at various locations on Homestead Extension of Florida's Turnpike (SR 821), Milepost (MP) 0.0 to 46.5; Florida's Turnpike (SR 91), MP 0.0X to 100.0, and Sawgrass Expressway (SR 869), MP 0.0 to 22.5.

Prior to beginning work under this Contract, the Contractor shall submit to the Engineer for approval, two copies of the Contractor's proposed plan and methods for performing the work, including a listing of equipment and personnel anticipated for use.

The Contractor shall perform all work during day hours in accordance with the Turnpike Lane Closure Policy.

No U-turns shall be permitted as a condition of this Contract, except at Service Plazas.

Florida Department of Agriculture Commercial Applicator's license with the categories of licensure in Right-of-Way Pest Control and Aquatic Pest Control is required to bid for this contract.

NO PRE-BID CONFERENCE WILL BE HELD FOR THIS PROJECT.

Call Order: 006 Proposal: E8S49-R0

ALT	Item	Description	Unit	Quantity
Section 0001 CHEM WEED AND GRASS CONTROL (GA)				
	E580-337- 2	HERBICIDE (STRIP APPLICATION)	AC	1,010.000
	E580-337- 6	HERBICIDE (HAND APPLICATION)	AC	714.000