



Florida Department of Transportation

RON DESANTIS
GOVERNOR

Florida's Turnpike Enterprise
P.O. Box 613069, Ocoee, FL 34761
407-532-3999

KEVIN J. THIBAUT, P.E.
SECRETARY

ADDENDUM No. 2

DATE: August 20, 2020

TO: PROPOSERS

FROM: *RMM* Richard M. Nethercote, Jr.
District Contracts Administrator
Florida's Turnpike Enterprise

SUBJECT: **SUBJECT:** Contract No.: E8S55
Financial Project Nos.: 440700-1-52-01; 440700-2-52-01
County(ies): Osceola
Project Name: Resurface & Safety IMP. TPK ML, MP 190.5 to 198.5

BIDS TO BE RECEIVED: August 31, 2020 at 2:30 P.M Local Time

Proposers and other interested parties are informed that the above referenced documents are hereby revised, changed and supplemented as set forth below:

PLANS AND PAY ITEMS REVISIONS

Plan sheets and Pay Items for the above-mentioned project have been revised. Please go to the Online Ordering Web Site at <https://fdotwp1.dot.state.fl.us/contractproposalprocessingonlineordering/> to download the Plans Revision from your Order History. Please substitute these sheets for the like-numbered sheets you now have. See the attached Revision Memo for a complete listing of Plans and Pay Items Revisions.

AMENDMENT NOTIFICATION

If you are a **BID DOCUMENT HOLDER** for the subject project, please go to the Online Ordering Web Site at <https://fdotwp1.dot.state.fl.us/contractproposalprocessingonlineordering/> to download **E8S55** with "File Type" **.002x** for this Bid Document from your Order History.

If you are a **BID DOCUMENT HOLDER**, in Expedite Bid open the Acceptance of Bidding Acknowledgements folder to confirm your acknowledgement of Amendment and Addenda Files. Failure to load all amendment files will cause the bid to be rejected.

If you have any questions regarding this information, please do not hesitate to contact Rich Nethercote at 407-264-3885.



Florida Department of Transportation

RON DESANTIS
GOVERNOR

605 Suwannee Street
Tallahassee, FL 32399-0450

KEVIN THIBAUT
SECRETARY

TRANSMITTAL OF CONTRACT ADDENDUM

Contract No. **E8S55**
 Letting August 2020
 FPID(s) 440700-1-52-01 + 440700-2-52-01
 Description Resurface & Safety Improvements Turnpike Mainline MP 190.5 – 198.5
 County Osceola

Contract Addendum No. 2 includes: *See Page 2 for details*

- ✓ Digitally signed + sealed Contract Plan Revision No. 1 (PDF file)
- ✓ Design + engineering data (CADD-Rev1.zip file)

Contract time revised No ___ Yes x If yes, 484 total calendar days

- ✓ Addendum package is complete, has no known errors or omissions, has been reviewed for constructability and biddability, and is ready for distribution to contract bidders.

CONCURRENCE:



Turnpike Program Management Administrator

DATE: 2020-08-20

CONTRACT ADDENDUM INCLUDES:

PLAN REVISIONS	
SHEET	DESCRIPTION OF MODIFICATION
1	Signature sheet 2A added to Index of Roadway Plans.
2A	Signature sheet 2A added to Roadway Plans.
3 - 7	Summary of Pay item tables have been updated.
14	Off-Ramp Shoulder Pavement limits from Sta. 325+00 to Sta. 327+79.39 has been added to Typical Section 8.
18	L3 Pavement limits from Sta. 1067+40.89 to Sta. 1074+59.64 will be added to Sheet 18.
28	Shoulder Lane Resurfacing (IR) limits is revised from Sta. 1073+00 to Sta. 1072+00.
28 - 29	Inside Shoulder Lane (IR) overbuild is revised to "Type SP Overbuild (Traffic D) (PG 76-22)" to match top SP lift.
38	Travel Lane Resurfacing (L2) Label is revised to reference (L3).
100	Type SP Structural Course (Traffic D) resurfacing & widening is revised to Type SP Structural Course (Traffic C) within "DETAIL A-A – TANDEM TRUCK PARKING LOT" Tandem Truck Parking Lot Milling & Resurfacing pattern is added to the plan sheet. Tandem Truck Parking Lot pavement design is revised to mill 5-inch and resurface with 4.00" Type B-12.5 & 1.00" Type SP Structural Course (Traffic C).
101	Special Traffic Separator Detail Added. Concrete traffic separator replacement added to plan sheet.
340 - 341	Revised General and Phase notes based on responses to questions.
342	Added temporary construction U-turn at median openings detail.
343	Revised detail to show ¾" resurfacing along the inside shoulder.
343A – 343C	Add sheets based on changes to overall phasing.
344 – 347	Revised Stage number based on changes to overall phasing.
348	Sheet removed based on changes to overall phasing.
349	Removed temporary overbuild from the outside shoulders.
351	Removed temporary overbuild from the outside shoulders.
352	Removed temporary overbuild from the outside shoulders. Clarified TTCP requirements for the two SB lanes.
353	Removed temporary overbuild from the outside shoulders.
356	Removed temporary overbuild from the outside shoulders.
358	Removed temporary overbuild from the outside shoulders. Clarified TTCP requirements for two lane sections.
359	Removed temporary overbuild from the outside shoulders.
361 – 362	Removed temporary overbuild from the outside shoulders. Extended work zone to include median guardrail.
364 – 365	Removed temporary overbuild from the outside shoulders.
372A – 372L	Added sheet to show deep milling and resurfacing in Phase 1.
373 – 379	Revised Stage number based on changes to overall phasing Also clarified TTCP design based on responses to questions.
380 – 397	Removed deep milling from work zones as this was constructed during Phase 1. Also clarified TTCP design based on responses to questions.
400 - 424	Revised Stage number based on changes to overall phasing.

PLAN REVISIONS	
SHEET	DESCRIPTION OF MODIFICATION
SQ-1	Index of Summary of Quantities was updated.
SQ-1 – SQ-2	Pay Item No. 0102-014-000 has been added to SQ sheets. Quantity revision for pay item 0102-001-000. Quantity revision for pay item 0102-060-000. Quantity revision for pay item 0102-074-001. Quantity revision for pay item 0102-076-000. Quantity revision for pay item 0102-078-000. Quantity revision for pay item 0102-099-000. Quantity revision for pay item 0102-115-000. Quantity revision for pay item 0102-150-001. Quantity revision for pay item 0102-150-002. Quantity revision for pay item 0710-011-101. Quantity revision for pay item 0710-011-131. Quantity revision for pay item 0710-011-201.
SQ-2 – SQ-6	Summary of Quantity Tables were reorganized.
SQ-3	Quantity revision for pay item 0102-002-200.
SQ-11	Quantity revision for pay item 0285-701-000. Quantity revision for pay item 0327-070-001.
SQ-12	Quantity revision for pay item 0327-070-010.
SQ-14	Quantity revision for pay item 0334-001-012.
SQ-15	Quantity revision for pay item 0334-001-014.
SQ-16 - SQ-17	Quantity revision for pay item 0334-001-053.
SQ-17 - SQ-19	Quantity revision for pay item 0334-001-054.
SQ-25	Pay item no. 0520-070-000 added.
SQ-26 - SQ-28	Pay item no. 0536-005-002 is revised to pay item no. 0536-005-001.
SQ-29	Quantity revision for pay item 0570-001-002.

PAY ITEMS + QUANTITIES (AASHTOWare PrP) – FPID 440700-1-52-01					
COMPONENT	PAY ITEM	SHEET	ADD MOD DEL	OLD QUANTITY	NEW QUANTITY
MAINTENANCE OF TRAFFIC	0102-001-000	4	MOD	1 LS / 515 Days	1 LS / 484 Days
SPECIAL DETOUR – TEMP. PAV'T	0102-002-200	4	MOD	1 LS / 43723 SY	1 LS / 43501 SY
TRAFFIC CONTROL OFFICER	0102-014-000	4	ADD	0.000 HR	8989.000 HR
WORK ZONE SIGN	0102-060-000	4	MOD	18620.000 ED	42309.000 ED
CHANNELIZING DEVICE - TYPES I, II, DI, VP, DRUM, OR LCD	0102-074-001	4	MOD	239340.000 ED	224895.000 ED
ARROW BOARD / ADVANCE WARNING ARROW PANEL	0102-076-000	4	MOD	642.000 ED	2486.000 ED

PAY ITEMS + QUANTITIES (AASHTOWare PrP) – FPID 440700-1-52-01					
COMPONENT	PAY ITEM	SHEET	ADD MOD DEL	OLD QUANTITY	NEW QUANTITY
TEMPORARY RETRO-REFLECTIVE PAVEMENT MARKER	0102-078-000	4	MOD	4520.000 EA	4877.000 EA
PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	0102-099-000	4	MOD	1220.000 ED	2401.000 ED
CHANNELIZING DEVICE, TYPE III, 6'	0102-115-000	4	MOD	610.000 ED	616.000 ED
PORTABLE REGULATORY SIGN	0102-150-001	4	MOD	1828.000 ED	1803.000 ED
RADAR SPEED DISPLAY UNIT	0102-150-002	4	MOD	1828.000 ED	1803.000 ED
OPTIONAL BASE, BASE GROUP 01	0285-701-000	4	MOD	4110.000 SY	7265.000 SY
MILLING EXIST ASPH PAVT, 1" AVG DEPTH	0327-070-001	4	MOD	4235.000 SY	1080.000 SY
MILLING EXIST ASPH PAVT, 5" AVG DEPTH	0327-070-010	4	MOD	10746.000 SY	13901.000 SY
SUPERPAVE ASPHALT CONCRETE, TRAFFIC B	0334-001-012	5	MOD	9916.000 TN	9824.000 TN
SUPERPAVE ASPHALT CONCRETE, TRAFFIC D	0334-001-014	5	MOD	22563.100 TN	22350.200 TN
SUPERPAVE ASPHALT CONCRETE, TRAFFIC C, PG 76-22	0334 -001-053	5	MOD	996.600 TN	1230.400 TN
SUPERPAVE ASPHALT CONCRETE, TRAFFIC D, PG 76-22	0334-001-054	5	MOD	26021.000 TN	26631.700 TN
PAINTED PAVEMENT MARKINGS, STANDARD, WHITE SOLID, 6"	0710-011-101	6	MOD	44.853 GM	45.696 GM
PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	0710-011-131	6	MOD	32.794 GM	36.706 GM
PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	0710-011-201	6	MOD	17.303 GM	17.587 GM

PAY ITEMS + QUANTITIES (AASHTOWare PrP) – FPID 440700-2-52-01					
COMPONENT	PAY ITEM	SHEET	ADD MOD DEL	OLD QUANTITY	NEW QUANTITY
MAINTENANCE OF TRAFFIC	0102-001-000	4	MOD	1 LS / 515 Days	1 LS / 484 Days
CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH	0520-070-000	5	ADD	0.000 SY	49.000 SY
RUBRAIL FOR GUARDRAIL, SINGLE SIDED RUB RAIL	0536-005-001	5	ADD	0.000 LF	41033.000 LF
RUBRAIL FOR GUARDRAIL, DOUBLE SIDED RUB RAIL	0536-005-002	5	DEL	41033.000 LF	0.000 LF
PERFORMANCE TURF, SOD	0570-001-002	6	MOD	109414.000 SY	121051.000 SY