

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 08201208 Call Order: 001 Proposal: E8S51 District:08

Counties: POLK

Road Name: ALL ELECTRONIC TOLL (AET) CONVERSION - POLK PKWY

Limits: 16470000

Project(s): 44085715201(*) Federal Aid No: N/A

Total Roadway Length:	60.785 Miles	Contract Days:	1086
Total Bridge Length:	0.122 Miles	Letting Date:	12/08/20
Total Proposal Length:	60.907 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	60

Proposal Budget Estimate: \$34,368,351.00

Please read the full advertisement

Description:

Work consists of providing all labor, materials, equipment and incidentals necessary for the converting of the Polk Parkway (SR 570) to an All Electronic Tolling (AET) facility in Polk County. The project limits are between mileposts 0 to 18. The project consists of replacing the existing mainline toll plazas to new AET gantries and the existing ramps will be converted to AET Lite. Work includes roadway, drainage, ITS, lighting and signing and pavement marking associated with the AET conversions. No Pre-Bid Conference. Contractor must be prequalified.
 The summary of pay items for this project is listed in the Plans.

Call Order: 001 Proposal: E8S51

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0458- 1- 21	BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITH BACKER ROD	LF	105.000
	0458- 1- 22	BRIDGE DECK EXPANSION JOINT, REHABILITATION, STRIP SEAL	LF	192.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (44085715201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44085715201)	LS	1.000
	0102- 2-200	SPECIAL DETOUR- TEMPORARY PAVEMENT (44085715201)	LS	1.000
	0102- 2-300	SPECIAL DETOUR- TEMPORARY EARTHWORK/BASE (44085715201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	1,080.000
	0102- 60-	WORK ZONE SIGN	ED	100,822.000
	0102- 62-	BARRIER MOUNTED WORK ZONE SIGN- INDEX 11871/700-013	ED	1,600.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	903.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	2,020.000
	0102- 71- 16	TEMPORARY BARRIER, F&I, FREE STANDING	LF	23,461.000
	0102- 71- 26	TEMPORARY BARRIER, RELOCATE, FREE STANDING	LF	14,986.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	201,122.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	1,200.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	352.000
	0102- 78-	TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER	EA	28,051.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	36.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	4,325.000
	0102-115-	TYPE III BARRICADE	ED	1,603.000

Call Order: 001 Proposal: E8S51

ALT	Item	Description	Unit	Quantity
	0104- 10- 3	SEDIMENT BARRIER	LF	64,404.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	219.000
	0107- 1-	LITTER REMOVAL	AC	1,031.950
	0107- 2-	MOWING	AC	816.260
	0110- 1- 1	CLEARING & GRUBBING (44085715201)	LS	1.000
	0110- 2- 2	SELECTIVE CLEARING AND GRUBBING, AREAS WITH TREES TO REMAIN	AC	6.660
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	21,456.000
	0110- 21-	TREE PROTECTION BARRIER	LF	33,015.000
	0110- 22-	TREE ROOT AND BRANCH PRUNING	EA	449.000
	0110- 23-	TREE REMOVAL	EA	9.000
	0120- 1-	REGULAR EXCAVATION	CY	39,236.200
	0120- 4-	SUBSOIL EXCAVATION	CY	704.100
	0120- 6-	EMBANKMENT	CY	12,647.800
	0120- 74-	SURCHARGE EMBANKMENT	CY	9,301.200
	0141- 70-	SETTLEMENT PLATE ASSEMBLY	AS	10.000
	0144- 1- 1	DIGITAL INCLINOMETER CASING, VERTICAL	LF	110.000
	0145- 2-	GEOSYNTHETIC REINFORCED FOUNDATION OVER SOFT SOIL	SY	2,634.000
	0160- 4-	TYPE B STABILIZATION	SY	47,077.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	20,355.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	20,359.000
	0285-711-	OPTIONAL BASE, BASE GROUP 11	SY	3,266.000
	0327- 70- 1	MILLING EXIST ASPH PAVT, 1" AVG DEPTH	SY	27,331.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	66,567.000
	0327- 70- 7	MILLING EXIST ASPH PAVT, 4" AVG DEPTH	SY	11,861.000
	0327- 70- 11	MILLING EXIST ASPH PAVT, 2 1/4" AVG DEPTH	SY	3,467.000
	0327- 70- 19	MILLING EXIST ASPH PAVT, 3/4" AVG DEPTH	SY	15,630.000
	0327- 70- 20	MILLING EXIST ASPH PAVT, 3 3/4" AVG DEPTH	SY	16,876.000
	0327- 70- 22	MILLING EXISTING ASPHALT PAVEMENT, 4 1/4" AVG DEPTH	SY	40,252.000
	0334- 1- 11	SUPERPAVE ASPHALTIC CONC, TRAFFIC A	TN	2,790.600
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	3,247.800
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	9,954.400
	0334- 1- 14	SUPERPAVE ASPHALTIC CONC, TRAFFIC D	TN	4,928.700
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	1,044.500
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	4,726.200
	0334- 1- 54	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC D, PG76-22	TN	2,392.500
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	3,349.900
	0337- 7- 81	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-12.5, PG 76-22	TN	6,583.800
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	183.300
	0337- 7- 85	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC D, FC-12.5, PG 76-22	TN	86.200
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	393.700
	0425- 1-541	INLETS, DT BOT, TYPE D, <10'	EA	12.000
	0425- 1-543	INLETS, DITCH BOTTOM, TYPE D, J BOT, <10'	EA	1.000

Call Order: 001 Proposal: E8S51

ALT	Item	Description	Unit	Quantity
	0425- 1-701	INLETS, GUTTER, TYPE S, <10'	EA	3.000
	0425- 1-703	INLETS, GUTTER, TYPE S, J BOTTOM <10'	EA	1.000
	0425- 2- 61	MANHOLES, P-8, <10'	EA	3.000
	0430-175-115	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 15"S/CD	LF	16.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	416.000
	0430-175-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	72.000
	0430-175-242	PIPE CULVERT, OPT MATERIAL, OTHER SHAPE - ELIP/ARCH, 42"S/CD	LF	29.000
	0442- 70-	VERTICAL DRAINAGE WICKS	LF	13,280.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	1,158.000
	0520- 6-	SHOULDER GUTTER- CONCRETE	LF	1,184.000
	0521- 1- 11	MEDIAN CONCRETE BARRIER, 38" HEIGHT	LF	666.000
	0521- 1- 12	MEDIAN CONCRETE BARRIER, SHORT GRADE-SEPARATED	LF	72.000
	0521- 1- 13	MEDIAN CONCRETE BARRIER, TALL GRADE-SEPARATED	LF	182.000
	0521- 1- 14	MEDIAN CONCRETE BARRIER, VARIABLE SECTION WIDTH FOR SIGN OR PIER SHIELDING	LF	328.000
	0521- 72- 40	SHOULDER CONCRETE BARRIER, 38" OR 44" HEIGHT	LF	156.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	3,457.000
	0536- 1- 3	GUARDRAIL- ROADWAY, DOUBLE FACE	LF	4,909.000
	0536- 8- 13	APPROACH TRANSITION CONNECTION TO RIGID BARRIER, FURNISH AND INSTALL, TL-3	EA	6.000
	0536- 73-	GUARDRAIL REMOVAL	LF	3,375.000
	0536- 85- 20	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE	EA	7.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	9.000
	0536- 85- 27	GUARDRAIL END TREATMENT- DOUBLE FACE APPROACH TERMINAL	EA	1.000
	0536- 85- 29	GUARDRAIL END TREATMENT- DOUBLE FACE TRAILING ANCHORAGE	EA	2.000
	0538- 1-	GUARDRAIL RESET	LF	106.000
	0544- 3- 1	CRASH CUSHION, TL-3, NARROW	EA	1.000
	0546- 72- 1	GROUND-IN RUMBLE STRIPS, 16"	GM	9.257
	0550- 10-220	FENCING, TYPE B, 5.1-6.0', STANDARD	LF	596.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	193,957.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	18.512
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	1.174
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	1.863
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	22.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	8.332
	0710- 11-203	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 12"	GM	0.443
	0999- 16-	PARTNERING, DO NOT BID (44085715201)	LS	1.000
	0999- 20- 1	DISPUTES REVIEW BOARD, MEETING- DO NOT BID	DA	11.000
	0999- 20- 2	DISPUTES REVIEW BOARD, HEARING- DO NOT BID	EA	2.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44085715201)	LS	1.000

Call Order: 001 Proposal: E8S51

ALT	Item	Description	Unit	Quantity
	Section 0003 Signing			
	0630- 2- 16	CONDUIT, FURNISH & INSTALL, EMBEDDED CONCRETE BARRIERS AND TRAFFIC RAILINGS	LF	337.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	5.000
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	8.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	43.000
	0700- 1- 13	SINGLE POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	72.000
	0700- 1- 21	SINGLE POST SIGN, F&I BARRIER MOUNT INDEX 11871/700-013 UP TO 12 SF	AS	25.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	147.000
	0700- 2- 15	MULTI- POST SIGN, F&I GROUND MOUNT, 51-100 SF	AS	12.000
	0700- 2- 16	MULTI- POST SIGN, F&I GROUND MOUNT, 101-200 SF	AS	40.000
	0700- 2- 17	MULTI- POST SIGN, F&I GROUND MOUNT, 201-300 SF	AS	1.000
	0700- 2- 18	MULTI- POST SIGN, F&I GROUND MOUNT, 301-400 SF	AS	8.000
	0700- 2- 60	MULTI- POST SIGN, REMOVE	AS	90.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	24.000
	0700- 3-203	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 21-30 SF	EA	17.000
	0700- 3-205	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 51-100 SF	EA	1.000
	0700- 3-206	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 101-200 SF	EA	18.000
	0700- 3-207	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 201-300 SF	EA	6.000
	0700- 3-208	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 301-400 SF	EA	5.000
	0700- 3-209	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 401-500 SF	EA	7.000
	0700- 3-210	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 501-600 SF	EA	3.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	48.000
	0700- 3-602	SIGN PANEL, REMOVE, 12-20 SF	EA	7.000
	0700- 3-603	SIGN PANEL, REMOVE, 21-30 SF	EA	7.000
	0700- 3-605	SIGN PANEL, REMOVE, 51-100 SF	EA	1.000
	0700- 3-606	SIGN PANEL, REMOVE, 101-200 SF	EA	8.000
	0700- 3-607	SIGN PANEL, REMOVE, 201-300 SF	EA	3.000
	0700- 3-608	SIGN PANEL, REMOVE, 301-400 SF	EA	1.000
	0700- 3-625	SIGN PANEL, REMOVE, 51-100 SF WITH LIGHTING	EA	6.000
	0700- 3-626	SIGN PANEL, REMOVE, 101-200 SF WITH LIGHTING	EA	23.000
	0700- 3-627	SIGN PANEL, REMOVE PANEL, 201-300 SF WITH LIGHTING	EA	11.000
	0700- 3-628	SIGN PANEL, REMOVE PANEL, 301-400 SF WITH LIGHTING	EA	2.000
	0700- 3-629	SIGN PANEL, REMOVE PANEL, 401-500 SF WITH LIGHTING	EA	3.000
	0700- 4-112	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, CANTILEVER, 21-30 FT	EA	2.000
	0700- 4-113	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, CANTILEVER, 31-40 FT	EA	3.000
	0700- 4-114	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, CANTILEVER, 41-50 FT	EA	18.000
	0700- 4-125	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, SPAN, 51-100 FT	EA	1.000
	0700- 4-126	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, SPAN, 101-150 FT	EA	1.000
	0700- 4-610	OVERHEAD STATIC SIGN STRUCTURE, REMOVE CANTILEVER	EA	11.000
	0700- 4-620	OVERHEAD STATIC SIGN STRUCTURE, REMOVE SPAN	EA	8.000

Call Order: 001 Proposal: E8S51

ALT	Item	Description	Unit	Quantity
	0700- 4-640	OVERHEAD STATIC SIGN STRUCTURE, REMOVE BRIDGE MOUNT	EA	16.000
	0700- 13- 12	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 2'	EA	2.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	336.000
	0705- 11-113	DELINEATOR, FLEXIBLE HIGH PERFORMANCE 36" MANAGED LANES- EXPRESS LANE MARKER, PROJECT 440857-1-52-01	EA	241.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44085715201)	LS	1.000
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	0.734
	0711- 11-103	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR INTERCHANGE MARKINGS	GM	1.222
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	528.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	2,966.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	168.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.002
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	5.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	55.000
	0711- 11-180	THERMOPLASTIC, STANDARD, WHITE, YIELD LINE	LF	50.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	365.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	2.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	7.034
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	5.653
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	6.475
	0711- 15-231	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SKIP, 6"	GM	0.296
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	4.602
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.570
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	3.713
	0713-103-131	PERMANENT TAPE, WHITE, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	2.234
	0713-103-331	PERMANENT TAPE, BLACK, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	2.229
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	1,011.000
	0715- 1- 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	LF	1,578.000
Section 0004 Lighting				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	22,222.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	1,081.000
	0630- 2- 16	CONDUIT, FURNISH & INSTALL, EMBEDDED CONCRETE BARRIERS AND TRAFFIC RAILINGS	LF	171.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	173.000

Call Order: 001 Proposal: E8S51

ALT	Item	Description	Unit	Quantity
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	1.000
	0639- 6- 1	ELECTRICAL POWER SERVICE- TRANSFORMER FURNISH & INSTALL	EA	1.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	94,111.000
	0715- 1- 13	LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2	LF	41,647.000
	0715- 1- 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	LF	162,628.000
	0715- 4- 13	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT	EA	30.000
	0715- 4- 14	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 45' MOUNTING HEIGHT	EA	103.000
	0715- 4- 70	LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION	EA	124.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	1.000
	0715- 7- 21	LOAD CENTER, REWORK, SECONDARY VOLTAGE	EA	2.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	133.000
Section 0005 Architectural				
	0110- 1- 1	CLEARING & GRUBBING (44085715201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	7,560.000
	0110- 86- 5	DELIVERY OF SALVAGEABLE MATERIAL- GENERATOR AND TOLL EQUIPMENT, PROJECT 440857-1-52-01 (44085715201)	LS	1.000
	0121- 70- 11	FLOWABLE FILL, TUNNEL FILLING, PROJECT 440857-1-52-01	CY	2,812.500
	0400- 2- 8	CONCRETE CLASS II, BULKHEAD	CY	11.900
	0519- 78-	BOLLARDS	EA	60.000
	0520- 2-103	CONCRETE CURB, TOLL HEADER CURB, PROJECT 440857-1-52-01	LF	600.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	9.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	602.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	2,535.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	3,632.000
	0635- 2-105	PULL & SPLICE BOX, F&I, HS-20 24" X 36", PROJECT 440857-1-52-01	EA	6.000
	0635- 2-106	PULL & SPLICE BOX, F&I, HS-20 30" X 48", PROJECT 440857-1-52-01	EA	54.000
	0635- 2-107	PULL & SPLICE BOX, F&I, HS-20 12" X 12", PROJECT 440857-1-52-01	EA	12.000
	0639- 5- 20	EMERGENCY GENERATOR- PERMANENT, 50 KW, PROJECT 440857-1-52-01	EA	3.000
	0735- 1- 3	TOLL GANTRY, ACCESSIBLE, FURNISH AND INSTALL, SPAN, 151-200', PROJECT 440857-1-52-01	EA	3.000
	0735- 74- 1	TOLL PLAZA, LOCATION 1 (44085715201)	LS	1.000
	0735- 74- 2	TOLL PLAZA, LOCATION 2 (44085715201)	LS	1.000
	0735- 74- 3	TOLL PLAZA, LOCATION 3 (44085715201)	LS	1.000
	0735- 88- 1	TOLL PLAZA MODIFY EXISTING, LOCATION 1 (44085715201)	LS	1.000
	0735- 88- 2	TOLL PLAZA MODIFY EXISTING, LOCATION 2 (44085715201)	LS	1.000
	0735- 88- 3	TOLL PLAZA MODIFY EXISTING, LOCATION 3 (44085715201)	LS	1.000
	0735- 88- 4	TOLL PLAZA MODIFY EXISTING, LOCATION 4 (44085715201)	LS	1.000
	0735- 88- 5	TOLL PLAZA MODIFY EXISTING, LOCATION 5 (44085715201)	LS	1.000
	0735- 88- 6	TOLL PLAZA MODIFY EXISTING, LOCATION 6 (44085715201)	LS	1.000
	0735- 88- 7	TOLL PLAZA MODIFY EXISTING, LOCATION 7 (44085715201)	LS	1.000
	0735- 88- 8	TOLL PLAZA MODIFY EXISTING, LOCATION 8 (44085715201)	LS	1.000

Call Order: 001 Proposal: E8S51

ALT	Item	Description	Unit	Quantity
	0735- 88- 9	TOLL PLAZA MODIFY EXISTING, LOCATION 9 (44085715201)	LS	1.000
	0735- 88- 10	TOLL PLAZA MODIFY EXISTING, LOCATION 10 (44085715201)	LS	1.000
	0735- 88- 11	TOLL PLAZA MODIFY EXISTING, LOCATION 11 (44085715201)	LS	1.000
	0735- 88- 12	TOLL PLAZA MODIFY EXISTING, LOCATION 12 (44085715201)	LS	1.000
	0735- 88- 13	TOLL PLAZA MODIFY EXISTING, LOCATION 13 (44085715201)	LS	1.000
	0751- 2-100	ARCHITECTURAL - ELECTRICAL/POWER, TOLL SITE LOCATION, PROJECT 440857-1-52-01 (44085715201)	LS	1.000
	0751- 11- 25	ARCHITECTURAL- SPECIAL, SCREEN WALL, PROJECT 440857-1-52-01	SF	294.000
	1050- 16-002	UTILITY PIPE,REMOVE & DISPOSE, 2-4.9"	LF	5,780.000
	1050- 16-003	UTILITY PIPE,REMOVE & DISPOSE, 5-7.9"	LF	772.000
	1050- 16-004	UTILITY PIPE,REMOVE & DISPOSE, 8-19.9"	LF	99.000
	1050- 18-002	UTILITY PIPE,PLUG & PLACE OUT OF SERVICE, 2- 4.9"	LF	2,650.000
	1050- 18-003	UTILITY PIPE,PLUG & PLACE OUT OF SERVICE, 5- 7.9"	LF	1,710.000
	1050- 18-004	UTILITY PIPE,PLUG & PLACE OUT OF SERVICE, 8-19.9"	LF	1,361.000
	1501- 1-	LIFT STATION, SANITARY SEWER	EA	12.000
	1720-900-	TRANSFORMER, REMOVE	EA	1.000
Section 0006 Intelligent Transportation System				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	1,208.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	6,316.000
	0633- 1-122	FIBER OPTIC CABLE, F&I, UNDERGROUND,13-48 FIBERS	LF	9,315.000
	0633- 1-123	FIBER OPTIC CABLE, F&I, UNDERGROUND,49-96 FIBERS	LF	12,735.000
	0633- 1-420	FIBER OPTIC CABLE, RELOCATE, UNDERGROUND	LF	100.000
	0633- 1-620	FIBER OPTIC CABLE, REMOVE, UNDERGROUND	LF	19,268.000
	0633- 2- 31	FIBER OPTIC CONNECTION, INSTALL, SPLICE	EA	944.000
	0633- 3- 12	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE TRAY	EA	71.000
	0633- 3- 13	FIBER OPTIC CONNECTION HARDWARE, F&I, PRETERMINATED CONNECTOR ASSEMBLY	EA	432.000
	0633- 3- 16	FIBER OPTIC CONNECTION HARDWARE, F&I, PATCH PANEL- FIELD TERMINATED	EA	7.000
	0633- 3- 17	FIBER OPTIC CONNECTION HARDWARE, F&I, CONNECTOR PANEL	EA	34.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	4.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	12.000