Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 08200609 Call Order: 004 Proposal: E8S59-R0 District:08

Counties: LAKE, ORANGE, OSCEOLA, SEMINOLE, SUMTER, TURNPIKE

Road Name: BRIDGE DECK STRIPING - ZONE 3

Limits: Midpoint

Project(s): 44734827201(*) Federal Aid No: N/A

Total Roadway Length:	0.000 Miles	Contract Days:	365
Total Bridge Length:	0.000 Miles	Letting Date:	06/09/20
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	14

Proposal Budget Estimate: $500,000.00

Please read the full advertisement

Description:

The work specified in this contract consists of providing all labor, materials, equipment and incidentals necessary to remove existing pavement markings and install permanent tape markings on concrete bridge decks at various locations on the Southern Connector Extension (SR 417), Milepost (MP) 0.0 to 5.5, Seminole Expressway (SR 417), MP 38.0 to 55.0, Florida's Turnpike (SR91), MP 200.0 to 309.0.

Prior to beginning work under this Contract, the Contractor shall submit to the Engineer for approval, two copies of the Contractor's proposed plan and methods for performing the work, including a listing of equipment and personnel anticipated for use.

The Contractor shall perform all work during day hours in accordance with the Turnpike Lane Closure Policy.

The quantities shown on the Bid Price Proposal are approximate and only represent estimated planned requirements based on historical or specific needs.

Use products listed on the Department's Approved Product List (APL).

No U-turns shall be permitted as a condition of this Contract, except at Service Plazas.

NO PRE-BID CONFERENCE WILL BE HELD FOR THIS PROJECT.

CONTRACTOR EXPERIENCE DOCUMENTATION: Expertise and Experience is required in the performance of Pavement Markings. The Experience in Pavement Markings form (850-070-06) must be filled out and submitted with the bid to be reviewed by the Department. If a Contractor is presently prequalified with the Department in pavement marking, it is not necessary to submit the form.

Call Order: 004 Proposal: E8S59-R0

ALT	Item	Description	Unit	Quantity
Section 0001 PAVEMENT STRIPING (LARGE MACHINE) (LM)				
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	260.000
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	51,000.000
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	4.300
	0713-103-131	PERMANENT TAPE, WHITE, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	7.000
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	4.300
	0713-103-331	PERMANENT TAPE, BLACK, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	7.000