

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 08200310 Call Order: 007 Proposal: E8S09 District:08

Counties: HILLSBOROUGH

Road Name: VETERANS EXPRESSWAY DRAINAGE FACILITY

Limits: 10470000

Project(s): 44263125201(*) Federal Aid No: N/A

Project(s): 44263135201 Federal Aid No: N/A

Total Roadway Length:	2.000 Miles	Contract Days:	280
Total Bridge Length:	0.000 Miles	Letting Date:	03/10/20
Total Proposal Length:	2.000 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	30

Proposal Budget Estimate: \$1,631,929.00

Please read the full advertisement

Description:

Work consists of providing all labor, materials, equipment and incidentals necessary for Drainage Facility Improvements, Drainage Improvements, Drainage Repairs, Guardrail Installation, Signing & Pavement Markings, Lighting Improvements, and other incidental construction on SR 589 (Veterans Expressway) in Hillsborough County from Milepost 7.226 to Milepost 8.218 and from Milepost 10.823 to Milepost 14.204. No Pre-Bid Conference. Contractor must be prequalified.

The summary of pay items for this project is listed in the Plans.

Call Order: 007 Proposal: E8S09

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44263125201)	LS	1.000
	0101- 1-	MOBILIZATION (44263135201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44263125201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44263135201)	LS	1.000
	0102- 2- 1	SPECIAL DETOUR 1 (44263135201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	3,871.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	228.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	902.000
	0102- 71- 16	TEMPORARY BARRIER, F&I, FREE STANDING	LF	373.000
	0102- 71- 26	TEMPORARY BARRIER, RELOCATE, FREE STANDING	LF	3,357.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	7,245.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	75.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	3.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	112.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	150.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	150.000
	0102-913- 21	REMOVABLE TAPE, WHITE, SOLID 6"	GM	0.154
	0102-913- 31	REMOVABLE TAPE, YELLOW, SOLID, 6"	GM	0.034
	0104- 10- 3	SEDIMENT BARRIER	LF	5,398.000
	0107- 1-	LITTER REMOVAL	AC	148.400
	0107- 2-	MOWING	AC	120.680

Call Order: 007 Proposal: E8S09

ALT	Item	Description	Unit	Quantity
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (44263125201)	LS	1.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (44263125201)	LS	1.000
	0108- 3-	MONITOR EXISTING STRUCTURES- GROUNDWATER MONITORING (44263125201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (44263125201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (44263135201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	107.000
	0120- 1-	REGULAR EXCAVATION	CY	20.700
	0120- 6-	EMBANKMENT	CY	13.000
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	1.300
	0400- 1- 2	CONCRETE CLASS I, ENDWALLS	CY	0.800
	0400- 2- 8	CONCRETE CLASS II, BULKHEAD	CY	83.500
	0415- 1- 8	REINFORCING STEEL- BULKHEAD	LB	6,073.000
	0425- 1-521	INLETS, DT BOT, TYPE C,<10'	EA	1.000
	0425- 1-701	INLETS, GUTTER, TYPE S, <10'	EA	1.000
	0430-173-118	PIPE CULVERT OPTIONAL MATERIAL, ROUND, 18", GUTTER DRAIN	LF	40.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	13.000
	0430-611-325	U-ENDWALL WITH BAFFLES, INDEX 261/430-011, 1:2 SLOPE, 18"PIPE	EA	1.000
	0440- 1- 50	UNDERDRAIN, TYPE V	LF	7,269.000
	0440- 73- 3	UNDERDRAIN OUTLET PIPE, 8"	LF	212.000
	0455-133- 2	SHEET PILING STEEL, TEMPORARY-CRITICAL	SF	22,580.000
	0520- 6-	SHOULDER GUTTER- CONCRETE	LF	10.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	38.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	38.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	28,448.000
	0571- 1- 12	PLASTIC EROSION MAT, TRM, TYPE 2	SY	160.000
	0706- 1- 1	RAISED PAVEMENT MARKER, TYPE B WITHOUT FINAL SURFACE MARKINGS	EA	208.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44263135201)	LS	1.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	173.000
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	0.044
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.075
	0999- 16-	PARTNERING, DO NOT BID (44263125201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44263125201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44263135201)	LS	1.000
Section 0002 Lighting				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	559.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	2,515.000
	0630- 2- 14	CONDUIT, FURNISH & INSTALL, ABOVEGROUND	LF	5.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	13.000
	0715- 1- 11	LIGHTING CONDUCTORS, F&I, INSULATED, NO. 10 OR <	LF	3,184.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	14,361.000
	0715- 1- 13	LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2	LF	1,080.000

Call Order: 007 Proposal: E8S09

ALT	Item	Description	Unit	Quantity
	0715- 1- 14	LIGHTING CONDUCTORS, F&I, INSULATED, NO 1 TO NO 0	LF	3,885.000
	0715- 1- 15	LIGHTING CONDUCTORS, F&I, NO.1/0 - 3/0 (0 to 000)	LF	112.000
	0715- 1- 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	LF	22,622.000
	0715- 4- 23	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE SPECIAL FOUNDATION, 40' MOUNTING HEIGHT	EA	12.000
	0715- 4- 70	LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION	EA	12.000
	0715- 7- 31	LOAD CENTER, RELOCATE, SECONDARY VOLTAGE	EA	1.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	12.000