

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	08200512	Call Order: 001	Proposal: E8S23	District:08
Counties:	SUMTER			
Road Name:	PAVEMENT MARKING - MP 309			
Limits:	18470000			
Project(s):	40611035201(*)	Federal Aid No: N/A		
Total Roadway Length:	0.270 Miles	Contract Days:	45	
Total Bridge Length:	0.000 Miles	Letting Date:	05/12/20	
Total Proposal Length:	0.270 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	14	
Proposal Budget Estimate:	\$160,000.00			

Please read the full advertisement

Description:

The work specified in this contract consists of providing all labor, materials, equipment and incidentals necessary to provide thermoplastic pavement markings at various locations on the I-75 at Florida's Turnpike – Wildwood Interchange Modification (MP 309).

Prior to beginning work under this Contract, the Contractor shall submit to the Engineer for approval, two copies of the Contractor's proposed plan and methods for performing the work, including a listing of equipment and personnel anticipated for use.

No U-turns shall be permitted as a condition of this Contract, except at Service Plazas.

The Contractor shall perform all work night hours in accordance with the Turnpike Lane Closure Policy.

All lane closures shall be during the hours of 9:00 P.M to 5:00 A.M. and in one direction for one lane only.

NO PRE-BID CONFERENCE WILL BE HELD FOR THIS PROJECT.

CONTRACTOR EXPERIENCE DOCUMENTATION: Expertise and Experience is required in the performance of Pavement Markings. The Experience in Pavement Markings form (850-070-06) must be filled out and submitted with the bid to be reviewed by the Department. If a Contractor is presently prequalified with the Department in pavement marking, it is not necessary to submit the form.

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Call Order: 001 Proposal: E8S23

ALT	Item	Description	Unit	Quantity
Section 0001 MAINTENANCE SUPPORT SERVICES (MH)				
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	120.000
	0711- 11-103	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR INTERCHANGE MARKINGS	GM	1.500
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	725.000
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	8.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	13.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	60.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	9.150
	0711- 15-102	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SOLID, 8"	GM	0.160
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	16.450
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	9.160
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.200
	0713-103-103	PERMANENT TAPE, WHITE, SOLID LANE DROP MARKING, 12" FOR CONCRETE BRIDGES	GM	0.125
	0713-103-131	PERMANENT TAPE, WHITE, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	0.225
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.275
	0713-103-331	PERMANENT TAPE, BLACK, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	0.120
	E706- 1- 42	REFLECTIVE PAVEMENT MARKER(REMOVE AND REPLACE)(CLASS B)	EA	100.000