

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	08200512	Call Order: 006	Proposal: E8S33	District:08
Counties:	TURNPIKE			
Road Name:	REPLACE GREAT SYSTEM AND HEXFOAM CRASH CUSHIONS TURNPIKEWIDE			
Limits:	10470000			
Project(s):	44261815201(*)	Federal Aid No: N/A		
Project(s):	44261815202	Federal Aid No: N/A		
Total Roadway Length:	249.940 Miles	Contract Days:	231	
Total Bridge Length:	0.000 Miles	Letting Date:	05/12/20	
Total Proposal Length:	249.940 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	30	

Proposal Budget Estimate: \$1,294,612.00

Please read the full advertisement

Description:

Work consists of providing all labor, materials, equipment and incidentals necessary for crash cushion replacement, crash cushion removal, milling and resurfacing with overbuild, cross slope correction, median barrier wall construction, and other incidental construction. The improvements will take place on various locations including:

- 1) SR-91 mile marker 66.7, 68.0, 69.7, 70.5, 73.8, 74.6, 75.2, 77.2, 80.2, 112.4, 113.4, 114.3, 115.3, 116.2, and 117.2.
- 2) SR 589 NB entrance ramp at MP 0.864.
- 3) West Linebaugh Avenue at MP 5.668.
- 4) Hutchison Road at MP 10.652
- 5) SR 417 at MP 0.053
- 6) US Highway 27 at MP 0.295

No Pre-Bid Conference. Contractor must be prequalified.

The summary of pay items for this project is listed in the Plans.

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Call Order: 006 Proposal: E8S33

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44261815201)	LS	1.000
	0101- 1-	MOBILIZATION (44261815202)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44261815201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44261815202)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	4,572.000
	0102- 62-	BARRIER MOUNTED WORK ZONE SIGN- INDEX 11871/700-013	ED	2,070.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	111.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	2,240.000
	0102- 71- 23	TEMPORARY BARRIER, RELOCATE, LOW PROFILE CONCRETE	LF	66.000
	0102- 71- 25	TEMPORARY BARRIER, RELOCATE, ANCHORED	LF	6,809.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	20,376.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	462.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	39.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	518.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	414.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	414.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	4.000
	0107- 1-	LITTER REMOVAL	AC	5.730
	0107- 2-	MOWING	AC	0.500
	0110- 1- 1	CLEARING & GRUBBING (44261815201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (44261815202)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	293.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	4.000
	0327- 70- 1	MILLING EXIST ASPH PAVT, 1" AVG DEPTH	SY	2,813.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	249.000
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	5.400
	0521- 1-105	MEDIAN CONCRETE BARRIER, 32" F-SHAPE, PROJECT 442618-1-52-01	LF	1,488.000
	0544- 2- 2	CRASH CUSHION, TL-2, WIDE	EA	1.000
	0544- 3- 1	CRASH CUSHION, TL-3, NARROW	EA	13.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	290.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	13.000
	0706- 1- 1	RAISED PAVEMENT MARKER, TYPE B WITHOUT FINAL SURFACE MARKINGS	EA	48.000
	0999- 16-	PARTNERING, DO NOT BID (44261815201)	LS	1.000
	0999- 16-	PARTNERING, DO NOT BID (44261815202)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44261815201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44261815202)	LS	1.000