Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 08201110 Call Order: 007 Proposal: E8S80-R0 District:08

Counties: BROWARD, MIAMI-DADE, PALM BEACH, TURNPIKE

Road Name: PAVED SHOULDER REPAIR - ZONE 1

Limits: Midpoint

Project(s): 44777317201(*) Federal Aid No: N/A

Total Roadway Length:	0.000 Miles	Contract Days:	365
Total Bridge Length:	0.000 Miles	Letting Date:	11/10/20
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	14

Proposal Budget Estimate: $500,000.00

Please read the full advertisement

Description:

The work specified in this contract consists of providing all labor, materials, equipment and incidentals necessary to repair and/or restore paved shoulders at various locations on the Homestead Extension of Florida's Turnpike, Milepost (MP) 0.0 to 46.5, Florida's Turnpike, MP 0.0X to 100.0, and Sawgrass Expressway, MP 0.0 to 22.5.

Prior to beginning work under this Contract, the Contractor shall submit to the Engineer for approval, two copies of the Contractor's proposed plan and methods for performing the work, including a listing of equipment and personnel anticipated for use.

The Contractor shall perform all work during day and night hours in accordance with the Turnpike Lane Closure Policy.

No U-turns shall be permitted as a condition of this Contract, except at Service Plazas.

Night work shall be performed between the hours of 9:00 PM to 5:00 AM, Monday through Thursday.

Mobilization item shall be full compensation for mobilization/demobilization per Location, for a routine response authorized by a work order. A Location is defined as item/items of work authorized by a single work order for work to be accomplished within a two (2)-mile length of highway.

NO PRE-BID CONFERENCE WILL BE HELD FOR THIS PROJECT.

CONTRACTOR EXPERIENCE DOCUMENTATION: Expertise and Experience is required in the performance of Asphalt Paving. The Experience in Asphalt Paving Form (850-070-01) must be filled out and submitted with the bid to be reviewed by the Department. If a Contractor is presently prequalified with the Department in asphalt paving, it is not necessary to submit the form.

Call Order: 007 Proposal: E8S80-R0

ALT	Item	Description	Unit	Quantity
Section 0001 MISCELLANEOUS ROUTINE MAINTENANCE (MH)				
	0120- 6-	EMBANKMENT	CY	200.000
	0327- 70- 5	MILLING EXIST ASPH PAVT, 2" AVG DEPTH	SY	7,800.000
	0337- 7- 81	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC B, FC-12.5, PG 76-22	TN	875.000
	E101- 1- 1	MOBILIZATION	LO	20.000
	E102- 1- 2	MAINTENANCE OF TRAFFIC (SITE SPECIFIC CONTRACTS)	DA	45.000
	E575- 1-	SODDING	SY	500.000
	E577- 70-	SHOULDER REWORK	SY	7,800.000